

HTE# 15-536121

## Harris County Department of Public Health

28329

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 275 Ray RdISSUED TO: KEITH ELLIOTT

SUBDIVISION \_\_\_\_\_

LOT # \_\_\_\_\_

NEW ☒REPAIR ☐EXPANSION ☐

Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_

Type of Structure: MAN HOME (16'x80')Proposed Wastewater System Type: 25% REDUCTION SYSTEMProjected Daily Flow: 360 GPDNumber of bedrooms: 3 Number of Occupants: 6 maxBasement ☐ Yes ☒ NoPump Required: ☐ Yes ☒ No ☐ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100 feetPermit valid for: ☒ Five yearsPermit conditions: \_\_\_\_\_ ☐ No expiration

Authorized State Agent: \_\_\_\_\_

Date: 5/27/15

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: KEITH ELLIOTTPROPERTY LOCATION: 275 Ray Rd

SUBDIVISION \_\_\_\_\_

LOT # \_\_\_\_\_

Facility Type: MAN HOME (16'x80') ☒ New☐ Expansion☐ RepairBasement? ☐ Yes ☐ NoBasement Fixtures? ☐ Yes ☐ NoType of Wastewater System\*\* 25% REDUCTION SYSTEM(Initial) Wastewater Flow: 360 GPD(See note below, if applicable ☐)25% REDUCTION (Repair)

## Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size \_\_\_\_\_ gallons

Number of trenches 2Exact length of each trench 75 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 24-36 inches

(Trench bottoms shall be level to +/-1/4"

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 12-24 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

\_\_\_\_\_ inches below pipe

Aggregate Depth: \_\_\_\_\_ inches above pipe

Conditions: \_\_\_\_\_ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_

Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: \_\_\_\_\_

Construction Authorization Expiration Date: 5/27/20

HTE# 15-5-36121

Permit # 28329

# Harnett County Department of Public Health Site Sketch

ISSUED TO: KEITH ELLIOTT PROPERTY LOCATOR: 275 RAY RD  
SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_  
Authorized State Agent: ~~OLIVER TOWSON~~ Date: 5/27/15

