

HTE# 16-5-38168

Harnett County Department of Public Health

28726

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Audrey Sue Underwood PROPERTY LOCATION: 136 Quail Acres Ln.
 NEW REPAIR sm EXPANSION SUBDIVISION: Quail Acres LOT # 1
 Type of Structure: Existing 20x80 MH Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: Conventional
 Projected Daily Flow: 480 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 50 feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: Bryan McJannet, PEHS Date: 3/15/2016 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Audrey Sue Underwood PROPERTY LOCATION: 136 Quail Acres Ln.
 Facility Type: MH New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Conventional (Initial) Wastewater Flow: 480 GPD
 (See note below, if applicable
25% Reduction System (Repair)

Installation Requirements/Conditions

Septic Tank Size Existing gallons
 Pump Tank Size _____ gallons
 Number of trenches 1
 Exact length of each trench 100 feet
 Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18 inches
 (Trench bottoms shall be level to +1-1/4" in all directions)
 Soil Cover: 6 inches
 (Maximum soil cover shall not exceed 36" above the trench bottom)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total
 Conditions: Connect new drain line to existing D-Box
run drain line on contour

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McJannet, PEHS Date: 3/15/2016
 Construction Authorization Expiration Date: 3/15/2021

HTE# 16-5-38168

Permit # 28726

Harnett County Department of Public Health Site Sketch

ISSUED TO: Audrey Sue Underwood PROPERTY LOCATOR: 136 Quail Acres Ln.
SUBDIVISION Quail Acres LOT # 1

Authorized State Agent: Gregory McSwain, PEH Date: 3/15/2016

