

**D. ALLEN HUGHES
ENGINEERING, Inc.**

1689 Jimmie Kerr Rd., Haw River, NC 27258
338-578-8634, Firm No. C-2951

January 10, 2018

Rubi Smith
833 Docs Rd.
Lillington, NC 27546

Reference: Evaluation of Interior Wall Changes, Rubi Smith Residence
833 Docs Rd., Lillington, NC 27546
Harnett County Permit No. 16-50038246
Project No. D17ms01


Dear Mrs. Smith:

Thank you for using D. Allen Hughes Engineering for your engineering needs. As requested, the site was visited on January 6, 2018 to evaluate the structural stability of the pier and anchoring system for the above referenced mobile home.

Upon arrival, the approximate 48-ft by 28-ft mobile home had been set up. A fireplace and an interior nonbearing wall oriented perpendicular to the marriage line near the fireplace had been removed. A wall constructed of 2x4 studs at 16 in. on center was built along part of the marriage line near the original fireplace location.

Based on measuring and observation, it is my professional opinion that the wall framing changes to the doublewide mobile home at 833 Docs Rd., Lillington, NC 27546 (Harnett County Permit No. 16-50038246) are structurally sound. Specifically, the removal of the nonbearing wall and addition of a wall along the marriage line have no detrimental effect on the structural integrity of the home. Thank you for using D. Allen Hughes Engineering for your evaluation. If you should have any questions pertaining to this report, please call me.

Sincerely,



D. Allen Hughes, P.E., President
D. Allen Hughes Engineering, Inc.