

HTE# 16-539550

Harr County Department of Public Health

29005

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: KELLY PAINTER PROPERTY LOCATION: TITAN ROBERTS RD  
NEW ☒ REPAIR ☐ EXPANSION ☐ SUBDIVISION: JAMES McLAMB LOT # 1  
Type of Structure: MAN HOME (28x60) Site Improvements required prior to Construction Authorization Issuance:  
Proposed Wastewater System Type: CONVENTIONAL  
Projected Daily Flow: 360 GPD  
Number of bedrooms: 3 Number of Occupants: 6 max  
Basement ☐ Yes ☒ No  
Pump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilities  
Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100 feet Permit valid for: ☒ Five years  
Permit conditions: ☐ No expiration

Authorized State Agent: [Signature] Date: 8/29/16 SEE ATTACHED SITE SKETCH  
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: KELLY PAINTER PROPERTY LOCATION: TITAN ROBERTS RD  
FACILITY TYPE: MAN HOME (28x60) SUBDIVISION: JAMES McLAMB LOT # 1  
Basement? ☐ Yes ☒ No Expansion ☐ Repair ☐  
Type of Wastewater System\*\* CONVENTIONAL (Initial) Wastewater Flow: 360 GPD  
(See note below, if applicable ☐ PUMP TO CONVENTIONAL (Repair)

Installation Requirements/Conditions  
Septic Tank Size 1000 gallons Number of trenches 2  
Pump Tank Size \_\_\_\_\_ gallons Exact length of each trench 100 feet  
Trench Spacing: 9 Feet on Center  
Trenches shall be installed on contour at a Soil Cover: 24-30 inches  
Maximum Trench Depth of: 36-42 inches (Maximum soil cover shall not exceed 36" above the trench bottom)  
(Trench bottoms shall be level to +/- 1/4" in all directions)  
Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM Aggregate Depth: \_\_\_\_\_ inches below pipe  
Conditions: CONTRACTOR TO CALL PRIOR TO INSTALLATION \_\_\_\_\_ inches above pipe  
\_\_\_\_\_ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_  
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 8/29/16  
Construction Authorization Expiration Date: 8/29/21

HTE# 16-5-39550

Permit # 29005

# Harnett County Department of Public Health Site Sketch

ISSUED TO: KELLY PAINTER PROPERTY LOCATION: TITAN ROBERTS RD  
SUBDIVISION JAMES McLane LOT # 1  
Authorized State Agent: ~~OLIVER TOLKSDORF~~ Date: 8/29/14

\* SET TANK AS HIGH AS POSSIBLE  
TO GET FALL INTO DRAINLINES

↑  
TO TITAN  
ROBERTS RD

