

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: SPIEGEL, BARRY & LINDA
PROPERTY LOCATION: NC27N (HARVELL LN)
SUBDIVISION: WHITETAIL BUCK
LOT # 4
Type of Structure: Man Home (32x64)
Proposed Wastewater System Type: 25% REDUCTION SYSTEM
Projected Daily Flow: 360 GPD
Number of bedrooms: 3
Number of Occupants: 6 max
Basement: No
Pump Required: No
Type of Water Supply: Public
Permit valid for: Five years

Authorized State Agent: [Signature] REAS Date: 10/25/17 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: SPIEGEL, BARRY & LINDA
PROPERTY LOCATION: NC27N (HARVELL LN)
SUBDIVISION: WHITETAIL BUCK
LOT # 4
Facility Type: Man Home (32x64)
Basement? No
Type of Wastewater System: 25% REDUCTION SYSTEM
(Initial) Wastewater Flow: 360 GPD
25% REDUCTION SYS. (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons
Pump Tank Size
Number of trenches 4
Exact length of each trench 60 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth of: 18 inches
Pump Requirements: ft. TDH vs. GPM
Aggregate Depth: inches below pipe, inches above pipe, inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] REAS Date: 10/25/17
Construction Authorization Expiration Date: 10/25/17

HTE# 17-5-42526

Permit # 29734

Harnett County Department of Public Health Site Sketch

ISSUED TO: SPIEGEL, BARRY & LINDA PROPERTY LOCATOR: N 027 N (HARVELL LN)
SUBDIVISION WHITESAIL BUCK LOT # 4

Authorized State Agent: ~~REAS (OLIVER TOLKSOOP)~~ Date: 10/25/17

- * DO NOT REMOVE ANY SOIL WHEN CLEARING.
- * HAND CLEARING RECOMMENDED
- * CALL WITH ANY QUESTIONS PRIOR TO INSTALLATION

