

IMPROVEMENT PERMIT

03-5-6397

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) Qual Run Homes

New Installation

Septic Tank

Property Location: SR# 1230 Harrington Pl

Repairs

Nitrification Line

Subdivision

Lot # 4

Tax ID #

Quadrant #

Number of Bedrooms Proposed: 3 (28x56)

Lot Size: 1.00ac plus septic easement

Basement with Plumbing:

Garage:

1.58ac TOTAL

Water Supply: Well Public

Community

Meet onsite before installing septic system final layout may change

Distance From Well: 50 ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: Conventional

Other

Size of tank: Septic Tank: 1000 gallons

Pump Tank: gallons

Subsurface Drainage Field No. of ditches 4 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: Linear feet


Date: 02-28-03

This permit is subject to revocation if site plans or intended use change.

Signed: Jr Worel

Environmental Health Specialist

Meet onsite for final layout maintain all setbacks keep system within area marked by blue flags



SR 1230

HARNETT COUNTY HEALTH DEPARTMENT
AUTHORIZATION TO CONSTRUCT

Authorization is hereby given to construct a wastewater system to the specifications described by Harnett County Health Department, Improvement Permit # 19256. This authorization shall be valid for a period not to exceed five (5) years from the date of issuance. This authorization will be invalid if ownership, site plans, or intended use change.

Name Qual Run Homes Telephone# 775-7044

Address _____

Property Location SR# 1230 Road Name _____

Subdivision _____ Lot # 4 # Bedrooms Proposed 3 (28x56) Lot Size 1.00 ac plus .58 ac Septic Easement 1.58 ac Total

TYPE OF SYSTEM

New Installation Repair Septic Tank Nitrification Lines

Conventional Other _____

Basement With Plumbing Without Plumbing

Water Supply: Well Public Water Supply Minimum Well Setback: 50 Ft.

Septic Tank 1000 gal Pump Chamber _____ gal

NITRIFICATION FIELD SPECIFICATIONS

Number of fields 1 # of lines per field 4 Length of lines 100 Ft.

Width of ditches 3 ft. Depth of ditches 18 inches

French Drain: Linear feet required _____ Depth of gravel _____

No wastewater system shall be covered or placed into use by any person until an inspection by the Harnett County Health Department has determined that the system has been installed according to the conditions of the Improvement Permit and that a valid Operations Permit has been issued.

Signature of Authorized Agent for Harnett County of Harnett Joe W. R. 11 Date 02-28-03