

HTE 03-5-6977L

OPERATIONS PERMIT

Name: (owner) Katherine & Christopher Thompson

New Installation Septic Tank

Property Location: SR# Carter Lane

Repairs Nitrification Line

Subdivision Beagle Run Pk II

Lot # 8

Tax ID # _____

Quadrant # _____

Contractor: Larry Sharp

Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Chamber System

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field: No. of ditches 2 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: _____ Linear feet

Date: 5/17/2004

Inspected by: [Signature]
Environmental Health Specialist

PERMIT NO. 17547

