

HTE 03-5-8334

# OPERATIONS PERMIT

Name: (owner) JOHNSON, RANDALL & SHERMAN  New Installation  Septic Tank  
 Property Location: SR# 1505 PEARCE RD  Repairs  Nitrification Line  
 Subdivision \_\_\_\_\_ Lot # \_\_\_\_\_  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: SELF INSTALLED Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface	No. of	exact length	width of	depth of
Drainage Field	ditches <u>1</u>	of each ditch <u>200</u> ft.	ditches <u>3</u> ft.	ditches <u>8</u> in.

French Drain Required: 300 Linear feet

Date: 6/1/04  
 Inspected by: [Signature] ES  
 Environmental Health Specialist

PERMIT NO. 20715

