

HTE# 08-500-21120

Hamilton County Department of Public Health

25095

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Tim Marks II
NEW [X] REPAIR [ ] EXPANSION [ ]
Type of Structure: MH - 32x76 - 3 BR
Proposed Wastewater System Type: GRAVEL
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [ ] Yes [X] No

PROPERTY LOCATION: Pace Lane - off Buchanan Rd
SUBDIVISION: LOT #

Site Improvements required prior to Construction Authorization Issuance: 11.1 AC

Pump Required: [ ] Yes [X] No
Type of Water Supply: [ ] Community [X] Public [ ] Well Distance from well 100 feet
Permit valid for: [X] Five years [ ] No expiration
Permit conditions: Met on site for final layout - maintain all setbacks
Stub out plumbing shallows, at ground level or higher where shown

Authorized State Agent: Joe WARS Date: 10.28.08 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Tim Marks II

PROPERTY LOCATION: Pace Lane - off Buchanan Rd
SUBDIVISION: LOT #

Facility Type: MH-32x76-3BR [X] New [ ] Expansion [ ] Repair
Basement? [ ] Yes [X] No Basement Fixtures? [ ] Yes [X] No

Type of Wastewater System\*\* GRAVEL (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable) [X] Pump: 25% Reduction Sys (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons Exact length of each trench 300 feet Trench Spacing: 7 Feet on Center
Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
(Trench bottoms shall be level to +/- 1/4" in all directions)

Pump Requirements: ft. TDH vs. GPM
Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Joe WARS Date: 10.28.08
Construction Authorization Expiration Date: 10.28.2013

HTE# 08-500-~~3~~21120

Permit # 25095

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Tim Marks II      AUTHORIZED STATE AGENT: Jan Waters

PROPERTY LOCATION: Pace Lane off of Buchanan      LOT # 11.1AC

SUBDIVISION \_\_\_\_\_      Date: 10.28.08

1310

