

HTE# 18-54384

Harnett County Department of Public Health

29838

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: CLYDE STANLEY FAIRCLOTH PROPERTY LOCATION: COOL SPRINGS RD
NEW ☒ REPAIR ☐ EXPANSION ☐ SUBDIVISION _____ LOT # _____
Type of Structure: MAN. HOME (52x28) Site Improvements required prior to Construction Authorization Issuance: _____
Proposed Wastewater System Type: 25% REDUCTION SYSTEM
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement ☐ Yes ☒ No
Pump Required: ☐ Yes ☒ No ☐ May be required based on final location and elevations of facilities
Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well _____ feet Permit valid for: ☒ Five years
Permit conditions: _____ ☐ No expiration

Authorized State Agent: [Signature] Date: 2/12/18 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CLYDE STANLEY FAIRCLOTH PROPERTY LOCATION: COOL SPRINGS RD
FACILITY TYPE: MAN HOME (52x28) ☒ New ☐ Expansion ☐ Repair
Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☐ No
Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable ☐ 25% RED. SYS. (Repair)

Installation Requirements/ConditionsSeptic Tank Size 1000 gallons

Pump Tank Size _____ gallons

Number of trenches 1Exact length of each trench 450 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 18 inches

(Trench bottoms shall be level to +/-1/4"

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 6 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

_____ inches below pipe

Aggregate Depth: _____ inches above pipe

Conditions: HOUSE #2

_____ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 2/12/18Construction Authorization Expiration Date: 2/12/23

HTE# 18-5-43184

Permit # 29838

Harnett County Department of Public Health Site Sketch

ISSUED TO: Clyde Stanley Farcloth PROPERTY LOCATOR: COOL SPRINGS RD SUBDIVISION _____ LOT # _____

Authorized State Agent: ~~Old Oliver Tolson~~ Date: 2/12/18

