ENGINEERING BY
TRENCO
A MiTek Affiliate

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: B0318-0840
Freelance A

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Comtech, Inc - Fayetteville.

Pages or sheets covered by this seal: E11513721 thru E11513738

My license renewal date for the state of North Carolina is December 31, 2018.

North Carolina COA: C-0844

March 5,2018

Lassiter, Frank

IMPORTANT NOTE: Truss Engineer's responsibility is solely for design of individual trusses based upon design parameters shown on referenced truss drawings. Parameters have not been verified as appropriate for any use. Any location identification specified is for file reference only and has not been used in preparing design. Suitability of truss designs for any particular building is the responsibility of the building designer, not the Truss Engineer, per ANSI/TPI-1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	A1	COMMON SUPPORTED GAB	1	1	E11513721
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:24 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-vo5W8ns3wtky98howcP9S0zpn1E?nuoQ3B72t8ze14n

-0-10-8 18-0-0 36-0-0
0-10-8 18-0-0 18-0-0

Scale = 1:62.5



Plate Offsets (X,Y)-- [29:0-4-0,0-4-8], [33:0-4-0,0-4-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.09	Vert(LL)	-0.00	1	n/r	120	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(TL)	-0.00	1	n/r	120		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.16	Horz(TL)	0.01	22	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S							Weight: 262 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x6 SP No.1
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS T-Brace: 2x4 SPF No.2 - 12-31
Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c.,with 3in minimum end distance.
Brace must cover 90% of web length.

REACTIONS. All bearings 36-0-0.
(lb) - Max Horz 2=178(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 2, 32, 34, 35, 36, 37, 38, 30, 28, 27, 26, 25, 24 except 33=-100(LC 6), 39=-107(LC 6), 29=-101(LC 7), 23=-126(LC 7)
Max Grav All reactions 250 lb or less at joint(s) 2, 31, 32, 33, 34, 35, 36, 37, 38, 39, 30, 29, 28, 27, 26, 25, 24, 23, 22

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-281/27, 10-11=-43/337, 11-12=-46/442, 12-13=-46/442, 13-14=-43/337, 21-22=-277/22
BOT CHORD 2-39=0/285, 38-39=0/285, 37-38=0/285, 36-37=0/285, 35-36=0/285, 34-35=0/285, 33-34=0/285, 32-33=0/285, 31-32=0/285, 30-31=0/285, 29-30=0/285, 28-29=0/285, 27-28=0/285, 26-27=0/285, 25-26=0/285, 24-25=0/285, 23-24=0/285, 22-23=0/285
WEBS 21-23=-128/261

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) gable end zone and C-C Corner(3) -0-10-8 to 3-6-5, Exterior(2) 3-6-5 to 13-7-3, Corner(3) 13-7-3 to 18-0-0, Exterior(2) 22-4-13 to 31-7-3 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) All plates are 2x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 32, 34, 35, 36, 37, 38, 30, 28, 27, 26, 25, 24 except (jt=lb) 33=100, 39=107, 29=101, 23=126.
10) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.
11) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	A2	COMMON	4	1	E11513722
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:24 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-vo5W8ns3wtky98howcP9S0zk514mnnMQ3B72t8ze14n

-0-10-8	9-0-14	18-0-0	26-11-2	36-0-0
0-10-8	9-0-14	8-11-2	8-11-2	9-0-14

Scale = 1:65.2



12-0-9	23-11-7	36-0-0
12-0-9	11-10-13	12-0-9

Plate Offsets (X,Y)-- [2:0-3-4,0-2-0]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	-0.40	9-12	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.69	Vert(TL)	-0.58	9-12	>745	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.64	Horz(TL)	0.09	8	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S		Wind(LL)	0.08	8-9	>999	240	Weight: 228 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-11-12 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-2-1 oc bracing.

REACTIONS. (lb/size) 2=1723/0-3-8, 8=1669/Mechanical
Max Horz 2=148(LC 6)
Max Uplift 2=-265(LC 6), 8=-222(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3119/954, 3-5=-2811/948, 5-7=-2822/962, 7-8=-3111/971
BOT CHORD 2-12=-705/2682, 9-12=-325/1773, 8-9=-728/2703
WEBS 5-9=-285/1167, 7-9=-542/435, 5-12=-266/1150, 3-12=-524/413

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 13-7-3, Exterior(2) 13-7-3 to 18-0-0, Interior(1) 22-4-13 to 31-6-7 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=265, 8=222.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	A2-P	COMMON	4	1	E11513723
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:25 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-N?euL7thhBspmIG_UJwO_DVuaRLaWEcZIrsbPaze14m

-0-10-8	9-0-14	18-0-0	26-11-2	36-0-0
0-10-8	9-0-14	8-11-2	8-11-2	9-0-14

Scale = 1:69.6



12-0-9	22-0-0	23-11-7	36-0-0
12-0-9	9-11-7	1-11-7	12-0-9

Plate Offsets (X,Y)-- [2:0-3-4,0-2-0]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.40	Vert(LL)	-0.56	9-12	>761	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.91	Vert(TL)	-0.74	9-12	>583	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.64	Horz(TL)	0.10	8	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S		Wind(LL)	0.08	8-9	>999	240	Weight: 246 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.3 *Except*
10-11: 2x6 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-9-7 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-2-1 oc bracing.

REACTIONS. (lb/size) 2=1842/0-3-8, 8=1787/Mechanical
Max Horz 2=148(LC 6)
Max Uplift 2=-265(LC 6), 8=-222(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3403/954, 3-5=-3096/948, 5-7=-3108/962, 7-8=-3419/971
BOT CHORD 2-12=-705/2932, 9-12=-325/1946, 8-9=-728/2955
WEBS 5-9=-285/1318, 7-9=-534/435, 5-12=-266/1301, 3-12=-514/413

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 13-7-3, Exterior(2) 13-7-3 to 18-0-0, Interior(1) 22-4-13 to 31-6-7 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
5) Refer to girder(s) for truss to truss connections.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=265, 8=222.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	A3-P	COMMON	1	1	E11513724
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 — 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:26 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-rBCGYTuJSU_gOSrA21RdXR217rmXFeoiXVc8x0ze14I



LOADING (psf)		SPACING-	2-3-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.53	9-12	>807	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.60	Vert(TL)	-0.70	9-12	>608	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.70	Horz(TL)	0.09	8	n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-S		Wind(LL)	0.08	2-12	>999	240	Weight: 246 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except*
10-11: 2x6 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-6-2 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=2067/0-3-8, 8=2008/0-3-8
Max Horz 2=166(LC 6)
Max Uplift 2=-297(LC 6), 8=-249(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3817/1071, 3-5=-3472/1064, 5-7=-3474/1076, 7-8=-3820/1085
BOT CHORD 2-12=-789/3288, 9-12=-363/2180, 8-9=-810/3294
WEBS 5-9=-316/1466, 7-9=-584/484, 5-12=-299/1463, 3-12=-576/463

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 13-7-3, Exterior(2) 13-7-3 to 18-0-0, Interior(1) 22-4-13 to 31-5-7 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=297, 8=249.

March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A	E11513725
B0318-0840	A4-P	COMMON	1	1	Job Reference (optional)	

Comtech, Inc., Fayetteville, NC 28309 — 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:26 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-rBCGYTuJSU_gOSrA21RdXR21VrmYFfRiXVc8x0ze14I

-0-10-8	9-0-14	18-0-0	26-11-2	36-0-0	36-10-8
0-10-8	9-0-14	8-11-2	8-11-2	9-0-14	0-10-8

Scale = 1:69.8



12-0-9	23-11-7	36-0-0
12-0-9	11-10-13	12-0-9

LOADING (psf)		SPACING-	2-3-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.52	Vert(LL)	-0.53	10-13	>812	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.60	Vert(TL)	-0.70	10-13	>610	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.66	Horz(TL)	0.09	8	n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-S		Wind(LL)	0.08	8-10	>999	240	Weight: 248 lb	FT = 20%

LUMBER-

TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except*
11-12: 2x6 SP No.1

BRACING-

TOP CHORD Structural wood sheathing directly applied or 3-7-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=2067/0-3-8, 8=2067/0-3-8
Max Horz 2=161(LC 6)
Max Uplift 2=-297(LC 6), 8=-297(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-3815/1062, 3-5=-3470/1056, 5-7=-3470/1056, 7-8=-3815/1062
BOT CHORD 2-13=-757/3286, 10-13=-332/2179, 8-10=-757/3286
WEBS 5-10=-298/1463, 7-10=-576/462, 5-13=-298/1463, 3-13=-576/462

NOTES-

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 13-7-3, Exterior(2) 13-7-3 to 18-0-0, Interior(1) 22-4-13 to 32-3-13 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 30.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=297, 8=297.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	A5	COMMON	4	1	E11513726
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 — 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:27 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-JNmempuxDo6X0bQMckzs4ebFuF5V_7psl9LiUTze14k

-0-10-8	9-0-14	18-0-0	26-11-2	36-0-0	36-10-8
0-10-8	9-0-14	8-11-2	8-11-2	9-0-14	0-10-8

Scale = 1:66.3



12-0-9	23-11-7	36-0-0
12-0-9	11-10-13	12-0-9

Plate Offsets (X,Y)-- [2:0-3-4,0-2-0], [8:0-3-4,0-2-0]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.35	Vert(LL)	-0.40	10-13	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.69	Vert(TL)	-0.57	10-13	>747	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.59	Horz(TL)	0.09	8	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S		Wind(LL)	0.08	2-13	>999	240	Weight: 230 lb	FT = 20%

LUMBER-

TOP CHORD	2x6 SP No.1
BOT CHORD	2x6 SP No.1
WEBS	2x4 SP No.3

BRACING-

TOP CHORD	Structural wood sheathing directly applied or 4-0-14 oc purlins.
BOT CHORD	Rigid ceiling directly applied or 9-6-2 oc bracing.

REACTIONS. (lb/size) 2=1718/0-3-8, 8=1718/0-3-8
Max Horz 2=-143(LC 7)
Max Uplift 2=-264(LC 6), 8=-264(LC 7)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD	2-3=-3109/945, 3-5=-2801/939, 5-7=-2801/939, 7-8=-3109/945
BOT CHORD	2-13=-674/2673, 10-13=-295/1764, 8-10=-674/2673
WEBS	5-10=-265/1150, 7-10=-524/412, 5-13=-265/1150, 3-13=-524/412

NOTES-

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) -0-8-10 to 3-8-3, Interior(1) 3-8-3 to 13-7-3, Exterior(2) 13-7-3 to 18-0-0, Interior(1) 22-4-13 to 32-3-13 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=264, 8=264.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	A6	COMMON SUPPORTED GAB	1	1	E11513727
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 — 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:28 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-nZK1z9va_6EOdI?Z9RU5cs7Uleb2jho?_p5F0vze14j

-0-10-8 / 0-10-8 — 18-0-0 / 18-0-0 — 36-0-0 / 18-0-0 — 36-10-8 / 0-10-8

Scale = 1:63.0



Plate Offsets (X,Y)-- [30:0-4-0,0-4-8], [34:0-4-0,0-4-8]

LOADING (psf)		SPACING- 2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0		Plate Grip DOL 1.15	TC	0.09	Vert(LL)	-0.00	22	n/r	120	MT20	244/190
TCDL 10.0		Lumber DOL 1.15	BC	0.03	Vert(TL)	-0.00	22	n/r	120		
BCLL 0.0	*	Rep Stress Incr YES	WB	0.16	Horz(TL)	0.01	22	n/a	n/a		
BCDL 10.0		Code IRC2009/TPI2007	Matrix-S							Weight: 263 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x6 SP No.1
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS T-Brace: 2x4 SPF No.2 - 12-32
Fasten (2X) T and I braces to narrow edge of web with 10d (0.131"x3") nails, 6in o.c.,with 3in minimum end distance.
Brace must cover 90% of web length.

REACTIONS. All bearings 36-0-0.
(lb) - Max Horz 2=169(LC 6)
Max Uplift All uplift 100 lb or less at joint(s) 2, 33, 35, 36, 37, 38, 39, 31, 29, 28, 27, 26, 25, 22 except 34=-100(LC 6), 40=-107(LC 6), 30=-101(LC 7), 24=-103(LC 7)
Max Grav All reactions 250 lb or less at joint(s) 2, 32, 33, 34, 35, 36, 37, 38, 39, 40, 31, 30, 29, 28, 27, 26, 25, 24, 22

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-279/30, 10-11=-43/341, 11-12=-46/446, 12-13=-46/446, 13-14=-43/341
BOT CHORD 2-40=0/299, 39-40=0/299, 38-39=0/299, 37-38=0/299, 36-37=0/299, 35-36=0/299, 34-35=0/299, 33-34=0/299, 32-33=0/299, 31-32=0/299, 30-31=0/299, 29-30=0/299, 28-29=0/299, 27-28=0/299, 26-27=0/299, 25-26=0/299, 24-25=0/299, 22-24=0/299

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) gable end zone and C-C Corner(3) -0-10-8 to 3-6-5, Exterior(2) 3-6-5 to 13-7-3, Corner(3) 13-7-3 to 18-0-0, Exterior(2) 22-4-13 to 32-5-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) All plates are 2x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 33, 35, 36, 37, 38, 39, 31, 29, 28, 27, 26, 25, 22 except (jt=lb) 34=100, 40=107, 30=101, 24=103.
10) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.
11) Warning: Additional permanent and stability bracing for truss system (not part of this component design) is always required.

NORTH CAROLINA PROFESSIONAL SEAL 030652 ENGINEER FRANK R. LASSITER

March 5,2018

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	B1	COMMON GIRDER	1	1	E11513728
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:29 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-GmuPBVwCkPMEFvZlj9?K93gfN2x7S9J9DTqoYLze14i

-0-10-8 8-10-0 17-8-0 18-6-8
0-10-8 8-10-0 8-10-0 0-10-8

Scale = 1:33.2



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	0.00	10	n/r	120	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.04	Vert(TL)	0.00	10	n/r	120		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.08	Horz(TL)	0.00	10	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S							Weight: 100 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x6 SP No.1
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 17-8-0.
(lb) - Max Horz 2=-91(LC 7)
Max Uplift All uplift 100 lb or less at joint(s) 10, 18, 13, 2 except 17=-102(LC 6), 19=-130(LC 6), 14=-101(LC 7), 12=-129(LC 7)
Max Grav All reactions 250 lb or less at joint(s) 10, 16, 17, 18, 19, 14, 13, 12, 2

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 5-6=-46/265, 6-7=-46/265
WEBS 3-19=-152/264, 9-12=-152/264

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) gable end zone and C-C Corner(3) -0-10-8 to 3-6-5, Exterior(2) 3-6-5 to 4-5-3, Corner(3) 4-5-3 to 8-10-0, Exterior(2) 13-2-13 to 14-1-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) All plates are 2x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 10, 18, 13, 2 except (jt=lb) 17=102, 19=130, 14=101, 12=129.
10) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 2.

March 5,2018

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	B2	COMMON GIRDER	1	2	E11513729
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 — 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:30 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-kySnOrxqVjU5t38xHsWZhHCjLS6_BP6lS7aM4oze14h



Plate Offsets (X,Y)-- [2:0-2-15,0-2-2], [6:0-2-15,0-2-2]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.53	Vert(LL)	-0.13	8-10	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.76	Vert(TL)	-0.26	8-10	>804	240	M18SHS	244/190
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.94	Horz(TL)	0.09	6	n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-S		Wind(LL)	0.08	10-11	>999	240	Weight: 238 lb	FT = 20%

LUMBER-

TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP 2400F 2.0E
WEBS 2x4 SP No.3 *Except*
4-10: 2x4 SP No.2
WEDGE
Left: 2x4 SP No.3, Right: 2x4 SP No.3

BRACING-

TOP CHORD Structural wood sheathing directly applied or 4-0-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 6=7868/0-3-8, 2=7288/0-3-8
Max Horz 2=-77(LC 6)
Max Uplift 6=-1104(LC 6), 2=-1055(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-12796/1769, 3-4=-9115/1283, 4-5=-9116/1284, 5-6=-13171/1780
BOT CHORD 2-11=-1568/11281, 10-11=-1568/11281, 8-10=-1502/11623, 6-8=-1502/11623
WEBS 4-10=-1037/7660, 5-10=-4098/619, 5-8=-473/4030, 3-10=-3696/606, 3-11=-464/3665

NOTES-

1) 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x6 - 2 rows staggered at 0-5-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60
5) All plates are MT20 plates unless otherwise indicated.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 6=1104, 2=1055.
9) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1649 lb down and 232 lb up at 2-0-12, 1649 lb down and 232 lb up at 4-0-12, 1649 lb down and 232 lb up at 6-0-12, 1649 lb down and 232 lb up at 8-0-12, 1767 lb down and 232 lb up at 10-0-12, 1767 lb down and 232 lb up at 12-0-12, and 1767 lb down and 232 lb up at 14-0-12, and 1767 lb down and 232 lb up at 16-0-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard



March 5,2018

Continued on page 2

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced) + Uninhab. Attic Storage: Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
   Vert: 1-4=-60, 4-7=-60, 2-6=-20
   Concentrated Loads (lb)
   Vert: 12=-1649(B) 13=-1649(B) 14=-1649(B) 15=-1649(B) 16=-1767(B) 17=-1767(B) 18=-1767(B) 19=-1767(B)



March 5,2018

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	G1	COMMON SUPPORTED GAB	1	1	E11513730
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:30 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-kySnOrxqVjU5t38xHsWZhHCriSHYBdrIS7aM4oze14h

0-10-8 10-10-8 20-10-8 21-9-0
0-10-8 10-0-0 10-0-0 0-10-8

Scale = 1:34.9



0-10-8 20-10-8 21-9-0
0-10-8 20-0-0 0-10-8

Plate Offsets (X,Y)-- [17:0-2-8,0-3-0]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.06	Vert(LL)	-0.00	12	n/r	120	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.02	Vert(TL)	-0.00	12	n/r	120		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.06	Horz(TL)	0.00	12	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S							Weight: 88 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. All bearings 20-0-0.
(lb) - Max Horz 2=-67(LC 5)
Max Uplift All uplift 100 lb or less at joint(s) 2, 19, 20, 21, 22, 17, 16, 15, 14, 12
Max Grav All reactions 250 lb or less at joint(s) 2, 18, 19, 20, 21, 22, 17, 16, 15, 14, 12

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) gable end zone and C-C Corner(3) -0-10-8 to 3-6-5, Exterior(2) 3-6-5 to 5-7-3, Corner(3) 5-7-3 to 10-0-0, Exterior(2) 14-4-13 to 16-5-11 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) All plates are 2x4 MT20 unless otherwise indicated.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 2-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 19, 20, 21, 22, 17, 16, 15, 14, 12.
10) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	G2	Common	5	1	E11513731
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:31 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-C809cBxSG1cyUDj8ra1oEUlt8sQ?w2KSgnJvdEze14g

0-10-8 10-0-0 20-0-0 20-10-8
0-10-8 10-0-0 10-0-0 0-10-8

Scale = 1:36.0



10-0-0 20-0-0
10-0-0 10-0-0

Plate Offsets (X,Y)-- [2:0-0-15,Edge], [4:0-0-15,Edge]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.59	Vert(LL)	-0.17	2-7	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.78	Vert(TL)	-0.48	2-7	>491	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.17	Horz(TL)	0.05	4	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S		Wind(LL)	0.07	2-7	>999	240	Weight: 88 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x4 SP No.1
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-0-13 oc purlins.
BOT CHORD Rigid ceiling directly applied or 9-1-5 oc bracing.

REACTIONS. (lb/size) 2=838/0-3-8, 4=838/0-3-8
Max Horz 2=-54(LC 7)
Max Uplift 2=-180(LC 4), 4=-180(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1438/620, 3-4=-1438/620
BOT CHORD 2-7=-462/1294, 4-7=-462/1294
WEBS 3-7=0/455

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) -0-8-3 to 3-8-10, Interior(1) 3-8-10 to 5-7-3, Exterior(2) 5-7-3 to 10-0-0, Interior(1) 14-4-13 to 16-3-6 zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=180, 4=180.
6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	M1	GABLE	2	1	E11513732
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:32 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-gLaXpXy41Klp6NIKOHY1nil6vGuzfXHbvR3T9gze14f



Plate Offsets (X,Y)-- [2:Edge,0-0-14]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.33	Vert(LL)	-0.00	2-4	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.28	Vert(TL)	-0.01	2-4	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(TL)	-0.00	4	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-P		Wind(LL)	0.00	2	****	240	Weight: 22 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=224/0-3-8, 4=144/0-1-8
Max Horz 2=139(LC 6)
Max Uplift 2=-105(LC 6), 4=-92(LC 6)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 3-4=-106/275

NOTES-
1) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) gable end zone and C-C Corner(3) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) Gable studs spaced at 2-0-0 oc.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
6) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
7) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 4 except (jt=lb) 2=105.
9) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	M2	MONOPITCH	3	1	E11513733
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:32 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-gLaXpXy41Klp6NIKOHY1nil8gGwefXHbvR3T9gze14f



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.22	Vert(LL)	-0.00	2-4	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.18	Vert(TL)	-0.01	2-4	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(TL)	-0.00	4	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-P		Wind(LL)	0.00	2	****	240	Weight: 21 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=224/0-3-8, 4=144/0-1-8
Max Horz 2=98(LC 6)
Max Uplift 2=-64(LC 6), 4=-51(LC 6)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
4) Bearing at joint(s) 4 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
5) Provide mechanical connection (by others) of truss to bearing plate at joint(s) 4.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 4.
7) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	P1	COMMON	1	1	E11513734
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:34 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-cjhIEC_KZy?XLgSjWibVs7NUx3bc7QQuMkYZDZze14d

-0-10-8 5-0-0 10-0-0 10-10-8

0-10-8 5-0-0 5-0-0 0-10-8

Scale = 1:21.4



5-0-0 10-0-0

5-0-0 5-0-0

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	-0.01	2-6	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.21	Vert(TL)	-0.04	2-6	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.09	Horz(TL)	0.01	4	n/a	n/a		
BCDL	10.0	Code IRC2009/TPI2007		Matrix-S		Wind(LL)	0.01	2-6	>999	240	Weight: 36 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=450/0-3-8, 4=450/0-3-8
Max Horz 2=30(LC 6)
Max Uplift 2=-121(LC 4), 4=-121(LC 5)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-649/368, 3-4=-649/368
BOT CHORD 2-6=-257/557, 4-6=-257/557

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=121, 4=121.
6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 5,2018

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	P2	HIP GIRDER	1	1	E11513735
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:34 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-cjhIEC_KZy?XLgSjWibVs7NW43b27QouMkYZDZze14d



Plate Offsets (X,Y)-- [2:0-2-7,Edge], [5:0-2-7,Edge]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.10	Vert(LL)	-0.02	7	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.24	Vert(TL)	-0.04	2-7	>999	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.13	Horz(TL)	0.01	5	n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-S		Wind(LL)	0.02	7	>999	240	Weight: 57 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=672/0-3-8, 5=669/0-3-8
Max Horz 2=28(LC 5)
Max Uplift 2=-194(LC 3), 5=-194(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1324/337, 3-4=-1373/342, 4-5=-1323/337
BOT CHORD 2-7=-292/1215, 5-7=-281/1215
WEBS 3-7=-32/306, 4-7=-32/307

NOTES-
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60
3) Provide adequate drainage to prevent water ponding.
4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=194, 5=194.
7) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
8) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 64 lb down and 44 lb up at 4-0-0, and 64 lb down and 44 lb up at 6-0-0 on top chord, and 187 lb down and 47 lb up at 4-0-0, and 187 lb down and 47 lb up at 5-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
9) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-60, 3-4=-60, 4-6=-60, 2-5=-20
Concentrated Loads (lb)
Vert: 3=-46(B) 4=-46(B) 8=-187(B) 9=-187(B)

March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	PCJ1	DIAGONAL HIP GIRDER	2	1	E11513736
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:35 2018 Page 1
ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-4wFgRY?zKF7Ozq1v4P6kOKwg9TzWsu11bOH7m?ze14c



Plate Offsets (X,Y)-- [2:0-5-5,0-0-0]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.14	Vert(LL)	-0.01	2-6	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.10	Vert(TL)	-0.02	2-6	>999	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.00	Horz(TL)	0.00		n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-P		Wind(LL)	0.00	2	****	240	Weight: 31 lb	FT = 20%

LUMBER-
TOP CHORD 2x6 SP No.1
BOT CHORD 2x6 SP No.1
WEBS 2x4 SP No.3

BRACING-
TOP CHORD Structural wood sheathing directly applied or 5-6-6 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 6=198/Mechanical, 2=287/0-8-6
Max Horz 2=63(LC 3)
Max Uplift 6=-42(LC 3), 2=-109(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise); Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 6 except (jt=lb) 2=109.
6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
7) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) at 2-9-8, and at 2-9-8 on top chord, and at 2-9-8, and at 2-9-8 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard
1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-3=-60, 3-4=-20, 2-5=-20



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	PJ1	JACK-OPEN	2	1	E11513737
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:35 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-4wFgRY?zKF7Ozq1v4P6kOKwgeTz7su11bOH7m?ze14c



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.18	Vert(LL)	-0.01	2-4	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.13	Vert(TL)	-0.03	2-4	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-P		Wind(LL)	0.00	2	****	240	Weight: 14 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 3=106/Mechanical, 2=221/0-3-8, 4=38/Mechanical
Max Horz 2=64(LC 4)
Max Uplift 3=-56(LC 4), 2=-77(LC 4)
Max Grav 3=106(LC 1), 2=221(LC 1), 4=76(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

March 5,2018

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	Freelance A
B0318-0840	PJ2	JACK-OPEN	4	1	E11513738
					Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309 8.130 s Sep 15 2017 MiTek Industries, Inc. Mon Mar 5 08:27:36 2018 Page 1

ID:qBVty8JxTR2c0jvIHgLUvLzeJa3-Y6p2fu?b5ZFFb_c5d7dzxYStXtKsbLGBq21gIRze14b



LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.04	Vert(LL)	-0.00	2	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.03	Vert(TL)	-0.00	2-4	>999	240		
BCLL	0.0 *	Rep Stress Incr	YES	WB	0.00	Horz(TL)	-0.00	3	n/a	n/a		
BCDL	10.0	Code	IRC2009/TPI2007	Matrix-P		Wind(LL)	0.00	2	****	240	Weight: 8 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.1
BOT CHORD 2x4 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-11-11 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 3=45/Mechanical, 2=144/0-3-8, 4=19/Mechanical
Max Horz 2=38(LC 4)
Max Uplift 3=-23(LC 4), 2=-64(LC 4)
Max Grav 3=45(LC 1), 2=144(LC 1), 4=39(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

NOTES-
1) Wind: ASCE 7-05; 110mph; TCDL=6.0psf; BCDL=5.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (low-rise) and C-C Exterior(2) zone;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
3) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members.
4) Refer to girder(s) for truss to truss connections.
5) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 3, 2.
6) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.



March 5,2018

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MiTek 20/20 software or upon request.**

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

MiTek

ENGINEERING BY TRENCO
A MiTek Affiliate

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.