


ROOF TRUSS NOTES:
 DO NOT CUT, DRILL, NOTCH, OR OTHERWISE DAMAGE TRUSSES. Contact your SPS Representative for assistance PRIOR TO modifying any truss.
 Español: NO CORTE, PERFORE, HAGA MUESCAD O DANE DE CUALQUIER OTRA MANERA LAS TRUSSAS (CERCHAS DE MADERA). Contacte a su representante de SPS para asistencia ANTES de realizar cualquier modificación.
 1. This Truss Placement Diagram is intended to serve as a guide for truss installation. This Diagram has been prepared by a Truss Technician and is not an engineered drawing.
 2. The responsibilities of the Owner, Building Designer, Contractor, Truss Designer, and Truss Manufacturer shall be as defined by the TP 1 National Standard.
 3. The wood components shown on this diagram are to be used in dry service (moderate humidity) and non-toxic environmental applications. The metal plates and hangers are galvanized to the G90 Standard unless noted otherwise.
 4. Refer to the Truss Design Drawings for specific information about each individual truss design.
 5. The Truss Technician shall provide Truss-to-Truss Connection Requirements. Any special or other connection shall be the responsibility of the Building Designer.
 6. The Truss Placement Diagram and Truss Design Drawings are the property of Builders FirstSource and may not be reused or reproduced in part or in total under any circumstances without prior written authorization.
 7. In some cases, field framing may be required to achieve the final appearance shown on the Construction Documents.
 8. Field framing, including valley rafters, installed over roof trusses shall have a knee brace from the rafter to the truss top chord at intervals of 40' or greater (D.C.) or less. Sagger knee braces from adjacent rafters such that the load is distributed uniformly over multiple truss locations and not concentrated at one location or along one truss.
 9. Truss Top Chords shall be fully sheathed or have lateral bracing (truss) spaced at 24" O.C. or less. Truss Bottom Chord Bracing shall not exceed the maximum shown on the Truss Design Drawing. Field Braced bottom chord floor or ceiling attachments shall be spaced at 24" O.C. or less. Proper Bracing prevents buckling of individual truss members due to design loads.
 10. This Placement Diagram is based upon the supporting structure being structurally adequate. Irregularly spaced, square, plumb, and level to adequately support the trusses. The foundation design, structural member sizing, load transfer, bearing conditions, and the structural compliance with the applicable building code are the responsibility of the Owner, Building Designer, and Contractor.
 11. If Pigeonhole Trusses are included in this project, refer to the Metal Pigeonhole Connection Detail applicable for the project details and wind load category.
 12. The Contractor shall follow the SCSA TTB Partition Separation Prevention and Solutions for truss attachment to non-load bearing walls and carefully complete these details to avoid gypsum wall board related issues.

WARNING:
 TRUSSES MUST BE BRACED DURING INSTALLATION. FAILURE TO DO SO MAY RESULT IN INJURY OR DEATH.
 Español: (TRUSSAS) CERRCHAS DEBERAN TENER UN SOPORTE DURANTE LA INSTALACION. NO HACERLO PODRIA RESULTAR EN LESIONES O MUERTE!
 1. Trusses shall be installed in a safe manner meeting all code, local, OSHA, TPI, and SCSA Specifications. Failure to follow these specifications may result in injury or death.
 2. Buildings under construction are vulnerable to high winds and present a possible safety hazard. The Contractor is responsible for recognizing adverse weather conditions and shall take appropriate action to prevent injury or death.
 3. BCS INSTRUCTIONS SHALL BE FOLLOWED:
 BCSI-81 = Safe Truss Handling and Installation
 BCSI-82 = Installation and Temporary Restraint
 BCSI-83 = Permanent Restraint
 BCSI-84 = Safe Construction Loading
 BCSI-85 = Truss Damage and Modification Guidelines
 BCSI-87 = Floor Truss Installation
 BCSI-88 = Toe-Nailed Connections
 BCSI-89 = Nailing Schedules
 BCSI-810 = Post Frame Truss Installation
 BCSI-811 = Fall Protection
 4. Follow TPI Requirements for Long Span Trusses (LST).



Products				
PlotID	Length	Product	Plies	Net Qty
B1	14-00-00	1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP	2	2
B2	20-00-00	1-3/4" x 16" VERSA-LAM® 2.0 3100 SP	2	2
GDH	18-00-00	1-3/4" x 18" VERSA-LAM® 2.0 3100 SP	2	2

Truss Connector Total List		
Manuf	Product	Qty
Simpson	MUS26	27
Non-Proprietary	NAILED	47

TOTAL ROOF AREA
 5885.8 SQ FT

1/4" = 1'

Until this building is completely erected in accordance with plans, the trusses may be unstable and present a safety hazard. Truss instability may increase with building width, height, and length. Buildings under construction are vulnerable to high winds and present a possible safety hazard. The Contractor is responsible for recognizing adverse weather conditions and shall take appropriate action to prevent injury or death.

Builders FirstSource
 Albemarle, NC

Customer Name: STURIZ HOMIES
 Subdivision: LEIGH LAUREL
 Plan Name: PINEWOODROOTER
 Lot#: 23
 File Name: 1625532

Revisions:

1625532	1625532
Drawn By: STW	DATE: 4/25/2019
Page Number	1 of 1