



SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: OAKMONT

LOT 199

INITIAL SYSTEM: APPROVED 25% REDUCTION
pump to

REPAIR APPROVED 25% REDUCTION
pump to

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION RC 199/200

NO. BEDROOMS: 5

LTAR 0.8 GPD/FT²

LINE FLAG COLOR ELEVATION LENGTH

1	B	100.0	45'
2	O	99.50	80'
3	B	98.67	80'
			<u>205'</u>
4	O	98.08	80'
5	B	97.17	80'
6	O	96.75	40'
			<u>200'</u>

Initial system

BY M. EAKER

DATE 03/2015

TYPICAL PROFILE

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

0-42" s/w (VF₁ w_g-)

cr 2/pm > 92"

INSTALL AT 18-24"