Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F06	Floor	2	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:18 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-_sUeH5qBj1wk6eEC_xEu5K3hweCh2U6gBJwS2WyCMs7





Plate Offsets (X,Y)-- [7:0-1-8,Edge], [12:0-3-0,Edge], [19:0-1-8,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.49	Vert(LL)	-0.26	18	>788	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.36	18-19	>574	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.69	Horz(CT)	0.01	12	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 90 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 22=0-5-8 (min. 0-1-8), 12=0-3-8 (min. 0-1-8)
Max Grav 22=941(LC 1), 12=948(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1992/0, 3-4=-3232/0, 4-5=-3232/0, 5-6=-3885/0, 6-7=-3885/0, 7-8=-3624/0, 8-9=-2725/0, 9-10=-1175/0, 10-11=-1151/0, 11-12=-1175/0
BOT CHORD 21-22=0/1177, 20-21=0/2772, 19-20=0/3669, 18-19=0/3885, 17-18=0/3885, 16-17=0/3339, 15-16=0/2082, 14-15=0/2082
WEBS 12-14=0/1443, 2-22=-1473/0, 2-21=0/1061, 3-21=-1016/0, 3-20=0/598, 5-20=-568/0, 5-19=-98/591, 9-14=-1157/0, 9-16=0/838, 8-16=-799/0, 8-17=0/481, 7-17=-571/28

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Plates checked for a plus or minus 1 degree rotation about its center.
4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
7) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F06A	Floor	3	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:19 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-S320VRrpUL2akopPYfm7eYcyT2j8n2EpQzf?ayyCMs6



0-4-0	1-10-0	3-2-3	3-2-8	3-10-7	4-6-5	7-4-13
0-4-0	1-6-0	1-4-3	0-0-5	0-7-15	0-7-15	2-10-8

Plate Offsets (X,Y)-- [4:0-1-8,Edge], [9:0-1-8,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.12	Vert(LL)	-0.02	8-9	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.16	Vert(CT)	-0.02	8-9	>999	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.25	Horz(CT)	0.00	8	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 41 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 8=Mechanical, 1=0-3-8 (min. 0-1-8)
Max Grav 8=378(LC 1), 1=378(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-424/0, 2-3=-426/0, 3-4=-424/0, 4-5=-611/0, 5-6=-611/0
BOT CHORD 10-11=0/611, 9-10=0/611, 8-9=0/410
WEBS 1-11=0/520, 6-8=-514/0, 6-9=0/290, 4-11=-299/0

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) Plates checked for a plus or minus 1 degree rotation about its center.
3) Refer to girder(s) for truss to truss connections.
4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
7) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F07	Floor	2	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:20 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-wFcOinsRFfARLyOb5MHMAl91JSt9WOpzfdPZ7OyCMs5



Plate Offsets (X,Y)-- [7:0-1-8,Edge], [12:0-3-0,Edge], [19:0-1-8,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.50	Vert(LL)	-0.26	18	>788	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.88	Vert(CT)	-0.36	18-19	>574	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.67	Horz(CT)	0.01	12	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 91 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 22=0-5-8 (min. 0-1-8), 12=0-6-12 (min. 0-1-8)
Max Grav 22=941(LC 1), 12=948(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1992/0, 3-4=-3232/0, 4-5=-3232/0, 5-6=-3886/0, 6-7=-3886/0, 7-8=-3624/0, 8-9=-2726/0, 9-10=-1153/0, 10-11=-1153/0, 11-12=-1157/0
BOT CHORD 21-22=0/1177, 20-21=0/2772, 19-20=0/3669, 18-19=0/3886, 17-18=0/3886, 16-17=0/3338, 15-16=0/2085, 14-15=0/2085
WEBS 12-14=0/1416, 2-22=-1473/0, 2-21=0/1061, 3-21=-1016/0, 3-20=0/598, 5-20=-568/0, 5-19=-98/591, 9-14=-1190/0, 9-16=0/834, 8-16=-796/0, 8-17=0/482, 7-17=-571/28

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Plates checked for a plus or minus 1 degree rotation about its center.
4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
7) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F08	Floor	6	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:22 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-sek97TthnGQ9bGY_DnJqGAEJMFZK_KGG6xufBHyCMs3



Plate Offsets (X,Y)-- [4:0-1-8,Edge], [9:0-3-0,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.72	Vert(LL)	-0.26	13-14	>665	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.83	Vert(CT)	-0.34	13-14	>497	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.55	Horz(CT)	-0.03	9	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 76 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP 2400F 2.0E(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 17=0-5-8 (min. 0-1-8), 9=0-6-12 (min. 0-1-8)
Max Grav 17=776(LC 1), 9=783(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1573/0, 3-4=-2447/0, 4-5=-2607/0, 5-6=-2106/0, 6-7=-940/0, 7-8=-940/0, 8-9=-944/0
BOT CHORD 16-17=0/923, 15-16=0/2447, 14-15=0/2447, 13-14=0/2447, 12-13=0/2549, 11-12=0/1653
WEBS 9-11=0/1154, 6-11=-909/0, 6-12=0/590, 5-12=-578/0, 4-13=-189/358, 4-14=-331/0, 2-17=-1154/0, 2-16=0/846, 3-16=-1097/0, 3-15=0/354

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Plates checked for a plus or minus 1 degree rotation about its center.
4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
6) Gap between inside of top chord bearing and first diagonal or vertical web shall not exceed 0.500in.
7) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F09	Floor	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:23 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-KqIXKouJXaY0DP6AnVq3oOnSSfu2jrHPLbdDjjyCMs2



Plate Offsets (X,Y)-- [1:Edge,0-1-8], [2:0-1-8,Edge], [11:0-1-8,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.89	Vert(LL)	-0.20	10-11	>647	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.93	Vert(CT)	-0.28	10-11	>471	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.31	Horz(CT)	0.02	8	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 57 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.

REACTIONS. (size) 13=Mechanical, 8=0-5-4 (min. 0-1-8)
Max Grav 13=604(LC 1), 8=598(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1056/0, 3-4=-1056/0, 4-5=-1595/0, 5-6=-1118/0
BOT CHORD 12-13=0/1056, 11-12=0/1056, 10-11=0/1559, 9-10=0/1504, 8-9=0/724
WEBS 6-8=-905/0, 6-9=0/514, 5-9=-502/0, 4-11=-666/0, 2-13=-1304/0, 2-12=0/285

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Plates checked for a plus or minus 1 degree rotation about its center.
4) Refer to girder(s) for truss to truss connections.
5) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
6) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
7) CAUTION, Do not erect truss backwards.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F10	Floor Girder	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:25 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-HDQHlUwa3BokSjGZuvsXtpsxZTeKBj0iov6KocyCMs0



Plate Offsets (X,Y)-- [4:0-3-0,Edge], [5:0-3-0,0-0-0], [9:0-3-0,Edge], [13:0-1-8,Edge], [14:0-1-8,Edge], [17:0-1-8,0-0-8], [18:0-1-8,0-0-8]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.27	Vert(LL)	-0.14	12-13	>999	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.69	Vert(CT)	-0.20	12-13	>907	360		
BCLL	0.0	Rep Stress Incr	NO	WB	0.42	Horz(CT)	0.04	10	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 95 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 16=0-5-8 (min. 0-1-8), 10=0-5-4 (min. 0-1-8)
Max Grav 16=828(LC 1), 10=810(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-19=-1765/0, 3-19=-1765/0, 3-4=-2955/0, 4-5=-2955/0, 5-6=-2955/0, 6-7=-2746/0, 7-8=-1751/0
BOT CHORD 15-16=0/1091, 14-15=0/2413, 13-14=0/2955, 12-13=0/3033, 11-12=0/2414, 10-11=0/1056
WEBS 8-10=-1292/0, 8-11=0/883, 7-11=-842/0, 7-12=0/421, 6-12=-365/0, 6-13=-236/318, 2-16=-1337/0, 2-15=0/855, 3-15=-823/0, 3-14=0/749, 4-14=-394/0

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) Plates checked for a plus or minus 1 degree rotation about its center.
3) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
4) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
5) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 93 lb down at 1-7-12, and 93 lb down at 3-7-12 on top chord. The design/selection of such connection device(s) is the responsibility of others.
6) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
1) Dead + Floor Live (balanced): Lumber Increase=1.00, Plate Increase=1.00
Uniform Loads (plf)
Vert: 10-16=-10, 1-9=-100
Concentrated Loads (lb)
Vert: 2=-13(B) 19=-13(B)

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	2F11	Floor	1	1	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:26 2018 Page 1
ID:n1MgMELpzItqfpK?soeuv2zRW0r-lPzfzqxCqVwb4trlSdOmQ0P0ItyLwAYr1ZstK2yCMs?



Plate Offsets (X,Y)-- [13:0-1-8,Edge], [14:0-1-8,Edge]

LOADING (psf)		**SPACING-**	2-0-0	**CSI.**		**DEFL.**	in	(loc)	l/defl	L/d	**PLATES**	**GRIP**
TCLL	40.0	Plate Grip DOL	1.00	TC	0.66	Vert(LL)	-0.20	12-13	>900	480	MT20	244/190
TCDL	10.0	Lumber DOL	1.00	BC	0.83	Vert(CT)	-0.27	12-13	>651	360		
BCLL	0.0	Rep Stress Incr	YES	WB	0.40	Horz(CT)	0.04	10	n/a	n/a		
BCDL	5.0	Code IRC2015/TPI2014		Matrix-S							Weight: 75 lb	FT = 20%F, 11%E

LUMBER-
TOP CHORD 2x4 SP No.1(flat)
BOT CHORD 2x4 SP No.1(flat)
WEBS 2x4 SP No.3(flat)

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 16=0-5-8 (min. 0-1-8), 10=0-5-4 (min. 0-1-8)
Max Grav 16=806(LC 1), 10=806(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-1630/0, 3-4=-2759/0, 4-5=-2759/0, 5-6=-2759/0, 6-7=-2590/0, 7-8=-1648/0
BOT CHORD 15-16=0/1003, 14-15=0/2258, 13-14=0/2759, 12-13=0/2837, 11-12=0/2274, 10-11=0/998
WEBS 8-10=-1249/0, 8-11=0/845, 7-11=-815/0, 7-12=0/412, 6-12=-322/0, 6-13=-298/288, 2-16=-1256/0, 2-15=0/816, 3-15=-818/0, 3-14=0/795, 4-14=-350/0

NOTES-
1) Unbalanced floor live loads have been considered for this design.
2) All plates are 3x4 MT20 unless otherwise indicated.
3) Plates checked for a plus or minus 1 degree rotation about its center.
4) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
5) Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	AGR01	ROOF SPECIAL GIRDER	1	3	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis

Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:32 2018 Page 1
ID:n1MgMELpzltqfpK?soeuv2zRW0r-aZLxDt?zQLhkooIvouVAgHe4NH8XKo8kPVJBXiyCMrv

7-3-12	10-7-4	19-6-0	28-4-11	37-3-7	46-0-11
7-3-12	3-3-8	8-10-12	8-10-12	8-10-12	8-9-4

Scale = 1:86.1



7-3-12	10-7-4	19-6-0	28-4-11	37-3-7	46-0-11
7-3-12	3-3-8	8-10-12	8-10-12	8-10-12	8-9-4

Plate Offsets (X,Y)-- [2:0-3-4,0-3-8], [3:0-4-12,0-4-0], [11:0-3-8,0-5-12], [13:0-5-0,0-7-12]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	-0.17	13-15	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.20	Vert(CT)	-0.31	13-15	>999	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.78	Horz(CT)	0.04	10	n/a	n/a		
BCDL	25.0	Code IRC2015/TPI2014		Matrix-S		Wind(LL)	0.07	15	>999	240	Weight: 1822 lb	FT = 20%

LUMBER-
TOP CHORD 2x8 SP 2400F 2.0E *Except* T1,T2: 2x6 SP No.1
BOT CHORD 2x12 SP 2400F 2.0E
WEBS 2x6 SP No.1

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2, 3-9.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 19=0-5-8 (min. 0-2-11), 10=Mechanical
Max Horz 19=105(LC 8)
Max Uplift19=-332(LC 4), 10=-265(LC 5)
Max Grav 19=9630(LC 2), 10=9899(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-19=-8810/264, 1-2=-9391/228, 2-3=-12769/359, 3-4=-9283/290, 4-20=-14525/401, 5-20=-14525/401, 5-21=-14525/401, 21-22=-14525/401, 22-23=-14525/401, 6-23=-14525/401, 6-24=-14525/401, 7-24=-14525/401, 7-25=-14525/401, 25-26=-14525/401, 26-27=-14525/401, 8-27=-14525/401, 8-28=-8268/198, 28-29=-8268/198, 29-30=-8268/198, 30-31=-8268/198, 9-31=-8268/198
BOT CHORD 18-35=-311/9684, 17-35=-311/9684, 17-36=-401/14525, 36-37=-401/14525, 16-37=-401/14525, 16-38=-401/14525, 38-39=-401/14525, 39-40=-401/14525, 15-40=-401/14525, 15-41=-401/14525, 41-42=-401/14525, 42-43=-401/14525, 14-43=-401/14525, 14-44=-401/14525, 13-44=-401/14525, 13-45=-198/8268, 12-45=-198/8268, 12-46=-198/8268, 46-47=-198/8268, 47-48=-198/8268, 11-48=-198/8268
WEBS 1-18=-305/12704, 2-18=-8098/246, 2-17=-1260/112, 3-17=-156/8908, 4-17=-7893/217, 4-15=-27/2699, 6-13=-4210/227, 8-13=-298/9198, 8-11=-6767/383, 9-10=-9532/297, 9-11=-298/12426

NOTES-
1) 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x8 - 2 rows staggered at 0-7-0 oc.
Bottom chords connected as follows: 2x12 - 2 rows staggered at 0-9-0 oc.
Webs connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 25.0psf.
8) Refer to girder(s) for truss to truss connections.

Continued on page 2

NOTES-

9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 332 lb uplift at joint 19 and 265 lb uplift at joint 10.
10) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 2478 lb down and 197 lb up at 21-1-2, 1071 lb down and 71 lb up at 23-0-6, 1071 lb down and 71 lb up at 25-0-6, 1071 lb down and 71 lb up at 27-0-6, 1071 lb down and 71 lb up at 29-0-6, 55 lb down and 81 lb up at 31-0-6, 55 lb down and 81 lb up at 33-0-6, 55 lb down and 81 lb up at 35-0-6, 22 lb down and 168 lb up at 37-0-6, 22 lb down and 167 lb up at 39-0-6, 22 lb down and 167 lb up at 41-0-6, and 22 lb down and 167 lb up at 43-0-6, and 21 lb down and 167 lb up at 45-0-6 on top chord, and 373 lb down and 181 lb up at 2-1-15, 423 lb down at 4-5-9, 423 lb down at 6-5-9, 423 lb down at 7-1-3, 423 lb down at 9-1-3, 294 lb down at 11-1-3, 294 lb down at 13-1-3, 478 lb down at 15-1-3, 478 lb down at 17-1-3, 478 lb down at 19-1-3, 458 lb down at 21-1-3, 478 lb down at 23-1-3, 581 lb down at 25-1-3, 241 lb down at 27-1-3, 581 lb down at 29-1-3, 478 lb down at 31-1-3, 478 lb down at 33-1-3, 478 lb down at 35-1-3, and 478 lb down at 37-1-3, and 1072 lb down at 38-11-7 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (plf)
Vert: 1-2=-60, 2-3=-60, 3-9=-60, 10-19=-50
Concentrated Loads (lb)
Vert: 18=-79(F) 17=-44(F) 11=-94(F) 20=-2478 21=-966(F) 22=-966(F) 23=-966(F) 24=-966(F) 25=-17(F) 26=-17(F) 27=-17(F) 32=-370(F) 33=-79(F) 34=-79(F) 35=-79(F) 37=-44(F) 38=-94(F) 39=-94(F) 40=-94(F) 41=-83(F) 42=-94(F) 43=-128(F) 44=-29(F) 45=-128(F) 46=-94(F) 47=-94(F) 48=-94(F) 50=-272(F)

Job	Truss	Truss Type	Qty	Ply	
J1118-5039	AGR02	ROOF SPECIAL GIRDER	1	3	Job Reference (optional)

Comtech, Inc., Fayetteville, NC 28309, Bob Lewis — Run: 8.120 s Jun 27 2017 Print: 8.120 s Jun 27 2017 MiTek Industries, Inc. Tue Dec 4 11:55:36 2018 Page 1

ID:n1MgMELpzItqfpK?soeuv2zRW0r-SKaR3F2TUZBAGPcg1jZ6q7prgvUoGahJK6HPgTyCMrr

5-11-12	10-3-0	10-7-4	17-9-1	24-10-13	32-0-10	39-2-6	46-0-11	46-4-3
5-11-12	4-3-4	0-4-4	7-1-13	7-1-13	7-1-13	7-1-13	6-10-5	0-3-8

Scale = 1:81.8



5-11-12	10-7-4	17-9-1	24-10-13	28-5-11	32-0-10	39-2-6	46-0-11
5-11-12	4-7-8	7-1-13	7-1-13	3-6-14	3-6-14	7-1-13	6-10-5

Plate Offsets (X,Y)-- [2:0-3-12,0-3-0], [3:0-8-12,0-4-0], [14:0-5-0,0-6-8], [17:0-3-12,0-8-0], [20:0-5-8,0-2-8]

LOADING (psf)		SPACING-	2-0-0	CSI.		DEFL.	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL	20.0	Plate Grip DOL	1.15	TC	0.15	Vert(LL)	-0.16	16	>999	360	MT20	244/190
TCDL	10.0	Lumber DOL	1.15	BC	0.31	Vert(CT)	-0.29	16-17	>999	240		
BCLL	0.0 *	Rep Stress Incr	NO	WB	0.87	Horz(CT)	0.06	12	n/a	n/a		
BCDL	10.0	Code IRC2015/TPI2014		Matrix-S		Wind(LL)	0.10	17-19	>999	240	Weight: 1784 lb	FT = 20%

LUMBER-

TOP CHORD 2x8 SP No.1 *Except* T1,T2: 2x6 SP No.1
BOT CHORD 2x10 SP 2400F 2.0E
WEBS 2x6 SP No.1

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 1-2, 3-11.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (size) 21=0-5-8 (min. 0-2-3), 12=Mechanical
Max Horz 21=137(LC 8)
Max Uplift 21=-121(LC 5)
Max Grav 21=8023(LC 2), 12=10229(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

TOP CHORD 1-21=-7720/132, 1-2=-8281/120, 2-3=-11682/303, 3-4=-13929/152, 4-5=-13929/152, 5-6=-13929/152, 6-7=-11270/0, 7-8=-11270/0, 8-9=-11270/0

BOT CHORD 19-20=-229/8643, 18-19=-264/8305, 18-22=-264/8305, 17-22=-264/8305, 17-23=-152/13929, 23-24=-152/13929, 24-25=-152/13929, 16-25=-152/13929, 16-26=-152/13929, 26-27=-152/13929, 15-27=-152/13929, 15-28=-152/13929, 28-29=-152/13929, 14-29=-152/13929, 14-30=0/6462, 30-31=0/6462, 31-32=0/6462, 32-33=0/6462, 13-33=0/6462, 13-34=0/6462, 34-35=0/6462, 35-36=0/6462, 12-36=0/6462

WEBS 1-20=-160/11173, 2-20=-8023/277, 2-19=-541/19, 3-19=-242/999, 3-17=0/9027, 5-17=-545/292, 9-13=0/2440, 9-12=-11141/0, 9-14=0/7897, 8-14=-413/190, 6-14=-4552/997, 6-16=-526/3210

NOTES-

1) 3-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc, 2x8 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x10 - 4 rows staggered at 0-4-0 oc.
Webs connected as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Unbalanced roof live loads have been considered for this design.
4) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=15ft; Cat. II; Exp C; enclosed; MWFRS (envelope); Lumber DOL=1.60 plate grip DOL=1.60
5) Provide adequate drainage to prevent water ponding.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas with a clearance greater than 6-0-0 between the bottom chord and any other members, with BCDL = 10.0psf.
8) Refer to girder(s) for truss to truss connections.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 121 lb uplift at joint 21.
10) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

NOTES-

12) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 4321 lb down and 369 lb up at 17-1-8, 1099 lb down and 52 lb up at 19-1-12, 1099 lb down and 52 lb up at 21-1-12, 1099 lb down and 52 lb up at 23-1-12, 1106 lb down and 52 lb up at 25-1-12, 497 lb down and 77 lb up at 27-1-12, 556 lb down at 29-1-12, 565 lb down at 31-1-12, 562 lb down at 33-1-12, 556 lb down at 35-1-12, 556 lb down at 37-1-12, 562 lb down at 39-1-12, 556 lb down at 41-1-12, and 556 lb down at 43-1-12, and 571 lb down at 45-1-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

1) Dead + Roof Live (balanced): Lumber Increase=1.15, Plate Increase=1.15
   Uniform Loads (plf)
      Vert: 1-2=-60, 2-3=-60, 12-21=-20, 3-11=-60
   Concentrated Loads (lb)
      Vert: 13=-484(B) 16=-1021(B) 22=-4321(B) 23=-1021(B) 24=-1021(B) 25=-1021(B) 26=-425(B) 27=-484(B) 28=-484(B) 31=-484(B) 32=-484(B) 33=-484(B) 34=-484(B) 35=-484(B) 36=-487(B)