

HTE# SFD1812-0008

Harnett County Department of Public Health

30309

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Craig Matthews Realty Inc

PROPERTY LOCATION: 48 John White Rd. (Harvell Rd.) ^{SR 2008}

NEW REPAIR EXPANSION

SUBDIVISION White Pines S/D LOT # 6

Type of Structure: 3BR 55' x 43' SFD

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: 25% reduction

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well NA feet

Permit valid for: Five years No expiration

Permit conditions:

Authorized State Agent: [Signature]

Date: 12/20/2018

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Craig Matthew Realty Inc.

PROPERTY LOCATION: 48 John White Rd. (Harvell Rd.) ^{SR 2008}

Facility Type: 3BR 55' x 43' SFD New Expansion Repair

SUBDIVISION White Pines S/D LOT # 6

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% Reduction system (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable)

25% Reduction Sys. (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Number of trenches 3

Pump Tank Size _____ gallons

Exact length of each trench 80 feet

Trench Spacing: 9 Feet on Center

Trenches shall be installed on contour at a Maximum Trench Depth of: 24 inches

Soil Cover: 12 inches
(Maximum soil cover shall not exceed 36" above the trench bottom)

(Trench bottoms shall be level to +/- 1/4" in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: NA inches below pipe
NA inches above pipe
NA inches total

Conditions: D-Box Equal Distribution Required

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature]

Date: 12/20/2018

ANDREW CURRIN

Construction Authorization Expiration Date: 12/20/2023

HTE# SR1812-0008

Permit # 30309

Harnett County Department of Public Health Site Sketch

ISSUED TO: Craig Matthews Realty Inc. SUBDIVISION White Pines S/D LOT # C
PROPERTY LOCATOR: 48 John White Rd. (Harvell Road) ^{SL 2008}

Authorized State Agent: Andrew Curran Date: 12/20/2018

