

HTE# SFD1901-0010

Harnett County Department of Public Health

30461

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: W&H Const. of Fayetteville

PROPERTY LOCATION: 307 Heatherwood Dr. (Docs Road)

NEW REPAIR EXPANSION

SUBDIVISION Oakmont S/D LOT # 183

Type of Structure: 4BR 41'x47' SFD

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: 25% Reduction

Projected Daily Flow: 480 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well NA feet

Permit valid for: Five years No expiration

Permit conditions:

Authorized State Agent: [Signature]

Date: 02/04/2019

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: W&H Const. of Fayetteville

PROPERTY LOCATION: 307 Heatherwood Dr. (Docs Road)

Facility Type: 4BR 41'x47' SFD New Expansion Repair

SUBDIVISION Oakmont S/D LOT # 183

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% Reduction Sys. (Initial) Wastewater Flow: 480 GPD

(See note below, if applicable 25% Reduction Sys. (Repair))

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Number of trenches 4

Pump Tank Size _____ gallons

Exact length of each trench 60 feet

Trench Spacing: 9 Feet on Center

Trenches shall be installed on contour at a Maximum Trench Depth of: 18 inches

Soil Cover: 6 inches

(Trench bottoms shall be level to +/-1/4"

(Maximum soil cover shall not exceed 36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: NA inches below pipe

NA inches above pipe

NA inches total

Conditions:

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 02/04/2019
ANDREW CURRAN Construction Authorization Expiration Date: 02/04/2024

HTE# SFD1901-0010

Permit # 30461

Harnett County Department of Public Health Site Sketch

52111C

ISSUED TO: H&H Consts of Fayetteville SUBDIVISION Oakmont S/D LOT # 183
PROPERTY LOCATOR: 307 Heatherwood Dr. (Doss Road)

Authorized State Agent: *Andrew Curran* Date: 02/04/2019
ANDREW CURRAN

