## Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 14 Treasure Dr. (Neills Creek Rd. - SR 1513) ISSUED TO: Cumberland Homes Inc. LOT # 23 (IIBDIVISION South Creek REPAIR 🔲 EXPANSION | Site Improvements required prior to Construction Authorization Issuance: NEW X Type of Structure: 41.4X54.6 3BR 2.5BA SFD Slab Proposed Wastewater System Type: 25% Reduction Sys Projected Daily Flow: 360 Number of bedrooms: 3\_ Number of Occupants: 6 Basement Yes May be required based on final location and elevations of facilities X No Pump Required: Yes Type of Water Supply: Community Dublic Well Distance from well NA X Five years Permit valid for: No expiration Permit conditions: 03/01/2019 Date: \_ The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules . 1950, . 1952, . 1954, . 1955, . 1956, . 1957, . 1958, and . 1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. PROPERTY LOCATION: 14 Treasure Dr. (Neills Creek Rd. - SR 1513) ISSUED TO: Cumberland Homes Inc. SUBDIVISION South Creek LOT # 23 Facility Type: 41.4X54.6 3BR 2.5BA SFD Slab × New Expansion Repair Basement? Yes Basement Fixtures? Yes  $\times$ 25% Reduction System (Initial) Wastewater Flow: 360 Type of Wastewater System\*\* (See note below, if applicable ) 25% Reduction Sys. Number of trenches 1 Installation Requirements/Conditions Exact length of each trench 225 Trench Spacing: 9 Septic Tank Size 1000 gallons Soil Cover: 6\_\_\_\_\_inches gallons Trenches shall be installed on contour at a Pump Tank Size \_\_\_\_\_ (Maximum soil cover shall not exceed Maximum Trench Depth of: 18 (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) inches below pipe Pump Requirements: ft. TDH vs. \_ Aggregate Depth: inches above pipe Conditions: Four (4) 60ft lines with D-Box if contour allows inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Date: Authorized State Agent: Construction Authorization Expiration Date: 03/01/2024

## Harnett County Department of Public Health Site Sketch

				511573	,
	PROPERTY LOCATON:_	14 Treas	ore Dr. (No	eillscrapt	cni.)
ISSUED TO: Combestand Homes FAC.	SUBDIVISION _	South		LOT # _	23
		aciic .	F-71-1	10	
Authorized State Agent:	-com,	Date:	03/01	10019	
ANNE	E S CURR				

