

Project Title: Prelude Plan crawl

Energy Code: North Carolina Energy Conservation Code

Location: Lillington, North Carolina

Construction Type: Single Family
Project Type: New construction

Building Orientation: Bldg. faces 90 deg. from North

Glazing Area Percentage: 12%
Heating Degree Days: 3502
Climate Zone: 4

Construction Site: Owner/Agent: NC H&H Homes

2919 Breezewood Ave, Suite 400

Fayetteville, NC 28303

910-486-4864

Designer/Contractor:

Justin Smith

Southern Energy Management

101 Kitty Hawk Dr Morrisville, NC 27560 (919) 836-0330

jsmith@southern-energy.com

## Compliance: Passes using UA trade-off

Compliance: 11.6% Better Than Code Maximum UA: 431 Your UA: 381 Maximum SHGC: 0.30 Your SHGC: 0.27

The~%~Better~or~Worse~Than~Code~index~reflects~how~close~to~compliance~the~house~is~based~on~code~trade-off~rules.

It DOES NOT provide an estimate of energy use or cost relative to a minimum-code home

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Glazing or Door U-Factor	UA
Ceiling 1: Flat Ceiling or Scissor Truss	1446	26.0	12.0		39
Wall 1: Wood Frame, 16" o.c. Orientation: Front	684	19.0	0.0		33
Window 1: Vinyl Frame:Double Pane with Low-E SHGC: 0.27 Orientation: Front	90			0.350	31
Door 1: Solid Orientation: Front	20			0.200	4
Door 2: Solid Orientation: Front	18			0.200	4
Wall 2: Wood Frame, 16" o.c. Orientation: Left Side	738	19.0	0.0		41
Window 2: Vinyl Frame:Double Pane with Low-E SHGC: 0.27 Orientation: Left Side	60			0.350	21
Wall 3: Wood Frame, 16" o.c. Orientation: Right Side	738	19.0	0.0		42
Window 3: Vinyl Frame:Double Pane with Low-E SHGC: 0.27 Orientation: Right Side	46			0.350	16
Wall 4: Wood Frame, 16" o.c. Orientation: Back	684	19.0	0.0		33
Window 4: Vinyl Frame:Double Pane with Low-E SHGC: 0.27 Orientation: Back	138			0.350	48
over crawl: All-Wood Joist/Truss:Over Unconditioned Space	1040	19.0	0.0		49
over garage: All-Wood Joist/Truss:Over Unconditioned Space	394	19.0	0.0		19
over ambient: All-Wood Joist/Truss:Over Outside Air	12	19.0	0.0		1

Compliance Statement: The proposed building design described here is consistent with the building plans, specifications, and other calculations submitted with the permit application. The proposed building has been designed to meet the North Carolina Energy Conservation Code requirements in REScheck Version 4.6.4 and to comply with the mandatory requirements listed in the REScheck Inspection Checklist.

Project Title: Prelude Plan crawl Report date: 03/19/18

Data filename: C:\Users\Justin\Desktop\SEM files\REM files\H&H Homes\RESchecks\H&H Homes-Prelude Plan crawl-CZ 4-worst case.rck Page 1 of 6

ame - Title	Signature	Date



## REScheck Software Version 4.6.4

## **Inspection Checklist**

North Carolina Energy Conservation Code Lillington, North Carolina Single Family New construction Energy Code: Location:

Construction Type: Project Type:

Bldg. faces 90 deg. from North Building Orientation:

Glazing Area Percentage: Heating Degree Days: 12% 3502 Climate Zone: 4

Floors:

Ceilings:  Ceiling 1: Flat Ceiling or Scissor Truss, R-26.0 cavity + R-12.0 continuous insulation  Comments:
Above-Grade Walls: Wall 1: Wood Frame, 16" o.c., R-19.0 cavity insulation Comments:
Wall 2: Wood Frame, 16" o.c., R-19.0 cavity insulation  Comments:
Wall 3: Wood Frame, 16" o.c., R-19.0 cavity insulation  Comments:
Wall 4: Wood Frame, 16" o.c., R-19.0 cavity insulation  Comments:
Windows:  Window 1: Vinyl Frame:Double Pane with Low-E, U-factor: 0.350, SHGC: 0.27,  For windows without labeled U-factors, describe features:  #Panes Frame Type Thermal Break? Yes No  Comments:
Window 2: Vinyl Frame:Double Pane with Low-E, U-factor: 0.350, SHGC: 0.27,  For windows without labeled U-factors, describe features:  #Panes Frame Type Thermal Break? Yes No  Comments:
Window 3: Vinyl Frame:Double Pane with Low-E, U-factor: 0.350, SHGC: 0.27,  For windows without labeled U-factors, describe features:  #Panes Frame Type Thermal Break? Yes No  Comments:
Window 4: Vinyl Frame:Double Pane with Low-E, U-factor: 0.350, SHGC: 0.27,  For windows without labeled U-factors, describe features:  #Panes Frame Type Thermal Break? Yes No  Comments:
Doors:  Door 1: Solid, U-factor: 0.200  Comments:
Door 2: Solid, U-factor: 0.200 Comments:

Project Title: Prelude Plan crawl Report date: 03/19/18 Data filename: C:\Users\Justin\Desktop\SEM files\REM files\H&H Homes\Prelude Plan crawl-CZ 4-worst

case.rck

	over crawl: All-Wood Joist/Truss:Over Unconditioned Space, R-19.0 cavity insulation
	Comments:
	Floor insulation is installed to maintain permanent continuous contact with the underside of the subfloor decking, and insulation ends are blocked. Insulation supports that are noncontinuous (i.e., tension support wires) are spaced no more than 18 inches apart and are within 6 inches from each end of the insulation.
	over garage: All-Wood Joist/Truss:Over Unconditioned Space, R-19.0 cavity insulation
	Comments:Floor insulation is installed to maintain permanent continuous contact with the underside of the subfloor decking, and insulation ends are blocked. Insulation supports that are noncontinuous (i.e., tension support wires) are spaced no more than 18 inches apart and are within 6
	inches from each end of the insulation.
Ц	over ambient: All-Wood Joist/Truss:Over Outside Air, R-19.0 cavity insulation  Comments:
	Floor insulation is installed to maintain permanent continuous contact with the underside of the subfloor decking, and insulation ends are blocked. Insulation supports that are noncontinuous (i.e., tension support wires) are spaced no more than 18 inches apart and are within 6 inches from each end of the insulation.
	Solar Heat Gain Coefficient:
	Solar Heat Gain Coefficient (SHGC) values are determined in accordance with the NFRC test procedure or taken from the default table.
	Air Leakage:
	Joints (including rim joist junctions), attic access openings, penetrations, and all other such openings in the building envelope that are sources of air leakage are sealed with caulk, gasketed, weatherstripped or otherwise sealed with an air barrier material, suitable film or solid material.
	Air barrier and sealing exists on common walls between dwelling units, on exterior walls behind tubs/showers, and in openings between window/door jambs and framing.
	Recessed lights in the building thermal envelope are 1) type IC rated and ASTM E283 labeled and 2) sealed with a gasket or caulk between the housing and the interior wall or ceiling covering.
	Access doors separating conditioned from unconditioned space (e.g., attic, unconditioned basements and crawlspaces) are weather-stripped and insulated (without insulation compression or damage). Where loose fill insulation exists, a wood framed or equivalent baffle is installed to maintain insulation application. Required insulation values are as follows:
	(1) Hinged vertical doors have a minimum of R-5 insulation.
	(2) Hatches/scuttle hole covers have a minimum of R-10 insulation.
	(3) Pull down stairs have a minimum of R-5 rigid insulation.
	Site-built masonry fireplaces have doors and comply with Section R1006 of the North Carolina Residential Code for combustion air.
	Air Sealing and Insulation:
	Building envelope air tightness and insulation installation complies with one of the following (mark the method that was applied):
	(1) Post rough-in blower door test result of less than or equal to 5 ACH at 50 pascals.
	(2) Post rough-in blower door test result of less than or equal to 0.30 CFM50/square foot of surface area.
	(3) Visual inspection. The following items, along with all other air leakage requirements in this report, are certified by the builder, permit holder or registered design professional as completed.
	(a) Ceiling/attic: Sealants or gaskets provide a continuous air barrier system joining the top plate of framed walls with either the ceiling drywall or the top edge of wall drywall to prevent air leakage. Top plate penetrations are sealed.
	(b) Ceiling/attic: For ceiling finishes that are not air barrier systems such as tongue-and-groove planks, air barrier systems (e.g., taped house wrap) are used above the finish.
	(c) Above Grade Walls: Sill plate is gasketed or sealed to subfloor or slab.
	(d) Windows/doors: Space between window and door jambs and framing are sealed.
	(e) Floors: Air barrier system is installed at any exposed edge of insulation.
	Sunrooms:
	Sunrooms that are thermally isolated from the building envelope have a maximum fenestration U-factor of 0.40 and the maximum skylight U-factor of 0.75.
	Sunrooms with cooling systems shall have a maximum fenestration SHGC or 0.40 for all glazing.
	Materials Identification and Installation:
	Materials and equipment are installed in accordance with the manufacturer's installation instructions.
	Materials and equipment are identified so that compliance can be determined.
	Manufacturer manuals for all installed heating and cooling equipment and service water heating equipment have been provided.
	Insulation R-values and glazing U-factors are clearly marked on the building plans or specifications.

Project Title: Prelude Plan crawl

Report date: 03/19/18

Data filename: C:\Users\Justin\Desktop\SEM files\REM files\H&H Homes\RESchecks\H&H Homes-Prelude Plan crawl-CZ 4-worst

	Ouct Insulation:
	Supply and return ducts in unconditioned space and outdoors are insulated to R-8. Supply ducts inside semi-conditioned space are insulated to R-4.
[	Ouct Construction and Testing:
	Building framing cavities are not used as supply ducts.
	All joints and seams of air ducts, air handlers, filter boxes, and building cavities used as return ducts are sealed. Joints and seams comply with Part V - Mechanical, Section 603.9 of the North Carolina Residential Code.
	Postconstruction total duct leakage test (including air handler enclosure) has been performed and results are less than or equal to 146.1 cfm (6 cfm per 100 ft2 of conditioned floor area) pressure differential of 0.1 inches w.g. Tests are performed according to North Carolina Energy Conservation Code guidelines (Section 403.2.2).
7	Femperature Controls:
	Where the primary heating system is a forced air-furnace, at least one programmable thermostat is installed to control the primary heating system and has set-points initialized at 70 degree F for the heating cycle and 78 degree F for the cooling cycle.
	Heat pumps having supplementary electric-resistance heat have controls that prevent supplemental heat operation when the compressor can meet the heating load.
ŀ	leating and Cooling Equipment Sizing:
	Heating and cooling equipment shall be sized in accordance with the North Carolina Mechanical Code.
	For systems serving multiple dwelling units documentation has been submitted demonstrating compliance with 2009 IECC Commercial Building Mechanical and/or Service Water Heating (Sections 503 and 504).
(	Circulating Service Hot Water Systems:
	Circulating service hot water pipes are insulated to R-2.
	Circulating service hot water systems include an automatic or accessible manual switch to turn off the circulating pump when the system is not in use.
H	leating and Cooling Piping Insulation:
	HVAC piping conveying fluids above 105 degrees F or chilled fluids below 55 degrees F are insulated to R-3.
5	Swimming Pools:
	Heated swimming pools have an on/off heater switch.
	Pool heaters operating on natural gas or LPG have an electronic pilot light.
	Timer switches on pool heaters and pumps are present.  Exceptions:
	Where public health standards require continuous pump operation.
	Where pumps operate within solar- and/or waste-heat-recovery systems.
	Heated swimming pools and in-ground permenantly installed spas have a vapor-retardent cover.  Exceptions:
	Covers are not required when 70% of the heating energy is from site-recovered energy or solar energy source.
L	ighting Requirements:
	A minimum of 75 percent of the lamps in permanently installed lighting fixtures can be categorized as one of the following:
	(a) Compact fluorescent
	(b) T-8 or smaller diameter linear fluorescent
	(c) 40 lumens per watt for lamp wattage <= 15
	(d) 50 lumens per watt for lamp wattage > 15 and <= 40
	(e) 60 lumens per watt for lamp wattage > 40
(	Other Requirements:
	Snow- and ice-melting systems with energy supplied from the service to a building shall include automatic controls capable of shutting off the system when a) the pavement temperature is above 50 degrees F, b) no precipitation is falling, and c) the outdoor temperature is above 40 degrees F (a manual shutoff control is also permitted to satisfy requirement 'c').
(	Certificate:
	A permanent certificate is provided on or in the electrical distribution panel listing the predominant insulation R-values; window U-factors; type and efficiency of space-conditioning and water heating equipment. The certificate does not cover or obstruct the visibility of the circuit directory label, service disconnect label or other required labels.

NOTES TO FIELD: (Building Department Use Only)

Project Title: Prelude Plan crawl

Report date: 03/19/18

Data filename: C:\Users\Justin\Desktop\SEM files\REM files\H&H Homes\RESchecks\H&H Homes-Prelude Plan crawl-CZ 4-worst case.rck

Page 5 of 6

Insulation Rating	R-Value		
Ceiling / Roof	38.00		
Above-Grade Wall	19.00		
Below-Grade Wall	0.00		
Floor	19.00		
Ductwork (unconditioned spaces):			
Glass & Door Rating	U-Factor	SHGC	
Window	0.35	0.27	
Door	0.20	NA	
Heating & Cooling Equipment	Efficiency		
Heating System:			
Cooling System:			
Water Heater:			
Building Air Leakage and Duct Test Results			
Air Leakage Compliance Method:	Visual In	spection	
	Air Leak	age Test	
Building Air Leakage Test Results			
Name of Air Leakage Tester			
<b>Duct Tightness Test Results</b>			
Name of Duct Tester			
Name of Duct Tester			

Date: \_

Comments:

Name: