

# Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Lamco Custom Blds PROPERTY LOCATION: 155 Southern Place (Clark Road - SR 1129)  
 SUBDIVISION Currin Plantation LOT # 33

NEW  REPAIR  EXPANSION  Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_

Type of Structure: 3-bedroom 52'x 48' SFD

Proposed Wastewater System Type: 25% Reduction System

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max


Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well NA feet

Permit valid for:  Five years  No expiration

Permit conditions: \_\_\_\_\_

Authorized State Agent:  Date: 04/11/2019 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Lamco Custom Blds PROPERTY LOCATION: 155 Southern Place (Clark Road - SR 1129)  
 SUBDIVISION Currin Plantation LOT # 33

Facility Type: 3-bedroom 52'x 48' SFD  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* 25% Reduction System (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable  25% Reduction System (Repair))

Installation Requirements/Conditions	Number of trenches <u>3</u>	
Septic Tank Size <u>1000</u> gallons	Exact length of each trench <u>75</u> feet	Trench Spacing: <u>3</u> Feet on Center
Pump Tank Size _____ gallons	Trenches shall be installed on contour at a	Soil Cover: <u>14</u> inches
	Maximum Trench Depth of: <u>26</u> inches	(Maximum soil cover shall not exceed
	(Trench bottoms shall be level to +/-1/4"	<u>36"</u> above the trench bottom)
	in all directions)	
Pump Requirements: _____ ft. TDH vs. _____ GPM		Aggregate Depth: <u>NA</u> inches below pipe
		<u>NA</u> inches above pipe
		<u>NA</u> inches total


Conditions: 5ft foundation setback off any proposed deck; Pump sys. req. if plumbing is stubbed high

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent:  Date: 04/11/2019  
Andrew Curran Construction Authorization Expiration Date: 04/11/2024

HTE# SFD 1903-0044

Permit # NA

# Harnett County Department of Public Health Site Sketch

521129

PROPERTY LOCATOR: 155 Southern Pl. (Clark Road)


ISSUED TO: Lanico Custom Bldg

SUBDIVISION Carrin Plantation

LOT # 33

Authorized State Agent: *Andrew Curran*  
ANDREW CURRAN

Date: 04/11/2019



- \* 5ft setback off proposed deck foundation
- \* Relatively flat lot w/ micro contour variance
- \* Pump may be required if plumbing is stubbed to high
- \* Use trench depth to meet contour variance