HTE# 18-544000 SFD1905-0074

Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit		
ISSUED TO: ATLANTIC CONSTRUCTION SUBDIVISION 55 WEST NATER LOT # 23		
NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:		
Type of Structure: SFD (50×50)	51×37′)	
Proposed Wastewater System Type: Pune To 25	1% AGDUCTION System	
Projected Daily Flow:GPD	0	
Number of bedrooms: Number of Occup	ants:max	
Basement □Yes ☒ No Pump Required: ☒Yes □ No □ May be requi	red based on final location and elevations of facilities	
Type of Water Supply: Community Public		Five years
Permit conditions:		☐ No expiration
Authorized State Agent:		ACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The impresement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of		
the Laws and Rules for Sewage Treatment and Disposal and to condition	s of this permit.	
	Construction Authorization	
	(Required for Building Permit)	
The construction and installation requirements of Rules .1950, .1952, .19	54, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems	shall be installed in accordance
with the attached system layout. IVERCON INC		
ISSUED TO: ATLANTIC CONSTON	PROPERTY LOCATION: WILL LUCAS SUBDIVISION SWEETWATER	
151	SUBDIVISION SWEETWATER	LOT # 2-3
Facility Type: SFD (SCASO) Repair		
Basement? Yes No Basement Fixtures? Yes No		
Type of Wastewater System** Pune To 25% REDUCTION System (Initial) Wastewater Flow: 480 GPD		
(See note below if applicable)		
Pumplo	Number of trenches	
Installation Requirements/Conditions	Number of trenches	
Septic Tank Size <u>1000</u> gallons	Exact length of each trench 240 feet Trench Spacing: 9	Feet on Center
Pump Tank Size\OOO gallons	Trenches shall be installed on contour at a Soil Cover: 12-27	inches
	Maximum Trench Depth of: 24-36 inches (Maximum soil cover shall r	not exceed
	(Trench bottoms shall be level to +/-1/4" 36" above the trench bottoms	com)
	in all directions)	
Pump Requirements:ft. TDH vs		inches below pipe
	Aggregate Depth:	inches above pipe
Conditions:		inches total
WATER LINES (INCLUDING IRRIGATION) MUST B	E 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.	
NO UTILITIES ALLOWED IN INITIAL OR REPAIR D		
**If applicable: I understand the system type specified	is different from the type specified on the application I assert the specifications of	46 is a summit
**If applicable:_/ understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.		
/ner/Legal Representative Signature: Date:		
Owner/Legal Representative Signature:		
Construction Authorization is subject to compliance with the provisions of	the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.	ATTACHED SITE SKETCH
	1.1	
Authorized State Agent: Construction Authorization Expiration Date: 6 5 23 38 38 39 39 39 39 39 3		
वकार होस्त्रोव	Construction Authorization Expiration Date: 6 5 3	

HTE# 18-5-44060

Permit # 30112

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATON: WILL LUCAS

ISSUED TO: PTLANTIC CONSTRUCTION SUBDIVISION SWEETWATER LOT # 23

Authorized State Agent: Date: 6 5 18

THIS DRAWING IS FOR ILLUSTRATIVE PROPOSES ONLY

SYSTEM INSTALLATION MUST MEET ALL PERTINENT LAWS, RULES, AND REGULATIONS

RECTIONS 6 22 19

