



System:   
 Repair:

- \*Keep tanks and drain lines 10' from property lines.
- \*Not a survey.
- \*Not a guarantee of a septic permit.
- \*Keep supply lines >5' from property lines.
- \*Some lines are flagged longer in the field than lengths indicate.
- \*No grading septic area.

GRAPHIC SCALE  
 1" = 50'



System: Pressure Manifold  
 Lines: 2-4, (350')  
 Accepted Status System  
 0.35 Soil LTAR  
 18" Trench Bottom

Repair: Pressure Manifold  
 Lines: 5-8, (390')  
 Accepted Status System  
 0.35 Soil LTAR  
 18" Trench Bottom



Central Carolina Soil Consulting, PLLC  
 1900 South Main Street, Suite 110  
 Wake Forest, North Carolina 27587  
 Phone (919)569-6704 Fax (919)569-6703

4-Bedroom Septic Layout  
 Lot 6, Masons Pointe Subdivision  
 Harnett County, North Carolina

Job# : 2031  
 Drawn By : AH & TMB  
 Date : 04/22/2019  
 Revision: 10/23/2019