

# Harnett County Department of Public Health Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Southeastern Const. of Bases Creek SUBDIVISION Prop. of BC LLC 2017 LOT # 8  
 PROPERTY LOCATION: 1591 Main Street (sn 1532)  
 NEW  REPAIR  EXPANSION   
 Type of Structure: 3-Bedroom 28'x54' SFD  
 Proposed Wastewater System Type: 25% reduction sys.  
 Projected Daily Flow: 360 GPD  
 Number of bedrooms: 3 Number of Occupants: 6 max  
 Basement  Yes  No  
 Pump Required:  Yes  No  May be required based on final location and elevations of facilities  
 Type of Water Supply:  Community  Public  Well Distance from well 50+ feet  
 Permit valid for:  Five years  No expiration  
 Permit conditions: \_\_\_\_\_

Authorized State Agent: [Signature] Date: 12/04/2019 SEE ATTACHED SITE SKETCH  
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization (Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Southeastern Const. of Bases Creek PROPERTY LOCATION: 1591 Main Street (sn 1532)  
 SUBDIVISION Prop. of BC LLC 2017 LOT # 8  
 Facility Type: 3BR 28'x54' SFD  New  Expansion  Repair  
 Basement?  Yes  No Basement Fixtures?  Yes  No  
 Type of Wastewater System\*\* 25% reduction system (Initial) Wastewater Flow: 360 GPD  
 (See note below, if applicable   
25% reduction system (Repair)

**Installation Requirements/Conditions**  
 Septic Tank Size 1000 gallons  
 Pump Tank Size \_\_\_\_\_ gallons  
 Number of trenches 4  
 Exact length of each trench 60 feet  
 Trenches shall be installed on contour at a  
 Maximum Trench Depth of: 18-26 inches  
 (Trench bottoms shall be level to +/-1/4"  
 in all directions)  
 Trench Spacing: 9 Feet on Center  
 Soil Cover: 6-14 inches  
 (Maximum soil cover shall not exceed  
 36" above the trench bottom)  
 Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM  
 Aggregate Depth: NA inches below pipe  
NA inches above pipe  
NA inches total  
 Conditions: Install shallow (18") to deep (26") to keep uphill

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.  
 Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 12/04/2019  
 Construction Authorization Expiration Date: 12/04/2024


Application # SFD1911-0032

# Harnett County Department of Public Health Site Sketch

Property Location: 1591 Main Street (SN 1532)

Issued To: SOUTHEASTERN CONST. OF B.C. Subdivision Prop. of B.C. LLC 2019 Lot # 8

Authorized State Agent: ANDREW CURRIN Date: 12/05/2019



\* INSTALL SFS. AS TIGHT TO LEFT P.O.L. AS CONTOUR ALLOWS [10FT MIN SETBACK]

\* INSTALL SHALLOW (18IN) TO DEEP (26IN) TO KEEP INSTALL WHILL

\* POWER SHALL BE ROUTED WITH 5FT OF EITHER PROPERTY LINE

This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.