North Carolina 2018 - R402.1.5 Total UA

Property

53 Norris Farm Drive Angier , NC 27501 Model: 2098 Devin I-01 2

Community: Norris Farm

True_Norris Farm 2_2098 Devin I-01

Norris Farm 2

Organization

Performance Point, LLC. 704-614-7175 Rick Blair

Builder

True Homes

Inspection Status
Results are projected

Building UA

| Elements | NC Reference | As Designed |
|---|--------------|-------------|
| Ceilings | 38.9 | 33.5 |
| Above-Grade Walls | 176.4 | 178.9 |
| Windows, Doors and Skylights | 85.5 | 71.3 |
| Slab Floor: | 84.2 | 84.2 |
| Framed Floors | 0.0 | 0.0 |
| Foundation Walls | 0.0 | 0.0 |
| Rim Joists | 6.7 | 6.6 |
| Overall UA (Design must be equal or lower): | 391.7 | 374.5 |

Requirements

| 0 | 402.1.5 | Total UA alternative for insulation and fenestration | 1 |
|----------|-------------------------------------|--|---|
| | 402.3.2 Glazed Fenestration SHGC | Average SHGC: 0.30 Max SHGC: 0.30 | |
| 0 | R402.4.2.2 | Air Leakage Testing | Air sealing is 5.00 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa. |
| | R402.5 | Area-weighted average fenestration SHGC | |
| 0 | R402.5 | Area-weighted average fenestration U-Factor | |
| 2 | R404.1 | Lighting Equipment Efficiency | |
| 0 | Mandatory Checklist | Mandatory code requirements that are not checked by Ekotrope must be met | |
| | R403.3 | Duct Insulation | |
| 0 | 403.3.3 | Duct Testing | |

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 4.4%.

| Name: | Rick Blair | Signature: | 12/152 |
|---------------|-------------------------|-------------------|--------------------|
| Organization: | Performance Point, LLC. | Digitally signed: | 12/2/19 at 4:55 PM |

Property

53 Norris Farm Drive Angier , NC 27501 Model: 2098 Devin I-01_2 Community: Norris Farm Organization

Performance Point, LLC. 704-614-7175 Rick Blair Inspection Status Results are projected

True Norris Farm 2 2098 Devin I-01

Norris Farm 2

Builder

True Homes

General Building Information

Conditioned Area (sq ft) Conditioned Volume (cubic ft) Insulated Shell Area (sq ft) 2,095.8 19,058.98 5,246.9

The building energy model in Ekotrope reflects the building assemblies and energy features listed below. Sometimes energy features will change in the field from what has been modeled. The inspection process should identify any changes and ensure that the home continues to meet the applicable energy code.

| | Name: House Slab(1,295.8 s.f., 172 ft. exterior perimeter) |
|-------------------|--|
| \longrightarrow | R-10 perimeter insulation, R-0 under slab insulation. |

Framed Floor

None Present

Foundation Wall

None Present

Above Grade Wall

| Name: 2x4 Ambient (1,955.8 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I |
|--|
| Name: 2x4 Garage (361.1 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I |
| Name: 2x4 Knee wall (218.4 s.f.) R-0 continuous insulation, R-15 cavity insulation Insulation Grade: I |

Rim Joist

| Property 53 Norris Farm Drive Angier , NC 27501 Model: 2098 Devin I-01_2 Community: Norris Farm | | Organization Performance Point, LLC. 704-614-7175 Rick Blair | Inspection Status Results are projected | | |
|---|--|--|---|---|--|
| | Norris Farm 2_2098 Devin I-01 Farm 2 | Builder True Homes | | | |
| | Name: Ambient (74.5 s.f.) R: 13.30 | | | | |
| | Name: Attic (45.5 s.f.) R: 13.30 | | | | |
| Roof | f | | | | |
| | Name: 1 st FL/ Ceiling (495.8 s.f. R-28.5 continuous insulation, R-9 Insulation Grade: I | | | | |
| | Name: 2nd FL/ Ceiling (800 s.f.) R-28.5 continuous insulation, R-9.5 cavity insulation Insulation Grade: I | | | | |
| Opa | que Door | | | | |
| | Name: Front door (20 s.f.) R: 7.00 | | | | |
| | Name: Garage door (17.8 s.f.) R: 7.00 | | | | |
| | Name: Attic Door (17.8 s.f.) R: 5.00 | | | | |
| Glaz | ing | | | | |
| П | Name: Front (45 s.f.), U: 0.330, | SHGC: 0.3, Orientation: W | EST | | |
| | Name: Front sh (30 s.f.), U: 0.3 | 30, SHGC: 0.3, Orientation | WEST | | |
| | Name: Left (15 s.f.), U: 0.330, | SHGC: 0.3, Orientation: NO | PRTH | | |
| П | Name: Back (75 s.f.), U: 0.330, | SHGC: 0.3, Orientation: EA | AST | 2 | |

Organization Inspection Status Property 53 Norris Farm Drive Performance Point, LLC. Results are projected Angier, NC 27501 704-614-7175 Model: 2098 Devin I-01 2 Rick Blair Community: Norris Farm Builder True Norris Farm 2 2098 Devin I-01 True Homes Norris Farm 2 Name: Back door (17.8 s.f.), U: 0.330, SHGC: 0.3, Orientation: EAST Name: Right (6 s.f.), U: 0.330, SHGC: 0.3, Orientation: SOUTH Skylight None Present Mechanical Ventilation None Present Mechanical Equipment Air-source heat pump • Electric • 100% Heating Load @ 8.2 HSPF, 100% Cooling Load @ 14 SEER Water Heating • Electric • 100% Hot Water Load @ 0.95 Energy Factor Air Leakage Control

Infiltration Requirements for IECC in Climate Zone 4

Test Status: Blower-door tested

2009 IECC Infiltration limit for the design home is 7 ACH50.

House is air-sealed as to achieve 1,588 CFM50 (5.00 ACH50) or less at final blower-door test.

2012 IECC Infiltration limit for the design home is 3 ACH50.

2015 IECC Infiltration limit for the design home is 3 ACH50.

Duct Leakage

Duct System 1

NOT entirely within conditioned space, testing required Leakage to Outside specified as: 4 CFM25 / 100 ft² Total Leakage specified as: 4 CFM25 / 100 ft² (Post-Construction)

Property

53 Norris Farm Drive Angier , NC 27501 Model: 2098 Devin I-01 2

Community: Norris Farm

True_Norris Farm 2_2098 Devin I-01 Norris Farm 2 Organization

Performance Point, LLC. 704-614-7175 Rick Blair

Builder

True Homes

Inspection Status Results are projected

Duct Leakage Code Requirements for IECC

2009 IECC:

Postconstruction Leakage Test: Duct Leakage to Outdoors <= 8 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 6 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

2012 IECC and 2015 IECC Prescriptive Path:

Postconstruction Leakage Test: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test with AHU: Total Duct Leakage <= 4 CFM25 / 100 sq ft CFA.

Rough in Test without AHU: Total Duct Leakage <= 3 CFM25 / 100 sq ft CFA.

2015 Performance Path (Cost Compliance):

Leakage testing is required UNLESS all ducts and air handlers are located entirely within the thermal envelope.

There is no pass/fail threshold for duct leakage on the performance path.

Project Notes

DG 12/02/19

-Changed: Slab to R10 2' down, walls to R15, ceiling to R38, set duct location %

-Used worst orientation (current = west)

HG_11/28/2019___N/S Performance Report True 2098 Devin I-01 2

Energy Specifications Label 53 Norris Farm Drive

Model: 2098 Devin I-01_2 Ekotrope RATER - Version: 3.2.2.2306

Building Envelope Specs

Ceiling: R-38

Above Grade Walls: R-15 Foundation Walls: N/A Exposed Floor: N/A

Slab: R-10

Infiltration: 5 ACH50 Duct Insulation: R-8

Duct Lkg to Outdoors: 4 CFM25 / 100 ft2

Window & Door Specs

U-Value: 0.33, SHGC: 0.3

Door: R-7

Mechanical Equipment Specs

Heating: Air Source Heat Pump • Electric • 8.2

HSPF

Cooling: Air Source Heat Pump • Electric • 14

SEER

Hot Water: Water Heater • Electric • 0.95 Energy

Factor

Builder or Design Professional

Signature: