

Adams Soil Consulting
1676 Mitchell Road
Angier, NC 27501
919-414-6761

February 12, 2020
Project #868

Mark Walton

RE: Preliminary soil/site evaluation for a 5.0-acre lot for a minor subdivision for Joshua M. Quinn and Mark Walton adjacent to Joe Collins Road in Harnett County.

Mr. Walton,

Adams Soil Consulting (ASC) conducted a preliminary soil evaluation on the above referenced parcel to determine the areas of soils which are suitable for subsurface wastewater disposal systems (conventional & LPP). The soil/site evaluation was performed using hand auger borings during moist soil conditions and the suitable soil boundary was sketched onto a preliminary plat supplied by Lambert Surveying, Inc.

The suitable soils shown on the accompanying soil map have potential for a conventional type initial and repair area for at least one 4-bedroom home site. The lot contains greater than 30,000 ft² of suitable soils that consist of sandy clay loam subsoil that can support a daily loading rate of 0.3-0.4 gallons/day/ft². The lot should accommodate a house foot print of at least 60' x 60'.

The specific septic system and/or repair system will be permitted by the Harnett County Health Department. Additionally, the Harnett County Health Department will establish the loading rates for any proposed system. The areas for the proposed septic fields shall not be impacted by home sites, pools, garages and shall not be mechanically altered from the natural lay of the land.

The lot will require a detailed soils evaluation by the Harnett County Health Department prior to issuance of any permits for a septic system. A septic system layout may be required before a permit can be issued on the above referenced lot demonstrating available space for the primary and repair septic areas. Due to the subjective nature of the permitting process and the variability of naturally occurring soils, Adams Soil Consulting cannot guarantee that areas delineated as suitable for on-site wastewater disposal systems will be permitted by the governing agency. The lot may require a septic system utilizing pumps, shallow or ultra-shallow conventional trench placement, low pressure pipe system, and/or reductions system for final approval. The accompanying soil map is preliminary in nature, no further assumptions or subdivision should be made without a more detailed evaluation.

If you have any questions regarding the findings on the attached map or in this report, please feel free to contact me anytime. Thank you allowing me to perform this site evaluation for you.

Sincerely,



Alex Adams
NC Licensed Soil Scientist #1247

