



ROOF & FLOOR TRUSSES & BEAMS

Reilly Road Industrial Park
 Fayetteville, N.C. 28309
 Phone: (910) 864-8787
 Fax: (910) 864-4444

Bearing reactions less than or equal to 3000# are deemed to comply with the prescriptive Code requirements. The contractor shall refer to the attached Tables (derived from the prescriptive Code requirements) to determine the minimum foundation size and number of wood studs required to support reactions greater than 3000# but not greater than 15000#. A registered design professional shall be retained to design the support system for any reaction that exceeds those specified in the attached Tables. A registered design professional shall be retained to design the support system for all reactions that exceed 15000#.


Signature *Christine Shivy*

Christine Shivy

LOAD CHART FOR JACK STUDS

(BASED ON TABLES R502.5(1) & (b))
 NUMBER OF JACK STUDS REQUIRED @ EA END OF HEADER/GIRDER

END REACTION (UP TO)	REQ'D STUDS FOR (1) PLY HEADER	END REACTION (UP TO)	REQ'D STUDS FOR (1) PLY HEADER	END REACTION (UP TO)	REQ'D STUDS FOR (1) PLY HEADER
1700	1	2550	1	3400	1
3400	2	5100	2	6800	2
5100	3	7650	3	10200	3
6800	4	10200	4	13600	4
8500	5	12750	5	17000	5
10200	6	15300	6		
11900	7				
13600	8				
15300	9				



● = HUS410 (Qty. 11)

▲ = Denotes Left End of Truss
 (Reference Engineered Truss Drawing)

PlotID	Length	Product	Plies	Net Qty
GDH (Dropped)	21' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2
GDH-3 (Dropped)	13' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2
BM2 (Dropped)	9' 0"	1-3/4"x 11-7/8" LVL Kerto-S	2	2
BM1 (Flush) (Rip To 13")	14' 0"	1-3/4"x 14" LVL Kerto-S	2	2
BM3 (Flush)	5' 0"	1-3/4"x 16" LVL Kerto-S	2	2
BBO (Stairway)(Flush)	4' 0"	2x10 SP No.2	2	2

Truss Placement Plan
SCALE: 3/16" = 1'-0"

All Truss Reactions are Less than 3,000 lbs. Unless Noted Otherwise.

○ -- Denotes Reaction Greater than 3,000 lbs.
 Reaction / # of Studs

BUILDER	JOB NAME	PLAN	SEAL DATE	QUOTE #	JOB #
Wellons Realty Inc.	Johnston Co. / Johnston	Address	Model	Christine Shivy	J0320-1371
	Job Name	Site Address	Model	Christine Shivy	
	Avery (200310B)	/	/	Lenny Norris	

THIS IS A TRUSS PLACEMENT DIAGRAM ONLY. These trusses are designed as individual building components to be incorporated into the building design at the specification of the building designer. See individual design sheets for each truss design identified on the placement drawing. The building designer is responsible for temporary and permanent bracing of the roof and floor system and for the overall structure. The design of the truss support structure including headers, beams, walls, and columns is the responsibility of the building designer. For general guidance regarding bracing, consult BCSI-B1 and BCSI-B3 provided with the truss delivery package or online @ sbcindustry.com