

Client:

Signature Home Builders

Project:

Address: 215 Joe Collins Road

Lillington, NC


3/20/2020

Designer: Anthony Williams Job Name: Centrella Residence Page 1 of 4

Project #:

1.750" X 16.000" 2-Ply - PASSED **Kerto-S LVL**

Level: Level



| Member Inforn | nation | | | Reaction | ns UNPAT | TERNED I | (Uplift) | | |
|---------------------|---------------|-----------------|--------------|----------------|----------|----------|-----------|----------------|-------------|
| Type: | Girder | Application: | Floor | Brg | Live | Dead | Snow | Wind | Const |
| Plies: | 2 | Design Method: | ASD | 1 | 2829 | 3773 | 2054 | 0 | 0 |
| Moisture Condition: | Dry | Building Code: | IBC/IRC 2015 | 2 | 2829 | 3773 | 2054 | 0 | 0 |
| Deflection LL: | 480 | Load Sharing: | No | | | | | | |
| Deflection TL: | 360 | Deck: | Not Checked | | | | | | |
| Importance: | Normal | | | | | | | | |
| Temperature: | Temp <= 100°F | | | Page singer | | | | | |
| | | | | Bearings | 5 | | | | |
| | | | | Bearing | Length | Cap. Rea | ct D/L lb | Total Ld. Case | Ld. Comb. |
| | | | | 1 - SPF End | 3.500" | 70% 37 | 73 / 3662 | 7435 L | D+0.75(L+S) |
| Analysis Result | S | | | Grain | | | | | |
| Analysis Act | | n Allowed Capac | • | 2 - SPF End | 3.500" | 70% 37 | 73 / 3662 | 7435 L | D+0.75(L+S) |

Grain

| Analysis | Actual | Location | Allowed | Capacity | Comb. | Case |
|--------------|---------------|------------|---------------|-----------------|-------------|------|
| Moment | 21409 ft-lb | 6'11" | 34565 ft-lb | 0.619 (62%) | D+L | L |
| Unbraced | 24112 ft-lb | 6'11" | 24173 ft-lb | 0.997 (100%) | D+0.75(L+S) | L |
| Shear | 5951 lb | 1'6 5/8" | 11947 lb | 0.498 (50%) | D+L | L |
| LL Defl inch | 0.185 (L/869) | 6'11 1/16" | 0.335 (L/480) | 0.550 (55%) | 0.75(L+S) | L |
| TL Defl inch | 0.376 (L/428) | 6'11 1/16" | 0.447 (L/360) | 0.840 (84%) | D+0.75(L+S) | L |

Design Notes

- 1 Fasten all plies using 4 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 4'8 1/4" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| . Latera elema | onnece rame bacea en emigie | p., | | | | | | | | | |
|----------------|-----------------------------|----------|------------|-----------|----------|---------|-----------|----------|-------------|----------|--|
| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments | |
| 1 | Uniform | | | Near Face | 136 PLF | 409 PLF | 0 PLF | 0 PLF | 0 PLF | FLOOR | |
| 2 | Uniform | | | Тор | 219 PLF | 0 PLF | 219 PLF | 0 PLF | 0 PLF | B2 | |
| 3 | Uniform | | | Far Face | 78 PLF | 0 PLF | 78 PLF | 0 PLF | 0 PLF | C2 | |
| 4 | Uniform | | | Тор | 100 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | WALL | |
| | Self Weight | | | | 12 PLF | | | | | | |

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

LVL beams must not be cut or drilled
Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

2 Damaged Beams must not be used

- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 12/11/2021

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info





isDesign™

Client:

Signature Home Builders

Project:

Address: 215 Joe Collins Road


Lillington, NC

3/20/2020

Designer: Anthony Williams Job Name: Centrella Residence Page 2 of 4

Project #:

1.750" X 16.000" **Kerto-S LVL** 2-Ply - PASSED Level: Level



Multi-Ply Analysis

Fasten all plies using 4 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

| | | , | , |
|--------------------------|-----------|---|---|
| Capacity | 83.2 % | | |
| Load | 272.5 PLF | | |
| Yield Limit per Foot | 327.4 PLF | | |
| Yield Limit per Fastener | 81.9 lb. | | |
| Yield Mode | IV | | |
| Edge Distance | 1 1/2" | | |
| Min. End Distance | 3" | | |
| Load Combination | D+L | | |
| Duration Factor | 1.00 | | |

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Informing & Installation

 I. VIL beams must not be cut or drilled

 Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 Damaged Beams must not be used

 Design assumes top edge is laterally restrained

 Design assumes top edge is laterally restrained is provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

This design is valid until 12/11/2021

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850

www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info







Client:

Signature Home Builders

Project:

Address:

215 Joe Collins Road Lillington, NC


Date: 3/20/2020


Designer: Anthony Williams Job Name: Centrella Residence

Project #:

Kerto-S LVL 2-Ply - PASSED 1.750" X 16.000"

Level: Level





Page 3 of 4

Member Information

Type: Plies: 2 Moisture Condition: Dry Deflection LL: 480 Deflection TL: 360 Importance: Normal Temperature: Temp <= 100°F

Application: Floor Design Method: ASD **Building Code: IBC/IRC 2015** Load Sharing: No Deck: Not Checked

Reactions UNPATTERNED Ib (Uplift)

| Brg | Live | Dead | Snow | Wind | Const | |
|-----|------|------|------|------|-------|--|
| 1 | 2132 | 3370 | 1931 | 0 | 0 | |
| 2 | 2132 | 3370 | 1931 | 0 | 0 | |

Analysis Results

Analysis Actual Location Allowed Comb. Case Capacity 0.490 (49%) D+0.75(L+S) L Moment 19474 ft-lb 6'6" 39750 ft-lb Unbraced 19474 ft-lb 6'6" 19516 ft-lb 0.998 D+0.75(L+S) L (100%)Shear 4875 lb 1'6 5/8" 11947 lb 0.408 (41%) D+L LL Defl inch 0.129 (L/1169) 6'6" 0.314 (L/480) 0.410 (41%) 0.75(L+S) TL Defl inch 0.272 (L/555) 6'6" 0.419 (L/360) 0.650 (65%) D+0.75(L+S) L

Bearings

Grain

Bearing Length Cap. React D/L lb Total Ld. Case Ld. Comb. 1-SPF 3.500" 3370 / 3047 D+0.75(L+S) 6417 L End Grain 2 - SPF 3.500" 3370 / 3047 6417 L D+0.75(L+S) End

Design Notes

- 1 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6"
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 5'11 5/8" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

| ID | Load Type | Location | Trib Width | Side | Dead 0.9 | Live 1 | Snow 1.15 | Wind 1.6 | Const. 1.25 | Comments |
|----|-------------|----------|------------|-----------|----------|---------|-----------|----------|-------------|----------|
| 1 | Uniform | | | Near Face | 109 PLF | 328 PLF | 0 PLF | 0 PLF | 0 PLF | FLOOR |
| 2 | Uniform | | | Тор | 219 PLF | 0 PLF | 219 PLF | 0 PLF | 0 PLF | В3 |
| 3 | Uniform | | | Far Face | 78 PLF | 0 PLF | 78 PLF | 0 PLF | 0 PLF | C2 |
| 4 | Uniform | | | Тор | 100 PLF | 0 PLF | 0 PLF | 0 PLF | 0 PLF | WALL |
| | Self Weight | | | | 12 PLF | | | | | |

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code
- Damaged Beams must not be used Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 12/11/2021

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info





isDesign™

Client:

Signature Home Builders

Project:

Address:

215 Joe Collins Road Lillington, NC


3/20/2020


Designer: Anthony Williams Job Name: Centrella Residence

Project #:

1.750" X 16.000" 2-Ply - PASSED **Kerto-S LVL**

Level: Level





Page 4 of 4

Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

| 1 | | , | , |
|--------------------------|-----------|---|---|
| Capacity | 89.0 % | | |
| Load | 218.5 PLF | | |
| Yield Limit per Foot | 245.6 PLF | | |
| Yield Limit per Fastener | 81.9 lb. | | |
| Yield Mode | IV | | |
| Edge Distance | 1 1/2" | | |
| Min. End Distance | 3" | | |
| Load Combination | D+L | | |
| Duration Factor | 1.00 | | |

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Informing & Installation

 I. VIL beams must not be cut or drilled

 Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 Damaged Beams must not be used

 Design assumes top edge is laterally restrained

 Design assumes top edge is laterally restrained is provide lateral support at bearing points to avoid lateral displacement and rotation
- This design is valid until 12/11/2021

For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info



