SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: OAKMONT

LOT 305

INITIAL SYSTEM: APPROVED 25% RECUCTION (API)

REPAIR APPROVED 25% REDUCTION

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION PT ON LINE 304/305

NO. BEDROOMS: 3

LTAR 0.8 GPD/FT²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	B	99.84	80'
2A	O	99.42	40'
			120'
2B	O	99.42	40'
3	B	99.17	80'
			120'

Initial system

BY M EAKER

DATE 03/2015

TYPICAL PROFILE

0-40 S/CL (VFR, WGR)

CR 2 >36"

INSTALL AT 18-20"

THERE SHALL BE NO GRADING, CUTTING, LOGGING OR OTHER SOIL DISTURBANCE IN SEPTIC AREA

HOUSE, BOX LIMITED TO 50 FEET (DEEP) BY 60' WIDE