

NOTICE TO CONTRACTOR
 All construction must comply with current NC Building Codes and is subject to field inspection and verification.


APPROVED
 Limited building only review
 Permit holder responsible for full compliance with the code.

05/15/2020



APPROVED: 02-16-20
 REVISED ON: 02-20-20

See notes on foundation page



DATE: 2/20/2020
 SCALE: 1/8" = 1'-0"
 DRAWN BY: SG


SQUARE FOOTAGES (211)
 CRAWL SPACE: 214
 91 FL: 2111
 GARAGE: 508
 PORCHES: 353

CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 00 018 0616 CN #: 28632 VN #: LE111
 LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT


Raleigh/Durham, NC
 182 West Hamlin Road
 Benson, NC 27504
 (811) 261-3482
 www.schumacherhomes.com

SCHUMACHER HOMES

© 1993-2020 SCHUMACHER HOMES OPERATIONS, INC. ALL RIGHTS RESERVED. THE DESIGN AND CONSTRUCTION OF THE HOUSE AND ALL RELATED WORKS ARE THE PROPERTY OF SCHUMACHER HOMES OPERATIONS, INC. THESE DRAWINGS ARE NOT TO BE USED TO CREATE DERIVATIVE WORKS, TECHNICAL DRAWINGS OR TO BUILD A STRUCTURE, REPRODUCED, COPIED, OR MODIFIED IN WHOLE OR PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF SCHUMACHER HOMES, AND SUCH UNAUTHORIZED USE OR COPYING IS A VIOLATION OF UNITED STATES COPYRIGHT LAW AND THAT RESULT IN DAMAGES IN EXCESS OF \$10000 PER ACT OF INFRINGEMENT.



VERONA FRENCH COUNTRY / CUSTOM
 RIGHT ELEVATION
 9' CEILING HEIGHT



VERONA FRENCH COUNTRY / CUSTOM
 LEFT ELEVATION
 9' CEILING HEIGHT

NOTE:
 CONTINUOUS RIDGE VENTS
 ALL ROOF RIDGES

NOTE:
 CONTINUOUS RIDGE VENTS
 ALL ROOF RIDGES


DATE: 2/20/2020
 SCALE: 1/8" = 1'-0"
 DRAWN BY: SG
 PROJ. NO.: 2

SQUARE FOOTAGES (211)
 CRAWL SPACE: 2114
 9' F.L. 2111
 GARAGE: 508
 PORCHES: 353

CUSTOM BUILT FOR:
 CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 000 018 0616 CN #: 28632
 LOCATION:
 LOT 8 FREEDOM LANE
 BROADWAY, NC, 27505
 COUNTY: HARNETT

Raleigh/Durham, NC
 182 West Hamlin Road
 Benson, NC 27504
 (811) 261-3482
 www.schumacherhomes.com

Rachel Schumacher
 SCHUMACHER HOMES



Move location of crawl access

Provide enlarged footings for girder truss support

- FOUNDATION NOTES:**
- BRICK VENEER ALL EXPOSED FOUNDATION
 - BOTTOM OF PIER PADS ELEVATION SHALL BE 2" BELOW BOTTOM OF CONT. FOOTER ELEVATION.
 - CONCRETE 4 MASONRY FOUNDATION WALLS SHALL EXTEND ABOVE FINISHED GRADE ADJACENT TO THE FOUNDATION A MIN. OF 4" WHERE MASONRY VENEER IS USED AND 6" MIN. ELSEWHERE.
 - ALL SILLS, PLATES, OR BAND JOISTS THAT REST ON OR IN CONTACT WITH CONCRETE OR MASONRY EXTERIOR WALLS SHALL REQUIRE THE USE OF PRESSURE PRESERVATIVE TREATMENT.

- PIERS:**
- THE UNSUPPORTED HEIGHT OF MASONRY PIERS SHALL NOT EXCEED 10 TIMES THEIR LEAST DIMENSION. WHEN HOLLOW CONCRETE MASONRY UNITS ARE USED FOR ISOLATED PIERS TO SUPPORT BEAMS AND GIRDERS, THE CELLULAR SPACES SHALL BE FILLED SOLIDLY WITH CONCRETE.

CRAWL SPACE VENT CALCULATIONS:


TOTAL VENTED AREA: 2114
 8"X16" VENT = 128 SQ IN = 0.89 SQFT
 ASSUMED NET FREE AREA = 0.53 SQFT
 TOTAL SQFT VENTILATION NEEDED 2114 / 150 = 18.09
 18.09 / 0.53 = 35 TOTAL VENTS

- GENERAL ELECTRICAL NOTES:**
- GFI'S REQUIRED IN CRAWL SPACE * ACCESS PANEL
 - LIGHTS TO BE WITHIN 6' OF ACCESS PANEL
 - AIR HANDLER/FURNACE LOCATED IN ATTIC
 - ELECTRICAL PANEL TO BE GROUNDED TO THE OUTSIDE
 - WIRE DEDICATED CIRCUIT FOR WELL

SQUARE FOOTAGES (211) CRAWL SPACE: 2114
 91 FL: 2111
 GARAGE: 508
 PORCHES: 353

CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 00 018 0616 CN #: 28632 VN #: LE111
 LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT


VERONA FRENCH COUNTRY / CUSTOM
 FOUNDATION PLAN



CONSTRUCTION NOTES:
 1. 2X8 TREATED SILL PLATE
 2. 1/2" DIAM. X 18" L. ANCHOR BOLTS SHALL EXTEND A MINIMUM OF 1" INTO MASONRY OR CONCRETE AS REQUIRED BY CODE @ 6' O.C. AND 12" FROM ALL CORNERS (2 PER CORNER)
 3. ANCHOR BOLTS TO BE LOCATED IN CENTER 1/3 OF SILL PLATE

VERONA FRENCH COUNTRY / CUSTOM
 BOLT AND PLATE PLAN


DRAWN BY: SG	DATE: 2/20/2020	SCALE: 1/8" = 1'-0"	DWG. # 4
CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE			
JOB #: DU 000 019 0616 CN #: 28632		SQUARE FOOTAGES (211) CRAWL SPACE: 214 91 FL: 2111 GARAGE: 508 PORCHES: 353	
LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT			
Raleigh/Durham, NC 182 West Hamlin Road Benson, NC 27504 (811) 261-3482 www.schumacherhomes.com			
SCHUMACHER HOMES			



- FRAMING NOTES:
1. LEAVE 1/2" BETWEEN EACH END JOIST & RIM JOIST TO ALLOW FOR INSULATION.
 2. INSULATE ALL FRAMED CHANNELS & CORNERS; ALSO, BEHIND EACH TUB AND SHOWER UNIT
 3. INSTALL FIREBLOCK FRAMING IN ALL STAIRWAY CEILINGS
 4. INSTALL ALL TRUSSES, I-JOISTS, LVL'S AND BEAMS PER MANUFACTURER SPECIFICATIONS AND LAY OUTS. DO NOT CUT, NOTCH OR BORE WITHOUT EXACT SPECIFICATIONS.
 5. ALL FRAMING TO BE SOUTHERN YELLOW PINE NO. 2 OR GREATER UNLESS NOTED OTHERWISE
 6. DOUBLE JOISTS SHOULD BE LOCATED UNDER ALL PARTITIONS WHEN THE LENGTH OF THE PARTITION EXCEEDS 1/2 THE SPAN OF THE JOIST
 7. 3-PLY 2X10 JOISTS BELOW FIREPLACES & SOLID SURFACE ISLANDS
 8. ALL DECK MATERIAL TO BE TREATED
 9. PROVIDE DOUBLE 2X10 RIM JOIST WHEN RIM JOIST RUNS PARALLEL TO JOISTS

VERONA FRENCH COUNTRY / CUSTOM
 MAIN FLOOR JOIST PLAN

<p>SCHUMACHER HOMES</p>	CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE		SQUARE FOOTAGES (211) CRAWL SPACE: 214	DATE: 2/20/2020	SCALE: 1/8" = 1'-0"	DRAWN BY: SG	DWG: B
	JOB #: DU 00 019 0616 CN #: 28632 VN #: LE111		91 FL: 2111 GARAGE: 508 PORCHES: 353	© 1993-2020 SCHUMACHER HOMES OPERATIONS, INC. ALL RIGHTS RESERVED. THE DESIGN AND CONSTRUCTION OF THE HOME ARE THE PROPERTY OF SCHUMACHER HOMES. THESE DRAWINGS ARE NOT TO BE USED TO CREATE DERIVATIVE WORKS, TECHNICAL DRAWINGS OR TO BUILD A STRUCTURE, REPRODUCED, COPIED, OR MODIFIED, IN WHOLE OR PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF SCHUMACHER HOMES, AND SUCH UNAUTHORIZED USE OR COPYING IS A VIOLATION OF UNITED STATES COPYRIGHT LAW AND THAT RESULT IN DAMAGES IN EXCESS OF \$10000 PER ACT OF INFRINGEMENT.			
LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT		www.schumacherhomes.com					



GENERAL FRAMING NOTES:


- DRYWALLED OPENINGS TO BE CEILING HEIGHT
- PAINTED TRIM
- HEADERS TO BE 2-PLY 2X10 W/ (1) KING & (2) JACK STUDS UNLESS OTHERWISE NOTED

PLAN NOTES:

- SMOOTH CEILING THROUGHOUT HOME
- PAINTED TRIM
- 5-1/4" BASEBOARDS
- 3-1/4" CASING ON INTERIOR DOORS AND WINDOWS HAVE DRYWALLED RETURNS
- 6-PANEL HOLLOW CORE MOLDED INTERIOR DOORS
- SILVERLINE LOW-E DOUBLE-HUNG VINYL WINDOWS

FLOORING NOTES:

- ALL FLOORING BREAKS OCCUR @ CENTER LINE OF DOOR OPENINGS UNLESS OTHERWISE NOTED
- FLOORING SQUARE FOOTAGES INCLUDE CLOSETS RELATIVE TO THE AREA UNLESS OTHERWISE NOTED
- SOME FLOORING SQUARE FOOTAGES MAY INCLUDE HALLS OR AREAS THAT CONNECT WITHOUT WALL SEPARATION IF THE SAME FINISH IS CONTINUED




DATE: 2/20/2020
 SCALE: 1/8" = 1'-0"
 DRAWN BY: SG
 DUAL: 6

SQUARE FOOTAGES (211)
 CRAWL SPACE: 2114
 1ST FL: 2111
 GARAGE: 508
 PORCHES: 353

CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 00 018 0616 CN # 28632 VN # LE11
 LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT

Raleigh/Durham, NC
 182 West Hamlin Road
 Benson, NC 27504
 (811) 261-3482
 www.schumacherhomes.com

SCHUMACHER HOMES



GENERAL ELECTRICAL NOTES:



- (1) EXISTING SWITCH UPGRADED TO A 3-WAY SWITCH, (1) ADDITIONAL 3-WAY SWITCH AND (1) COACH LIGHT WIRED TO A STANDARD SWITCH ARE INCLUDED WHEN A GARAGE SERVICE DOOR IS PURCHASED
- (1) COACH LIGHT, (1) SWITCH, AND (1) GFI OUTLET ARE INCLUDED WHEN ANY ADDITIONAL DOOR IS PURCHASED, EXCLUDING THE GARAGE SERVICE DOOR
- ALL SMOKE DETECTORS TO BE INTERCONNECTED WITH BATTERY BACKUP
- E3902.11 ARC-FAULT CIRCUIT-INTERRUPTER PROTECTION ALL BRANCH CIRCUITS THAT SUPPLY 120-VOLT, SINGLE-PHASE, 15- AND 20-AMPERE OUTLETS INSTALLED IN FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DEN'S, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS AND SIMILAR ROOMS OR AREAS SHALL BE PROTECTED BY A COMBINATION TYPE ARC-FAULT CIRCUIT INTERRUPTER INSTALLED TO PROVIDE PROTECTION OF THE BRANCH CIRCUIT.
- GARAGE DOOR LOW VOLTAGE WIRING BY ELECTRICIAN
- TWO SEPARATE KITCHEN GENERAL ELECTRIC OUTLET CIRCUITS FED BY NUMBER 12 WIRE AND ON 20 AMP BREAKERS REQUIRED IN KITCHEN
- ALL OUTLETS INSTALLED IN BATHROOMS, GARAGES, & UNFINISHED BASEMENTS SHALL HAVE GFCI PROTECTIONS ALONG WITH OUTLETS LOCATED W/IN 6'-0" OF LAUNDRY, UTILITY & WET BAR SINKS & ALL OUTLETS SERVING KITCHEN COUNTERTOP SURFACES
- ALL OUTLETS TO BE PLACED PER CODE

ADDITIONAL ELECTRICAL NOTES:

- INSTALL ALL BATHROOM LIGHT FIXTURES W/ GLOBES FACING DOWN

VERONA FRENCH COUNTRY / CUSTOM
 MAIN FLOOR ELECTRICAL PLAN

CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE JOB #: DU 100 018 0616 CN # 28632 LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT	DRAWN BY: SG	DATE: 2/20/2020	SCALE: 1/8" = 1'-0"	DWG. NO.: T
	SQUARE FOOTAGES (211) CRAWL SPACE: 214 91 FL: 211 GARAGE: 508 PORCHES: 353			
Raleigh/Durham, NC 182 West Hamlin Road Benson, NC 27504 (811) 261-3482 www.schumacherhomes.com				
SCHUMACHER HOMES				



TYPICAL WALL SECTION

DRAWN BY: SG
 DATE: 2/20/2020
 SCALE: 1/4" = 1'-0"
 DWG. NO: 8

© 1993-2020 SCHUMACHER HOMES OPERATIONS, INC. ALL RIGHTS RESERVED. THE DESIGN AND CONSTRUCTION OF THE HOMES AND GARAGES SHOWN IN THESE DRAWINGS ARE NOT TO BE USED TO CREATE DERIVATIVE WORKS, TECHNICAL DRAWINGS OR TO BUILD A STRUCTURE, REPRODUCED, COPIED, OR MODIFIED, IN WHOLE OR PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF SCHUMACHER HOMES, AND SUCH UNAUTHORIZED USE OR COPYING IS A VIOLATION OF UNITED STATES COPYRIGHT LAW AND THAT RESULT IN DAMAGES IN EXCESS OF \$10000 PER ACT OF INFRINGEMENT.

SQUARE FOOTAGES (211)
 CRAWL SPACE: 2114
 91 FL: 2111
 GARAGE: 508
 PORCHES: 353



CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 00 019 0616 CN #: 28632 VN #: LE111
 LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT

Raleigh/Durham, NC
 182 West Hamlin Road
 Benson, NC 27504
 (811) 261-3482
 www.schumacherhomes.com









34-1/2" TALL
 FRAMED WALL
 BELOW COUNTER

(4) FPC34x48
 (5) CV96
 (7) UFUD696-74E
 (6) DCB9



**VERONA FRENCH COUNTRY / CUSTOM
 CABINET PLAN**

NOTE: CABINET DRAWING DIMENSIONS
 ACCOUNT FOR 1/2" OF DRYWALL



- CABINET NOTES:**
- KITCHEN**
- APEX MAPLE CABINETS W/ FULL OVERLAY
 - 2-1/4" KITCHEN CABINET CROWN MOLDING
 - GRANITE COUNTERTOPS
 - SINGLE-BOWL STAINLESS STEEL UNDERMOUNT KITCHEN SINK
 - OIL RUBBED BRONZE CURVED METAL PULLS
 - WALL OVEN, COOKTOP, & DISHWASHER BY HOMEOWNER
- BATHS**
- SYANNAH I MAPLE CABINETS W/ FULL OVERLAY
 - GRANITE COUNTERTOPS
 - OIL RUBBED BRONZE CURVED METAL PULLS

DATE: 2/20/2020
 SCALE: 1/4" = 1'-0"
 DRAWN BY: SG
 SQUARE FOOTAGES (211)
 CRAWL SPACE: 214
 91 FL: 211
 GARAGE: 508
 PORCHES: 353



CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 00 018 0616 CN #: 28632 VN #: LE11
 LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT

Raleigh/Durham, NC
 182 West Hamlin Road
 Benson, NC 27504
 (811) 261-3482
 www.schumacherhomes.com


SCHUMACHER HOMES

© 1993-2020 SCHUMACHER HOMES OPERATIONS, INC. ALL RIGHTS RESERVED. THE DESIGN AND CONSTRUCTION OF THIS PROJECT ARE THE PROPERTY OF SCHUMACHER HOMES OPERATIONS, INC. THESE DRAWINGS ARE NOT TO BE USED TO CREATE DERIVATIVE WORKS, TECHNICAL DRAWINGS OR TO BUILD A STRUCTURE, REPRODUCED, COPIED, OR MODIFIED, IN WHOLE OR PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF SCHUMACHER HOMES, AND SUCH UNAUTHORIZED USE OR COPYING IS A VIOLATION OF UNITED STATES COPYRIGHT LAW AND THAT RESULT IN DAMAGES IN EXCESS OF \$10000 PER ACT OF INFRINGEMENT.

CABINET NOTES:
 FOYER
 • SAVANNAH 1 MAPLE CABINETS W/
 FULL OVERLAY
 • OIL RUBBED BRONZE CURVED METAL PULLS



'CABINET STYLE' W/ COAT HOOKS
 FOYER



'BENCH STYLE' W/ COAT HOOKS
 LAUNDRY ROOM

VERONA FRENCH COUNTRY / CUSTOM

CABINET PLAN

NOTE: CABINET DRAWING DIMENSIONS
 ACCOUNT FOR 1/2" OF DRYWALL

DRAWN BY: SG
 DATE: 2/20/2020
 SCALE: 1/4" = 1'-0"
 DWG: 10

SQUARE FOOTAGES (STU)
 CRAWL SPACE: 214
 ST. FL: 2111
 GARAGE: 508
 PORCHES: 353

CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE
 JOB #: DU 00 018 0616 CN #: 28632 VN #: LE111
 LOCATION: LOT 8 FREEDOM LANE
 BROADWAY, NC 27505
 COUNTY: HARNETT

Raleigh/Durham, NC
 182 West Hamlin Road
 Benson, NC 27504
 (811) 261-3482
 www.schumacherhomes.com



** SILVERLINE VINYL WINDOWS **

APPROVED: 02-16-20
REVISED ON: 02-20-20

SILVERLINE V3 3900 SERIES WINDOW SCHEDULE				SILVERLINE VINYL SLIDING DOOR UNITS		ANDERSEN 200 SERIES NARROLINE GLIDING PATIO DOOR UNITS		SILVERLINE V1 2900 SERIES WINDOW SCHEDULE					
UNIT		ROUGH OPENING		MEETS EGRESS MIN. 5.1 SQ.FT.		UNIT	ROUGH OPENING	UNIT	ROUGH OPENING		MEETS EGRESS MIN. 5.1 SQ.FT.		
DOUBLE HUNG UNITS						MASONITE PATIO DOOR UNITS		DOUBLE HUNG UNITS					
2/0 x 5/0	24-1/4" x 60-1/2"	3.63	NO	3068 DOOR	38-1/2" x 82-1/2"	NLGD6068	72" x 80"	2/0 x 5/0	24-1/2" x 60-1/2"	3.40	NO		
2/0 x 5/6	24-1/4" x 66-1/2"	4.05	NO	3080 DOOR	38-1/2" x 98-1/2"	NLGD12068-4	141-3/4" x 80"	2/0 x 5/6	24-1/2" x 66-1/2"	3.79	NO		
2/4 x 4/0	28-1/4" x 48-1/2"	3.35	NO	6068 DOOR	75-5/8" x 82-1/2"	ANDERSEN 100 SERIES NARROLINE GLIDING PATIO DOOR UNITS		2/4 x 4/0	28-1/2" x 48-1/2"	3.15	NO		
2/4 x 4/6	28-1/4" x 54-1/2"	3.85	NO	6080 DOOR	75-5/8" x 98-1/2"	6068	72" x 80"	2/4 x 4/6	28-1/2" x 54-1/2"	3.63	NO		
2/4 x 5/0	28-1/4" x 60-1/2"	4.36	NO	9068 DOOR	112-5/8" x 82-1/2"	6080	72" x 96"	2/4 x 5/0	28-1/2" x 60-1/2"	4.11	NO		
2/4 x 5/6	28-1/4" x 66-1/2"	4.86	NO	9080 DOOR	112-5/8" x 98-1/2"	EXTERIOR DOOR W/SIDELITES		2/4 x 5/6	28-1/2" x 66-1/2"	4.59	NO		
2/8 x 4/6	32-1/4" x 54-1/2"	4.49	NO	INTERIOR DOOR UNITS		2'-8" W/(1) 14" S.L.	50-5/8" x 82-1/2"	2/8 x 4/6	32-1/2" x 54-1/2"	4.27	NO		
2/8 x 5/0	32-1/4" x 60-1/2"	5.08	NO	3' DBL. DOOR	3'-2" x 6'-10"	2'-8" W/(2) 14" S.L.	66-5/8" x 82-1/2"	2/8 x 5/0	32-1/2" x 60-1/2"	4.83	NO		
2/8 x 6/0	32-1/4" x 72-1/2"	6.25	YES	4' DBL. DOOR	4'-2" x 6'-10"	3'-0" W/(1) 14" S.L.	54-5/8" x 82-1/2"	2/8 x 6/0	32-1/2" x 72-1/2"	5.95	YES		
3/0 x 3/2	36-1/4" x 38-1/2"	3.35	NO	5' DBL. DOOR	5'-2" x 6'-10"	3'-0" W/(2) 14" S.L.	69-5/8" x 82-1/2"	3/0 x 3/2	36-1/2" x 38-1/2"	3.18	NO		
3/0 x 5/0	36-1/4" x 60-1/2"	5.80	YES	6' DBL. DOOR	6'-2" x 6'-10"	WINDOW JACKS FOR 8'-0" 82-1/2"		3/0 x 5/0	36-1/2" x 60-1/2"	5.70	BUMPER REMOVED 2901 SERIES		
3/0 x 4/6	36-1/4" x 54-1/2"	5.14	NO	EGRESS CRITERIA		WINDOW JACKS FOR 9'-0" 82-1/2"		3/0 x 4/6	36-1/2" x 54-1/2"	4.90	NO		
3/0 x 5/6	36-1/4" x 66-1/2"	6.47	YES	MIN. 20" NET OPG. IN WIDTH		DOOR JACKS 80-1/2"		3/0 x 5/6	36-1/2" x 66-1/2"	6.19	YES		
3/0 x 6/0	36-1/4" x 72-1/2"	7.14	YES	MIN. 24" NET OPG. IN HEIGHT		GLASS BLOCK WINDOWS		3/0 x 6/0	36-1/2" x 72-1/2"	6.84	YES		
				MIN. 5.1 SQ.FT. OPG. AREA		16" x 32" GLASS BLOCK =		3/4 x 5/0	40-1/2" x 60-1/2"	6.26	YES		
						R.O. 16-1/2" x 32-1/2"							
TRANSOM UNITS				VISIBLE GLASS		TRANSOM UNITS						VISIBLE GLASS	
2/0 x 2/0	24-1/4" x 24-1/2"					2/0 x 1/0	24-1/2" x 12-1/2"			2/0 x 1/0	24-1/2" x 12-1/2"	.92	
2/8 x 1/4	32-1/4" x 16-1/2"	2.16				2/8 x 1/0	32-1/2" x 12-1/2"	1.31		2/8 x 1/0	32-1/2" x 12-1/2"	1.31	
3/0 x 1/4	36-1/4" x 16-1/2"	2.48				3/0 x 1/0	36-1/2" x 12-1/2"	1.51		3/0 x 1/0	36-1/2" x 12-1/2"	1.51	
2/0 x 1/6	24-1/4" x 18-1/2"	1.79				2/0 x 1/6	24-1/2" x 18-1/2"	1.72		2/0 x 1/6	24-1/2" x 18-1/2"	1.72	
2/8 x 1/6	32-1/4" x 18-1/2"	2.54				2/8 x 1/6	32-1/2" x 18-1/2"	2.44		2/8 x 1/6	32-1/2" x 18-1/2"	2.44	
3/0 x 1/6	36-1/4" x 18-1/2"	2.54				3/0 x 1/6	36-1/2" x 18-1/2"	2.80		3/0 x 1/6	36-1/2" x 18-1/2"	2.80	
CASEMENT UNITS				VISIBLE GLASS		PICTURE UNITS						VISIBLE GLASS	
C1-2040	24-5/8" x 48-1/2"	4.93				3/0 x 4/0	36-1/2" x 48-1/2"	9.26		3/0 x 4/0	36-1/2" x 48-1/2"	9.26	
C1-2440	27-7/8" x 48-1/2"	6.14				3/4 x 4/0	40-1/2" x 48-1/2"	10.45		3/4 x 4/0	40-1/2" x 48-1/2"	10.45	
C1-21140	36-7/16" x 48-1/2"	8.30				5/0 x 6/0	60-1/2" x 72-1/2"	25.59		5/0 x 6/0	60-1/2" x 72-1/2"	25.59	
C2-48411	57" x 60-3/8"	16.01				HALF ROUNDS UNITS						VISIBLE GLASS	
PICTURE UNITS				VISIBLE GLASS									
3/0 x 4/0	36-1/2" x 48-1/2"	9.41				2/4	28-1/2" x 16-9/16"	1.35		2/4	28-1/2" x 16-9/16"	1.35	
3/4 x 4/0	40-1/2" x 48-1/2"	10.61				2/8	32-1/2" x 18-9/16"	1.88		2/8	32-1/2" x 18-9/16"	1.88	
5/0 x 6/0	60-1/2" x 72-1/2"	25.85				3/0	36-1/2" x 20-9/16"	2.49		3/0	36-1/2" x 20-9/16"	2.49	
HALF ROUNDS UNITS				VISIBLE GLASS									
2/4	28-1/4" x 16"	1.47				4/0	48-1/2" x 26-9/16"	4.87		4/0	48-1/2" x 26-9/16"	4.87	
2/8	32-1/4" x 18"	2.03				6/0	72" x 38-5/16"	11.79		6/0	72" x 38-5/16"	11.79	
3/0	36-1/4" x 20"	2.66				CUSTOM UNITS						VISIBLE GLASS	
4/0	48-1/4" x 26"	5.10				29P4066	40-1/2" x 66-1/2"	13.84		29P4066	40-1/2" x 66-1/2"	13.84	
6/0	72" x 37-7/8"	12.24				29E4760	48" x 68-3/4"	18.06		29E4760	48" x 68-3/4"	18.06	
CUSTOM UNITS				VISIBLE GLASS									
39P3966	40-1/4" x 66-1/2"	14.13											
39E4760	48" x 68-3/4"	18.46											
ADDITIONAL IMPORTANT INFORMATION						MISCELLANEOUS FRAMING							
						1. THERE IS NO ALLOWANCE IN ANY OF THE HEIGHT DIMENSIONS FOR CARPET SHIM. (PLEASE ADD ACCORDINGLY)							
						2. BRICK OPENINGS ARE 2-1/2" WIDER AND 1-1/4" HIGHER THAN ACTUAL UNIT SIZE.							
						3. FOR T' DOORS ADD 4" TO THE ACTUAL UNIT SIZE AND ROUGH OPENING HEIGHT DIMENSIONS.							
						4. DO NOT STORE PRE-HUNG UNITS OUTSIDE.							
						FIREPLACE FRAMING							
						36" WOOD BURNING EL36 W: 42" H: 40-1/4" D: 21-1/2"							
						42" WOOD BURNING EL42 W: 48" H: 40-1/4" D: 21-1/2"							
						36" DIRECT VENT NDV42361 W: 42" H: 35-1/4" D: 24"							
						42" DIRECT VENT NDV48421 W: 49" H: 35-1/4" D: 24"							
						36" MODERN GAS DV NEVO42361 W: 42" H: 40-1/4" D: 20-1/4"							
						42" RAVE DIRECT VENT RAVE40131 W: 50" H: 33-1/4" D: 18-1/4"							
						60" CRAVE DIRECT VENT CRAVET260-B W: 72-1/4" H: 48-1/2" D: 18-3/4"							
						LINTEL SCHEDULE							
						HOLD FIREPLACE UP 2" TO ALLOW FOR STONE HEARTH IF APP. A PLYWOOD FLOOR IS REQUIRED ON ALL WOODBURNERS AT LEAST 6' HIGH TO BE INSTALLED BY FRAMERS 2X6 WRAP AT TOP OF CHASE							
						NO. OF 1/2" OR EQUIVALENT REINFORCING BARS							
						SIZE OF STEEL ANGLE	NO STORY ABOVE	ONE STORY ABOVE	TWO STORIES ABOVE				
						3 X 3 X 1/4	6'-0"	4'-6"	3'-0"				
						4 X 3 X 1/4	8'-0"	6'-0"	4'-6"				
						5 X 3-1/2 X 5/16	10'-0"	8'-0"	6'-0"				
						6 X 3-1/2 X 5/16	14'-0"	9'-6"	7'-0"				
						(2) 6 X 3-1/2 X 5/16	20'-0"	12'-0"	9'-6"				

1. TO CALCULATE THE R.O. FOR A WINDOW WITH A TRANSOM, ADD BOTH UNIT DIMENSIONS TOGETHER AND ADD 1/2".
2. TO CALCULATE THE R.O. FOR MULTIPLE UNITS, ADD BOTH ACTUAL UNIT DIM TOGETHER AND ADD 1/2" PER MULL
3. FOR R.O.'S NOT LISTED, ADD 1/2" TO THE ACTUAL UNIT DIM FOR BOTH THE WIDTH AND HEIGHT

DATE: 2/20/2020

SCALE: 1/8" = 1'-0"

DRAWN BY: SG

SQUARE FOOTAGES (211)

CRAUL SPACE: 214

9" T.L. 211

GARAGE: 508

PORCHES: 353

CUSTOM BUILT FOR: CHRISTOPHER & CHRISTINE LEE

JOB #: DU 000 018 0616 CN #: 28632

LOCATION: LOT 8 FREEDOM LANE BROADWAY, NC 27505 COUNTY: HARNETT

RALEIGH/DURHAM, NC


182 West Hamlin Road

Benson, NC 27504

(877) 261-3482

www.schumacherhomes.com

© 1993-2020 SCHUMACHER HOMES OPERATIONS, INC. ALL RIGHTS RESERVED. THE DESIGN AND CONSTRUCTION OF THE HOMES SHOWN IN THESE DRAWINGS ARE THE PROPERTY OF SCHUMACHER HOMES. THESE DRAWINGS ARE NOT TO BE USED TO CREATE DERIVATIVE WORKS, TECHNICAL DRAWINGS OR TO BUILD A STRUCTURE, REPRODUCED, COPIED, OR MODIFIED, IN WHOLE OR PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF SCHUMACHER HOMES, AND SUCH UNAUTHORIZED USE OR COPYING IS A VIOLATION OF UNITED STATES COPYRIGHT LAW AND THAT RESULT IN DAMAGES IN EXCESS OF \$10000 PER ACT OF INFRINGEMENT.




Lee - Verona B

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H01	Hip Girder	1	2	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:16 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-IB9eLTJK_zcEtqx5qJljs7q4jfkgGnfyFnzbyzjTr



Scale = 1:37.2




Plate Offsets (X,Y)-- [5:0-4-0,0-2-12], [6:0-4-0,0-2-12], [11:0-3-8,0-5-0], [12:0-4-0,0-5-4]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.21	Vert(LL) -0.03	11-19	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.46	Vert(CT) -0.06	11-19	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.49	Horz(CT) 0.00	9	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 180 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
T2: 2x6 SPF 1650F 1.5E
BOT CHORD 2x8 SP No.1
WEBS 2x4 SPF Stud
SLIDER Left 2x4 SPF Stud -4 1-6-0, Right 2x4 SPF Stud -4 1-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS. (lb/size) 2=3832/0-4-0 (min. 0-3-0), 9=4056/0-4-0 (min. 0-3-3)
Max Horz 2=-118(LC 10)
Max Uplift 2=-880(LC 12), 9=-815(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-2549/595, 3-21=-3616/843, 4-21=-3548/849, 4-5=-3523/878, 5-6=-2434/651,
6-7=-3442/823, 7-22=-3457/793, 8-22=-3525/782, 8-9=-2661/545
BOT CHORD 2-23=-556/2475, 23-24=-556/2475, 12-24=-556/2475, 12-25=-451/2361, 11-25=-451/2361,
11-26=-474/2436, 26-27=-474/2436, 9-27=-474/2436
WEBS 5-12=-545/2266, 6-12=-179/253, 6-11=-404/2136

- NOTES-**
- 2-ply truss to be connected together with 10d (0.131"x3") nails as follows:
Top chords connected as follows: 2x4 - 1 row at 0-9-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
Bottom chords connected as follows: 2x8 - 2 rows staggered at 0-6-0 oc.
Webs connected as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 5-2-7, Exterior(2) 5-2-7 to 11-0-8, Interior(1) 11-0-8 to 12-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 880 lb uplift at joint 2 and 815 lb uplift at joint 9.
 - This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1466 lb down and 473 lb up at 2-3-4, 1339 lb down and 273 lb up at 4-3-4, 1407 lb down and 273 lb up at 6-3-4, and 1339 lb down and 273 lb up at 8-3-4, and 1370 lb down and 273 lb up at 10-3-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H01	Hip Girder	1	2	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:16 2020 Page 2
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-IB9eLTjK_zcEtqx5qJljs7q4jfkgaGnfyFnzbyzjTr

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-5=-60, 5-6=-60, 6-10=-60, 13-17=-20

Concentrated Loads (lb)

Vert: 23=-1466(B) 24=-1339(B) 25=-1339(B) 26=-1339(B) 27=-1339(B)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H02	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:16 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-IB9eLTJK_zcEtqx5qJjs7q0cfq8aLifyFnzbyzjTr




Plate Offsets (X,Y)-- [2:0-1-12,0-1-12], [3:0-4-4,0-1-12], [5:0-4-4,0-1-12], [6:0-1-12,0-1-12], [8:Edge,0-3-8], [8:0-0-0,0-1-12], [12:0-0-0,0-1-12]					
LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.47	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.11	Vert(LL) 0.03 9-10 >999 240		
TCDL 10.0	Lumber DOL 1.15	WB 0.17	Vert(CT) -0.03 10 >999 180		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS	Horz(CT) 0.00 8 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 59 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x6 SPF 1650F 1.5E
 WEBS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 12=537/0-4-0 (min. 0-1-8), 8=539/0-4-0 (min. 0-1-8)
 Max Horz 12=77(LC 11)
 Max Uplift 12=-239(LC 12), 8=-277(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-416/252, 3-13=-584/390, 4-13=-584/390, 4-14=-584/390, 5-14=-584/390,
 5-6=-418/287, 2-12=-407/252, 6-8=-408/277
 WEBS 3-10=-245/400, 4-10=-293/205, 5-10=-217/399

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 6-0-0, Interior(1) 6-0-0 to 10-1-9, Exterior(2) 10-1-9 to 12-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 239 lb uplift at joint 12 and 277 lb uplift at joint 8.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 89 lb up at 1-10-7, 82 lb up at 3-11-3, 82 lb up at 5-11-3, and 82 lb up at 7-11-3, and 176 lb up at 10-1-9 on top chord, and 5 lb down and 30 lb up at 1-11-3, 5 lb down and 30 lb up at 3-11-3, 5 lb down and 30 lb up at 5-11-3, and 5 lb down and 30 lb up at 7-11-3, and 11 lb down and 60 lb up at 9-11-3 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Snow (balanced); Lumber Increase=1.15, Plate Increase=1.15

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H02	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:17 2020 Page 2
ID:V19e1jzWg7fmbBoML6pDUzzowqH-mNi0ZpkyIGk5U_WHO0pyPKNBM3ANJoyoBvXW7OzjTrq

LOAD CASE(S) Standard

Uniform Loads (plf)

Vert: 1-2=-60, 2-3=-60, 3-5=-60, 5-6=-60, 6-7=-60, 8-12=-20


Concentrated Loads (lb)

Vert: 11=-3(F) 10=-3(F) 15=-3(F) 16=-3(F) 17=-5(F)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H03	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:17 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-mNi0ZpkylGk5U_WHO0pyPKNEA39PJpzoBvXW7OzjTrq



Scale = 1:28.1

Plate Offsets (X,Y)-- [3:0-4-4,0-1-12], [4:0-4-4,0-1-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.29	Vert(LL)	-0.02	8-9	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.17	Vert(CT)	-0.03	8-9	>999		
TCDL 10.0	Lumber DOL 1.15	WB 0.11	Horz(CT)	0.00	7	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 59 lb	FT = 20%

LUMBER-

TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 10=530/0-4-0 (min. 0-1-8), 7=530/0-4-0 (min. 0-1-8)
Max Horz 10=111(LC 11)
Max Uplift 10=-80(LC 12), 7=-80(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-11=-462/130, 3-11=-348/140, 3-12=-299/155, 12-13=-299/155, 4-13=-299/155,
4-14=-348/140, 5-14=-463/130, 2-10=-505/171, 5-7=-504/172
BOT CHORD 8-9=-57/273

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TC DL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-6-7, Exterior(2) 3-6-7 to 7-9-5, Interior(1) 7-9-5 to 8-5-9, Exterior(2) 8-5-9 to 12-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 80 lb uplift at joint 10 and 80 lb uplift at joint 7.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H04	Hip Girder	1	2	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:18 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-EaGOM9kbWaty675TykKBxYVF?TJL29KxQZG4fqzjTrp






Plate Offsets (X,Y)-- [4:0-3-8,Edge], [7:0-3-8,Edge], [10:Edge,0-4-2], [12:0-3-0,0-3-12], [13:0-3-4,0-5-12], [14:0-6-0,0-5-12], [16:0-3-8,0-6-4], [17:0-3-8,0-5-12], [18:0-3-8,0-4-12]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15		TC 0.92	Vert(LL) -0.15	14-16	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15		BC 0.96	Vert(CT) -0.28	14-16	>999	180	MT18HS	197/144
TCDL 10.0	Rep Stress Incr NO		WB 0.55	Horz(CT) 0.09	10	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014		Matrix-MS						
BCDL 10.0								Weight: 517 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* T2: 2x6 SPF 1650F 1.5E	TOP CHORD Structural wood sheathing directly applied or 2-3-2 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-7.
BOT CHORD 2x8 SP DSS *Except* B2: 2x8 SP No.1	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* W1,W2,W3: 2x4 SPF Stud	
SLIDER Left 2x4 SPF Stud -4 4-0-14, Right 2x4 SPF Stud -4 4-0-14	

REACTIONS. (lb/size) 1=12518/0-4-0 (req. 0-10-3), 10=10010/0-4-0 (req. 0-8-1)
 Max Horz 1=-171(LC 30)
 Max Uplift 1=-2437(LC 12), 10=-2973(LC 13)
 Max Grav 1=12989(LC 2), 10=10247(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-7801/1608, 2-27=-12473/2625, 3-27=-12445/2635, 3-4=-11697/2614, 4-5=-9936/2316, 5-6=-9851/2392, 6-7=-9851/2392, 7-8=-11441/2957, 8-28=-11895/3349, 9-28=-11930/3340, 9-29=-7011/2181, 10-29=-7094/2168
 BOT CHORD 1-30=-1800/8558, 30-31=-1800/8558, 18-31=-1800/8558, 18-32=-1815/8815, 17-32=-1815/8815, 17-33=-1713/8198, 33-34=-1713/8198, 34-35=-1713/8198, 16-35=-1713/8198, 15-16=-2135/9936, 15-36=-2135/9936, 36-37=-2135/9936, 37-38=-2135/9936, 14-38=-2135/9936, 14-39=-1880/8019, 39-40=-1880/8019, 40-41=-1880/8019, 13-41=-1880/8019, 13-42=-2203/8435, 12-42=-2203/8435, 12-43=-2202/8142, 10-43=-2202/8142
 WEBS 2-18=-224/427, 3-18=-227/1765, 3-17=-1470/322, 4-17=-878/4471, 4-16=-1074/3988, 5-16=-171/350, 6-14=-270/146, 7-14=-708/4202, 7-13=-1443/4097, 8-13=-1210/1016, 8-12=-1142/1350, 9-12=-225/488

- NOTES-**
- 2-ply truss to be connected together as follows:
 Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-4-0 oc, 2x6 - 2 rows staggered at 0-9-0 oc.
 Bottom chords connected with 10d (0.131"x3") nails as follows: 2x8 - 2 rows staggered at 0-5-0 oc.
 Web connected with Simpson SDS 1/4 x 3 screws as follows: 2x4 - 1 row at 0-9-0 oc.
 - All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
 - Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 2-11-6, Interior(1) 2-11-6 to 8-3-1, Exterior(2) 8-3-1 to 12-6-7, Interior(1) 12-6-7 to 21-2-15, Exterior(2) 21-2-15 to 25-5-13, Interior(1) 25-5-13 to 30-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H04	Hip Girder	1	2	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:19 2020 Page 2
ID:V19e1jzWg7fmbBoML6pDUzzowqH-imqm_VIDHu?pkHggWRrQUISQIsfancZ5eD0dCHzjTro

NOTES-

- 7) All plates are MT20 plates unless otherwise indicated.
- 8) The Fabrication Tolerance at joint 1 = 16%, joint 10 = 0%
- 9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 11) WARNING: Required bearing size at joint(s) 1, 10 greater than input bearing size.
- 12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 2437 lb uplift at joint 1 and 2973 lb uplift at joint 10.
- 13) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
- 14) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
- 15) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 1618 lb down and 240 lb up at 0-0-0, 1582 lb down and 250 lb up at 2-0-12, 1531 lb down and 252 lb up at 4-0-12, 1567 lb down and 266 lb up at 6-0-12, 1489 lb down and 291 lb up at 8-0-12, 1456 lb down and 312 lb up at 10-0-12, 1472 lb down and 302 lb up at 12-0-0, 1449 lb down and 302 lb up at 14-0-0, 1477 lb down and 302 lb up at 16-0-0, 1474 lb down and 285 lb up at 18-0-0, 1463 lb down and 351 lb up at 20-0-0, 1456 lb down and 373 lb up at 22-0-0, and 1394 lb down and 362 lb up at 24-0-0, and 1746 lb down and 1294 lb up at 26-0-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-4=-60, 4-7=-60, 7-11=-60, 19-23=-20


Concentrated Loads (lb)

Vert: 17=-1362(F) 12=-1363(F) 19=-1618(F) 30=-1582(F) 31=-1475(F) 32=-1475(F) 33=-1361(F) 35=-1361(F) 36=-1361(F) 38=-1361(F) 39=-1361(F) 41=-1360(F) 42=-1362(F) 43=-1715(F)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H05	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:19 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-imqm_VIDHu?pkHggWRrQUISWMSljin5eD0dCHzjTro



Scale = 1:66.2

Plate Offsets (X,Y)-- [4:0-1-12,0-0-0], [5:0-8-8,0-1-8], [6:0-4-4,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.56	Vert(LL)	-0.13 11-12	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.56	Vert(CT)	-0.22 11-12	>999	180	MT18HS	197/144
TCDL 10.0	Lumber DOL 1.15	WB 0.41	Horz(CT)	0.06 9	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 142 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-11-4 oc purlins, except 2-0-0 oc purlins (5-3-4 max.): 5-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1119/0-4-0 (min. 0-1-12), 9=1173/0-4-0 (min. 0-1-13)
 Max Horz 1=-182(LC 8)
 Max Uplift 1=-172(LC 12), 9=-187(LC 13)
 Max Grav 1=1119(LC 1), 9=1174(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-395/0, 2-27=-1362/285, 3-27=-1205/299, 3-28=-1273/376, 4-28=-1184/400, 4-5=-764/273, 5-29=-839/310, 29-30=-839/310, 6-30=-839/310, 6-31=-1239/400, 7-31=-1325/374, 7-32=-1312/295, 8-32=-1364/270, 8-9=-358/0
 BOT CHORD 1-15=-188/1045, 14-15=-92/792, 13-14=-92/792, 12-13=-92/792, 12-33=-41/786, 33-34=-41/786, 11-34=-41/786, 9-11=-123/964
 WEBS 3-15=-320/271, 15-16=-197/441, 4-16=-190/444, 6-11=-195/484, 7-11=-321/274


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-0-0, Interior(1) 3-0-0 to 10-7-8, Exterior(2) 10-7-8 to 14-10-7, Interior(1) 14-10-7 to 17-4-8, Exterior(2) 17-4-8 to 21-7-7, Interior(1) 21-7-7 to 28-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are MT20 plates unless otherwise indicated.
 - 6) The Fabrication Tolerance at joint 5 = 8%, joint 5 = 8%
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 172 lb uplift at joint 1 and 187 lb uplift at joint 9.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H06	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:20 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-AyO8Bmr2B7gLRFs39Mf1z?iJG8rW?NEttAKjzjTrn



Scale = 1:49.9




Plate Offsets (X,Y)-- [2:Edge,0-0-0], [4:0-4-4,0-2-0], [9:0-4-4,0-2-0], [11:Edge,0-0-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15		TC 0.49	Vert(LL) 0.22	15	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15		BC 0.32	Vert(CT) -0.21	15	>999	180		
TCDL 10.0	Rep Stress Incr NO		WB 0.77	Horz(CT) -0.04	11	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014		Matrix-MS						
BCDL 10.0								Weight: 135 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x6 SPF 1650F 1.5E
 WEBS 2x4 SPF Stud
 SLIDER Left 2x4 SPF Stud -4 1-6-0, Right 2x4 SPF Stud -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-3-10 oc purlins, except 2-0-0 oc purlins (3-5-7 max.): 4-9.
 BOT CHORD Rigid ceiling directly applied or 6-8-7 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1294/0-4-0 (min. 0-2-4), 11=1297/0-4-0 (min. 0-2-5)
 Max Horz 2=-70(LC 30)
 Max Uplift 2=-810(LC 9), 11=-839(LC 8)
 Max Grav 2=1449(LC 38), 11=1472(LC 39)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-914/581, 3-27=-1704/1036, 4-27=-1664/1049, 4-28=-2522/1597, 28-29=-2522/1597, 5-29=-2522/1597, 5-30=-2522/1597, 30-31=-2522/1597, 31-32=-2522/1597, 6-32=-2522/1597, 6-33=-2535/1616, 7-33=-2535/1616, 7-8=-2535/1616, 8-34=-2535/1616, 34-35=-2535/1616, 35-36=-2535/1616, 9-36=-2535/1616, 9-37=-1673/1089, 10-37=-1730/1075, 10-11=-931/605
 BOT CHORD 2-38=-780/1297, 18-38=-780/1297, 18-39=-781/1296, 39-40=-781/1296, 17-40=-781/1296, 17-41=-1826/2981, 41-42=-1826/2981, 16-42=-1826/2981, 16-43=-1826/2981, 15-43=-1826/2981, 15-44=-1826/2981, 44-45=-1826/2981, 14-45=-1826/2981, 14-46=-763/1292, 46-47=-763/1292, 13-47=-763/1292, 13-48=-762/1293, 11-48=-762/1293
 WEBS 4-17=-970/1533, 5-17=-389/312, 6-17=-506/333, 6-14=-491/310, 8-14=-390/314, 9-14=-959/1525

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-5-2, Exterior(2) 3-5-2 to 7-8-0, Interior(1) 7-8-0 to 24-6-14, Exterior(2) 24-6-14 to 28-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 810 lb uplift at joint 2 and 839 lb uplift at joint 11.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H06	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:20 2020 Page 2
ID:\19e1jzWg7fmbBoML6pDUzzowqH-AyO8Bmr2B7gLRFs39Mf1z?iJG8rW?NEtIiAkjzjTrn

NOTES-

- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 96 lb down and 112 lb up at 3-5-2, 99 lb down and 105 lb up at 5-5-14, 98 lb down and 105 lb up at 7-5-14, 98 lb down and 105 lb up at 9-5-14, 98 lb down and 105 lb up at 11-5-14, 98 lb down and 105 lb up at 13-5-14, 98 lb down and 105 lb up at 15-5-14, 98 lb down and 105 lb up at 17-5-14, 98 lb down and 105 lb up at 19-5-14, 99 lb down and 105 lb up at 21-5-14, and 99 lb down and 105 lb up at 23-5-14, and 96 lb down and 112 lb up at 24-6-14 on top chord, and 84 lb down and 90 lb up at 2-0-12, 38 lb down and 43 lb up at 3-5-14, 38 lb down and 43 lb up at 5-5-14, 38 lb down and 43 lb up at 7-5-14, 38 lb down and 43 lb up at 9-5-14, 38 lb down and 43 lb up at 11-5-14, 38 lb down and 43 lb up at 13-5-14, 38 lb down and 43 lb up at 15-5-14, 38 lb down and 43 lb up at 17-5-14, 38 lb down and 43 lb up at 19-5-14, 38 lb down and 43 lb up at 21-5-14, 38 lb down and 43 lb up at 23-5-14, and 38 lb down and 43 lb up at 24-6-2, and 84 lb down and 90 lb up at 25-11-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-4=-60, 4-9=-60, 9-12=-60, 19-23=-20


Concentrated Loads (lb)

Vert: 7=-2(B) 18=-6(B) 4=-2(B) 8=-2(B) 14=-6(B) 9=-2(B) 13=-6(B) 28=-2(B) 29=-2(B) 30=-2(B) 31=-2(B) 32=-2(B) 33=-2(B) 35=-2(B) 36=-2(B) 38=-74(B) 39=-6(B) 40=-6(B) 41=-6(B) 42=-6(B) 43=-6(B) 44=-6(B) 45=-6(B) 46=-6(B) 47=-6(B) 48=-74(B)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H08	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:21 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzZowqH-f9yXPBnTpVFXzbq2dsuuZAXrPgOjFRE06WVKG9zjTm



Scale = 1:53.0




Plate Offsets (X,Y)-- [5:0-4-4,0-2-0], [7:0-4-4,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.59	Vert(LL)	-0.27	13	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.66	Vert(CT)	-0.58	13	>578		
TCDL 10.0	Lumber DOL 1.15	WB 0.86	Horz(CT)	0.07	10	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 140 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-9-14 oc purlins, except 2-0-0 oc purlins (5-10-5 max.): 5-7.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 6-15, 6-12, 16-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1173/0-4-0 (min. 0-1-13), 10=1173/0-4-0 (min. 0-1-13)
 Max Horz 2=-148(LC 10)
 Max Uplift 2=-174(LC 12), 10=-174(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-286/0, 3-27=-1370/286, 4-27=-1320/304, 4-5=-1219/316, 5-28=-886/291, 6-28=-886/291, 6-29=-886/291, 7-29=-886/291, 7-8=-1219/316, 8-30=-1320/304, 9-30=-1370/286, 9-10=-286/0
 BOT CHORD 2-15=-209/966, 14-15=-175/1050, 13-14=-175/1050, 12-13=-175/1050, 10-12=-144/966
 WEBS 5-15=-70/481, 15-16=-272/175, 12-17=-272/174, 7-12=-70/481


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-2-11, Exterior(2) 8-2-11 to 12-5-10, Interior(1) 12-5-10 to 19-9-5, Exterior(2) 19-9-5 to 23-10-2, Interior(1) 23-10-2 to 28-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 174 lb uplift at joint 2 and 174 lb uplift at joint 10.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H09	Half Hip Girder	2	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:22 2020 Page 1
ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-7LWvcXn5ZpNOblPEBaP76O48_4u2_4SXLAEHobzjTrl



Scale = 1:15.7

Plate Offsets (X,Y)-- [2:0-4-7,0-0-6], [3:0-4-4,0-1-12], [6:0-3-0,0-2-4]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.09	Vert(LL)	0.00	9	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.01	Vert(CT)	-0.00	9	>999		
TCDL 10.0	Lumber DOL 1.15	WB 0.03	Horz(CT)	-0.00	2	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MP						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 21 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x6 SPF 1650F 1.5E
 WEBS 2x4 SPF Stud
 SLIDER Left 2x8 SP No.1 -4 1-2-12

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-8-8 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=164/0-4-0 (min. 0-1-8), 5=94/Mechanical
 Max Horz 2=77(LC 11)
 Max Uplift 2=-47(LC 12), 5=-71(LC 9)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Refer to girder(s) for truss to truss connections.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 47 lb uplift at joint 2 and 71 lb uplift at joint 5.
 - This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 5 lb down and 76 lb up at 1-6-4 on top chord, and 2 lb down and 32 lb up at 1-7-0 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
 Uniform Loads (plf)
 Vert: 1-3=-60, 3-4=-60, 5-7=-20
 Concentrated Loads (lb)
 Vert: 6=-1(B)




Plate Offsets (X,Y)-- [3:0-4-4,0-2-0], [8:0-4-4,0-2-0], [9:0-2-12,0-1-8], [10:Edge,0-1-8]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.99	Vert(LL) -0.08 14-15 >999 240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.49	Vert(CT) -0.15 14-15 >999 180		
TCDL 10.0	Rep Stress Incr YES	WB 0.99	Horz(CT) 0.04 10 n/a n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS			
BCDL 10.0				Weight: 271 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 5-7-15 oc purlins, except end verticals, and 2-0-0 oc purlins (5-4-2 max.): 3-8.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except*	WEBS 1 Row at midpt 2-18, 4-17, 5-14, 7-11, 9-10
W1,W2: 2x4 SPF Stud	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 18=1609/0-4-0 (min. 0-2-12), 10=1381/Mechanical
 Max Horz 18=327(LC 9)
 Max Uplift 18=-212(LC 12), 10=-265(LC 9)
 Max Grav 18=1752(LC 22), 10=1494(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1015/330, 3-22=-732/302, 4-22=-732/302, 4-5=-1136/382, 5-6=-1136/382, 6-7=-1136/382, 7-23=-462/275, 8-23=-462/275, 8-9=-643/318, 9-10=-1481/332
 BOT CHORD 18-24=-281/480, 24-25=-281/480, 17-25=-281/480, 17-26=-313/1052, 16-26=-313/1052, 15-16=-313/1052, 15-27=-313/1052, 14-27=-313/1052, 13-14=-230/904, 12-13=-230/904, 12-28=-230/904, 11-28=-230/904
 WEBS 2-18=-1540/341, 2-17=-115/706, 3-17=-74/359, 4-17=-838/245, 4-15=0/346, 5-14=-357/183, 7-14=-153/448, 7-12=0/368, 7-11=-1159/300, 9-11=-237/1151

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCCL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-10-15, Interior(1) 3-10-15 to 9-8-6, Exterior(2) 9-8-6 to 15-0-4, Interior(1) 15-0-4 to 34-1-3, Exterior(2) 34-1-3 to 37-6-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 212 lb uplift at joint 18 and 265 lb uplift at joint 10.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H11	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:23 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-bX4HqsojK6VFCv_RIHwMebd79U5UjchZq_rL2zjTrk




Plate Offsets (X,Y)-- [3:0-4-4,0-2-0], [8:0-4-4,0-2-0], [10:Edge,0-3-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.83	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.64	Vert(LL) -0.13 11-12 >999 240		
TCDL 10.0	Lumber DOL 1.15	WB 0.99	Vert(CT) -0.24 11-12 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.04 10 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 250 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W2: 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-8-13 max.): 3-8.
 BOT CHORD Rigid ceiling directly applied or 9-10-2 oc bracing.
 WEBS 1 Row at midpt 2-18, 3-17, 4-16, 5-16, 5-12, 7-12, 8-11
 2 Rows at 1/3 pts 9-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 18=1610/0-4-0 (min. 0-2-10), 10=1380/Mechanical
 Max Horz 18=288(LC 9)
 Max Uplift 18=-245(LC 9), 10=-331(LC 9)
 Max Grav 18=1685(LC 22), 10=1512(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-807/269, 3-21=-1195/355, 4-21=-1195/355, 4-5=-1195/355, 5-6=-1026/330,
 6-7=-1026/330, 7-22=-1026/330, 8-22=-1026/330, 8-9=-377/302, 9-10=-1674/369
 BOT CHORD 17-18=-258/358, 17-23=-253/586, 16-23=-253/586, 15-16=-354/1309, 15-24=-354/1309,
 14-24=-354/1309, 13-14=-354/1309, 13-25=-354/1309, 12-25=-354/1309
 WEBS 2-18=-1580/330, 2-17=-166/949, 3-17=-650/229, 3-16=-277/1058, 4-16=-475/245,
 5-16=-284/90, 5-14=0/403, 5-12=-599/168, 7-12=-477/243, 8-12=-356/1387,
 8-11=-1229/434, 9-11=-260/1457


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-9-14, Interior(1) 3-9-14 to 7-3-9, Exterior(2) 7-3-9 to 12-7-8, Interior(1) 12-7-8 to 36-6-0, Exterior(2) 36-6-0 to 37-6-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 245 lb uplift at joint 18 and 331 lb uplift at joint 10.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H12	Half Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:24 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-3kdf1CpL5Qd6q2Ydl?RbBp9OGtO7SnHqoUjOtUzjTrj



Scale = 1:66.1




Plate Offsets (X,Y)-- [2:0-3-8,0-2-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.49	Vert(LL)	-0.23 11-13	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.81	Vert(CT)	-0.42 13-15	>985	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.84	Horz(CT)	0.07 10	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 209 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 B2: 2x4 SPF 1650F 1.5E
 WEBS 2x4 SPF No.2 *Except*
 W1,W2: 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-4-3 max.): 2-9.
 BOT CHORD Rigid ceiling directly applied or 8-9-10 oc bracing.
 WEBS 1 Row at midpt 9-10, 2-17, 3-16, 4-15, 6-11, 7-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 10=1381/Mechanical, 17=1609/0-4-0 (min. 0-2-10)
 Max Horz 17=238(LC 11)
 Max Uplift 10=-353(LC 9), 17=-287(LC 9)
 Max Grav 10=1482(LC 21), 17=1677(LC 22)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-20=-351/186, 3-20=-351/186, 3-4=-1243/334, 4-5=-1665/380, 5-6=-1665/380, 6-7=-1113/303
 BOT CHORD 16-17=-218/404, 16-22=-362/1214, 15-22=-362/1214, 15-23=-433/1564, 14-23=-433/1564, 14-24=-433/1564, 13-24=-433/1564, 13-25=-396/1503, 12-25=-396/1503, 12-26=-396/1503, 11-26=-396/1503, 11-27=-255/1038, 10-27=-255/1038
 WEBS 2-17=-1548/284, 2-16=-188/1194, 3-16=-1461/328, 3-15=-37789, 4-15=-591/176, 6-13=0/305, 6-11=-751/228, 7-11=-70/914, 7-10=-1641/379


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-10-15, Interior(1) 3-10-15 to 4-10-12, Exterior(2) 4-10-12 to 10-2-11, Interior(1) 10-2-11 to 37-6-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are 3x5 MT20 unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 353 lb uplift at joint 10 and 287 lb uplift at joint 17.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H13	Half Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:25 2020 Page 1
 ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-XwB1EYq_skySC7psiyq0iX5HmcBH2z18TxPwzjTri



Scale = 1:66.5





Plate Offsets (X,Y)-- [2-0-4-4,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.61	Vert(LL) -0.12	12-14	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.66	Vert(CT) -0.25	12-14	>999	180		
TCDL 10.0	Rep Stress Incr YES	WB 0.68	Horz(CT) 0.07	10	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS						
BCDL 10.0							Weight: 195 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud *Except*
 W5,W7,W8: 2x4 SPF No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 10-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (3-9-13 max.): 2-9.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 9-10, 3-17, 6-14, 6-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 10=1379/Mechanical, 17=1611/0-4-0 (min. 0-2-9)
 Max Horz 17=179(LC 11)
 Max Uplift 10=-342(LC 9), 17=-352(LC 8)
 Max Grav 10=1419(LC 21), 17=1623(LC 22)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 3-4=-1920/485, 4-5=-1920/485, 5-6=-1920/485, 6-7=-1368/373, 7-21=-1368/373, 8-21=-1368/373, 8-9=-1368/373, 9-10=-1319/375
 BOT CHORD 17-22=-376/1270, 16-22=-376/1270, 16-23=-376/1270, 15-23=-376/1270, 14-15=-376/1270, 14-24=-495/1948, 13-24=-495/1948, 12-13=-495/1948, 12-25=-495/1948, 11-25=-495/1948
 WEBS 3-17=-1780/427, 3-16=0/319, 3-14=-217/871, 4-14=-412/211, 6-12=0/319, 6-11=-854/210, 7-11=-461/239, 9-11=-430/1726


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 7-9-14, Interior(1) 7-9-14 to 37-6-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 342 lb uplift at joint 10 and 352 lb uplift at joint 17.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H14	Half Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:26 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-?6lQSuqcd1tp3Mi0QPT3GEEF?h9AwfG7FoCVxNzjTrh



Scale: 3/16"=1'





Plate Offsets (X,Y)-- [12:0-5-8,0-1-8], [13:0-1-12,0-2-8], [21:0-4-0,0-5-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.73	Vert(LL)	0.36	16-17	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.45	Vert(CT)	-0.37	16-17	>999		
TCDL 10.0	Lumber DOL 1.15	WB 1.00	Horz(CT)	-0.06	12	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 248 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x8 SP No.1
 WEBS 2x4 SPF Stud

BRACING-
 TOP CHORD 2-0-0 oc purlins (2-9-10 max.): 1-11, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 5-6-8 oc bracing.
 WEBS 1 Row at midpt 3-21, 8-13, 11-13

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 12=1735/Mechanical, 21=2019/0-4-0 (min. 0-3-7)
 Max Horz 21=115(LC 9)
 Max Uplift 12=-1274(LC 9), 21=-1441(LC 8)
 Max Grav 12=1902(LC 38), 21=2205(LC 39)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 3-27=-3233/2165, 27-28=-3233/2165, 4-28=-3233/2165, 4-29=-3233/2165, 5-29=-3233/2165, 5-30=-3233/2165, 6-30=-3233/2165, 6-31=-3930/2629, 31-32=-3930/2629, 7-32=-3930/2629, 7-33=-3930/2629, 33-34=-3930/2629, 8-34=-3930/2629, 8-35=-2026/1366, 9-35=-2026/1366, 9-36=-2026/1366, 10-36=-2026/1366, 10-37=-2026/1366, 37-38=-2026/1366, 38-39=-2026/1366, 11-39=-2026/1366, 11-12=-1785/1232
 BOT CHORD 21-41=-1302/1904, 41-42=-1302/1904, 20-42=-1302/1904, 20-43=-1302/1904, 19-43=-1302/1904, 19-44=-1302/1904, 18-44=-1302/1904, 18-45=-2658/3946, 45-46=-2658/3946, 17-46=-2658/3946, 17-47=-2658/3946, 47-48=-2658/3946, 16-48=-2658/3946, 16-49=-2236/3324, 15-49=-2236/3324, 15-50=-2236/3324, 14-50=-2236/3324, 14-51=-2236/3324, 51-52=-2236/3324, 13-52=-2236/3324
 WEBS 2-21=-310/235, 3-21=-2482/1666, 3-18=-1156/1728, 4-18=-361/334, 6-18=-946/643, 6-17=-66/295, 7-16=-362/335, 8-16=-515/772, 8-14=-70/294, 8-13=-1724/1159, 10-13=-397/369, 11-13=-1697/2545

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-10-15, Interior(1) 3-10-15 to 37-6-4 zone; cantilever left and right exposed; and vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 1274 lb uplift at joint 12 and 1441 lb uplift at joint 21.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H14	Half Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:26 2020 Page 2
 ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-?6lQSuqcd1tp3Mi0QPT3GEEf?h9AwfG7FoCVxNzjTrh

NOTES-

- 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 116 lb down and 132 lb up at 0-7-4, 102 lb down and 75 lb up at 2-8-12, 122 lb down and 136 lb up at 4-8-12, 122 lb down and 136 lb up at 6-8-12, 122 lb down and 136 lb up at 8-8-12, 122 lb down and 136 lb up at 10-8-12, 122 lb down and 136 lb up at 12-8-12, 122 lb down and 136 lb up at 14-8-12, 122 lb down and 136 lb up at 16-8-12, 122 lb down and 136 lb up at 18-8-12, 122 lb down and 136 lb up at 20-8-12, 122 lb down and 136 lb up at 22-8-12, 122 lb down and 136 lb up at 24-8-12, 122 lb down and 136 lb up at 26-8-12, 122 lb down and 136 lb up at 28-8-12, 122 lb down and 136 lb up at 30-8-12, 122 lb down and 136 lb up at 32-8-12, and 122 lb down and 136 lb up at 34-8-12, and 119 lb down and 134 lb up at 36-8-12 on top chord, and 66 lb down and 36 lb up at 0-7-4, 43 lb down and 41 lb up at 4-8-12, 43 lb down and 41 lb up at 6-8-12, 43 lb down and 41 lb up at 8-8-12, 43 lb down and 41 lb up at 10-8-12, 43 lb down and 41 lb up at 12-8-12, 43 lb down and 41 lb up at 14-8-12, 43 lb down and 41 lb up at 16-8-12, 43 lb down and 41 lb up at 18-8-12, 43 lb down and 41 lb up at 20-8-12, 43 lb down and 41 lb up at 22-8-12, 43 lb down and 41 lb up at 24-8-12, 43 lb down and 41 lb up at 26-8-12, 43 lb down and 41 lb up at 28-8-12, 43 lb down and 41 lb up at 30-8-12, 43 lb down and 41 lb up at 32-8-12, and 43 lb down and 41 lb up at 34-8-12, and 45 lb down and 39 lb up at 36-8-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-11=-60, 12-22=-20

Concentrated Loads (lb)

Vert: 2=-12 18=-13(F) 4=-27(F) 7=-27(F) 16=-13(F) 10=-27(F) 13=-13(F) 23=-43(F) 25=-27(F) 26=-27(F) 27=-27(F) 28=-27(F) 29=-27(F) 30=-27(F) 31=-27(F) 32=-27(F) 33=-27(F) 34=-27(F) 35=-27(F) 36=-27(F) 38=-27(F) 39=-33(F) 40=-18(F) 41=-13(F) 42=-13(F) 43=-13(F) 44=-13(F) 45=-13(F) 46=-13(F) 47=-13(F) 48=-13(F) 49=-13(F) 50=-13(F) 51=-13(F) 52=-13(F) 53=-13(F) 54=-15(F)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H16	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:27 2020 Page 1
ID:VI9e1jzWg7fmbBoML6pDUzzowqH-TJJofErEOL?ghWHC_7_lpRnr35SHfDBGUSy2UpzjTrg





Plate Offsets (X,Y)-- [1:0-2-12,0-1-8], [2:0-4-4,0-1-12], [5:0-4-0,Edge], [6:0-4-4,0-1-12], [12:0-6-0,0-2-0], [14:0-5-0,0-2-0]									
LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.65	Vert(LL)	-0.14 13-14	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL	1.15	BC 0.58	Vert(CT)	-0.30 13-14	>999	180		
TCDL 10.0	Rep Stress Incr	YES	WB 0.57	Horz(CT)	0.07 10	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014		Matrix-MS						
BCDL 10.0								Weight: 149 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* T2,T3: 2x4 SPF 1650F 1.5E	TOP CHORD Structural wood sheathing directly applied or 4-7-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-1-14 max.): 2-6.
BOT CHORD 2x4 SPF No.2 *Except* B3,B5: 2x4 SPF Stud	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 2x4 SPF Stud *Except* W4,W8: 2x4 SPF No.2	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 19=1167/0-4-0 (min. 0-1-13), 10=1231/0-4-0 (min. 0-1-15)
Max Horz 19=-134(LC 8)
Max Uplift 19=-192(LC 9), 10=-196(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-20=-1291/252, 20-21=-1190/262, 2-21=-1163/277, 2-22=-1386/371, 3-22=-1386/371,
3-4=-1781/431, 4-23=-1814/439, 5-23=-1814/439, 5-6=-1814/439, 6-7=-1490/314,
7-24=-1553/308, 8-24=-1617/298, 1-19=-1124/259, 8-10=-1189/275
BOT CHORD 16-17=-192/837, 4-14=-449/234, 13-14=-149/1028, 12-13=-138/1108
WEBS 2-16=-216/784, 3-16=-666/251, 14-16=-261/1329, 3-14=-111/503, 6-14=-275/919,
6-13=0/351, 1-17=-131/734, 8-12=-142/1069


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 5-0-5, Exterior(2) 5-0-5 to 9-3-4, Interior(1) 9-3-4 to 24-5-11, Exterior(2) 24-5-11 to 28-8-9, Interior(1) 28-8-9 to 30-4-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 192 lb uplift at joint 19 and 196 lb uplift at joint 10.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H17	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:28 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-xvTAtass9f7XJgsOXqWXLfK1nVouOaqQj6hb0FzjTrf



Scale = 1:53.9





Plate Offsets (X,Y)-- [2:0-4-4,0-1-12], [7:0-6-4,0-1-12], [13:0-3-0,0-0-0], [16:0-4-8,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.58	Vert(LL)	-0.15 15-16	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.62	Vert(CT)	-0.31 15-16	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.93	Horz(CT)	0.12 11	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 140 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 B3,B5: 2x4 SPF Stud
 WEBS 2x4 SPF Stud *Except*
 W4: 2x4 SPF No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-5-7 oc purlins, except end verticals, and 2-0-0 oc purlins (3-2-3 max.): 2-7.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
 8-8-0 oc bracing: 15-16
 8-8-2 oc bracing: 14-15.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 21=1167/0-4-0 (min. 0-1-13), 11=1231/0-4-0 (min. 0-1-15)
 Max Horz 21=-101(LC 10)
 Max Uplift 21=-223(LC 9), 11=-228(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-1240/261, 2-22=-1892/459, 3-22=-1892/459, 3-4=-2661/633, 4-5=-2691/634,
 5-6=-2691/634, 6-23=-1047/251, 7-23=-1047/251, 7-8=-1529/331, 8-9=-1689/325,
 1-21=-1150/246, 9-11=-1200/281
 BOT CHORD 19-20=-198/835, 18-19=-198/835, 4-16=-330/169, 15-16=-465/2179, 14-15=-465/2179,
 13-14=-193/1136
 WEBS 2-18=-315/1255, 3-18=-800/307, 16-18=-422/1753, 3-16=-185/824, 6-16=-169/609,
 6-14=-1349/336, 7-14=-148/872, 1-20=-153/824, 9-13=-186/1094


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 7-7-4, Interior(1) 7-7-4 to 26-1-11, Exterior(2) 26-1-11 to 30-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 223 lb uplift at joint 21 and 228 lb uplift at joint 11.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H18	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:29 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDuzzowqH-QhR4wtUwyFOWqRb5Y1mussCVuA173eZymR9YhzjTre



Scale = 1:50.2




Plate Offsets (X,Y)--	[2:0-4-4,0-1-12], [8:0-4-4,0-1-12], [17:0-3-0,0-2-4]
-----------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.59	Vert(LL)	0.35 13-15	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.46	Vert(CT)	-0.45 13-15	>781	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.83	Horz(CT)	0.04 9	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 143 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x6 SPF 1650F 1.5E
 WEBS 2x4 SPF Stud
 SLIDER Left 2x8 SP No.1 -4 1-4-13, Right 2x8 SP No.1 -4 1-4-13

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-0-9 oc purlins, except 2-0-0 oc purlins (2-9-10 max.): 2-8.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 7-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1185/0-4-0 (min. 0-2-0), 9=1239/0-4-0 (min. 0-2-1)
 Max Horz 1=-46(LC 17)
 Max Uplift 1=-581(LC 9), 9=-584(LC 8)
 Max Grav 1=1293(LC 41), 9=1329(LC 40)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-1342/624, 2-26=-2870/1370, 26-27=-2870/1370, 3-27=-2870/1370, 3-28=-2870/1370, 28-29=-2870/1370, 29-30=-2870/1370, 4-30=-2870/1370, 4-31=-3879/1842, 5-31=-3879/1842, 5-6=-3879/1842, 6-32=-3879/1842, 32-33=-3879/1842, 33-34=-3879/1842, 7-34=-3879/1842, 7-35=-942/468, 35-36=-942/468, 8-36=-942/468, 8-9=-1330/623
 BOT CHORD 17-37=-448/979, 37-38=-448/979, 16-38=-448/979, 16-39=-1849/3962, 39-40=-1849/3962, 40-41=-1849/3962, 15-41=-1849/3962, 14-15=-1849/3962, 14-42=-1849/3962, 13-42=-1849/3962, 13-43=-1356/2927, 43-44=-1356/2927, 44-45=-1356/2927, 12-45=-1356/2927, 12-46=-1356/2927, 46-47=-1356/2927, 11-47=-1356/2927
 WEBS 2-16=-1008/2130, 3-16=-332/210, 4-16=-1170/558, 6-13=-313/197, 7-13=-509/1082, 7-11=-2171/1030, 8-11=-319/734

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TC DL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 5-11-4, Interior(1) 5-11-4 to 27-9-11, Exterior(2) 27-9-11 to 30-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 581 lb uplift at joint 1 and 584 lb uplift at joint 9.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H18	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:29 2020 Page 2
ID:VI9e1jzWg7fmbBoML6pDUzzowqH-QhRY4wtUwyFOwqRb5Y1mussCVuAl73eZymR9YhzjTre

NOTES-

10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 76 lb down and 80 lb up at 1-8-5, 77 lb down and 73 lb up at 3-9-1, 76 lb down and 73 lb up at 5-9-1, 76 lb down and 73 lb up at 7-9-1, 76 lb down and 73 lb up at 9-9-1, 76 lb down and 73 lb up at 11-9-1, 76 lb down and 73 lb up at 13-9-1, 76 lb down and 73 lb up at 15-9-1, 76 lb down and 73 lb up at 17-9-1, 76 lb down and 73 lb up at 19-9-1, 76 lb down and 73 lb up at 21-9-1, 76 lb down and 73 lb up at 23-9-1, and 77 lb down and 73 lb up at 25-9-1, and 76 lb down and 80 lb up at 27-9-11 on top chord, and 26 lb down and 31 lb up at 1-9-1, 26 lb down and 31 lb up at 3-9-1, 26 lb down and 31 lb up at 5-9-1, 26 lb down and 31 lb up at 7-9-1, 26 lb down and 31 lb up at 9-9-1, 26 lb down and 31 lb up at 11-9-1, 26 lb down and 31 lb up at 13-9-1, 26 lb down and 31 lb up at 15-9-1, 26 lb down and 31 lb up at 17-9-1, 26 lb down and 31 lb up at 19-9-1, 26 lb down and 31 lb up at 21-9-1, 26 lb down and 31 lb up at 23-9-1, and 26 lb down and 31 lb up at 25-9-1, and 26 lb down and 31 lb up at 27-9-1 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.

11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-2=-60, 2-8=-60, 8-10=-60, 18-22=-20


Concentrated Loads (lb)

Vert: 14=-1(B) 17=-1(B) 11=-1(B) 37=-1(B) 38=-1(B) 39=-1(B) 40=-1(B) 41=-1(B) 42=-1(B) 43=-1(B) 44=-1(B) 45=-1(B) 46=-1(B) 47=-1(B)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H19	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:30 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-ut?w!Gu6hGNFYz0nffY?Q4PU6lczsgciAQAi48zjTrd



Scale = 1:20.1




Plate Offsets (X,Y)-- [2:0-0-10,0-0-10], [2:0-1-5,0-3-10], [3:0-4-4,0-1-12], [5:0-4-4,0-1-12], [6:0-0-10,0-0-10], [6:0-1-5,0-3-10]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.15	Vert(LL) -0.01	8	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.07	Vert(CT) -0.02	8	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.14	Horz(CT) 0.00	6	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 47 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x6 SPF 1650F 1.5E
WEBS 2x4 SPF Stud
WEDGE
Left: 2x4 SPF Stud , Right: 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=463/0-4-0 (min. 0-1-8), 6=407/0-4-0 (min. 0-1-8)
Max Horz 2=42(LC 16)
Max Uplift 2=-146(LC 12), 6=-146(LC 8)
Max Grav 2=464(LC 38), 6=425(LC 40)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-448/185, 3-16=-613/283, 16-17=-613/283, 4-17=-613/283, 4-18=-613/283, 18-19=-613/283, 5-19=-613/283, 5-6=-467/205
BOT CHORD 2-9=-121/318, 9-20=-123/316, 8-20=-123/316, 8-21=-116/322, 21-22=-116/322, 7-22=-116/322, 6-7=-113/324
WEBS 3-8=-146/354, 5-8=-131/340

- NOTES-**
- Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 5-7-15, Interior(1) 5-7-15 to 8-7-0, Exterior(2) 8-7-0 to 10-0-0 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - Provide adequate drainage to prevent water ponding.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 146 lb uplift at joint 2 and 146 lb uplift at joint 6.
 - This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 77 lb down and 76 lb up at 1-5-0, 81 lb down and 69 lb up at 3-5-12, 81 lb down and 69 lb up at 5-5-12, and 81 lb down and 69 lb up at 7-5-12, and 77 lb down and 76 lb up at 8-7-0 on top chord, and 16 lb down and 15 lb up at 1-5-12, 16 lb down and 15 lb up at 3-5-12, 16 lb down and 15 lb up at 5-5-12, and 16 lb down and 15 lb up at 7-5-12, and 16 lb down and 15 lb up at 8-6-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard
Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H19	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:30 2020 Page 2
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-ut?wIGu6hGNFYz0nFY?Q4PU6lczsgciAQAi48zjTrd

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-60, 3-5=-60, 5-6=-60, 10-13=-20


Concentrated Loads (lb)

Vert: 9=-4(F) 7=-4(F) 20=-4(F) 21=-4(F) 22=-4(F)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H20	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:30 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-ut?wIGu6hGNFYz0nfFY?Q4PRriaVseDiAQAi48zjTrd



Scale = 1:37.2




Plate Offsets (X,Y)-- [2:0-1-11,0-0-10], [3:0-4-4,0-1-12], [5:0-4-4,0-1-12], [6:0-1-10,0-0-11]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.36	Vert(LL)	0.03	8-15	>999	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.23	Vert(CT)	-0.05	8-9	>999		
TCDL 10.0	Rep Stress Incr YES	WB 0.30	Horz(CT)	-0.01	2	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS						
BCDL 10.0							Weight: 92 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud *Except*
W4: 2x4 SPF No.2
SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-5.
BOT CHORD Rigid ceiling directly applied or 9-3-4 oc bracing.
MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 6=453/0-4-0 (min. 0-1-8), 2=476/0-4-0 (min. 0-1-8), 9=763/0-4-0 (min. 0-1-8)
Max Horz 2=104(LC 9)
Max Uplift 6=-131(LC 13), 2=-137(LC 12), 9=-121(LC 9)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-21=-424/175, 3-21=-379/191, 3-22=-251/217, 4-22=-251/217, 4-23=-354/202, 5-23=-354/202, 5-24=-403/196, 6-24=-473/184
BOT CHORD 2-12=-371/436, 11-12=-70/254, 10-11=-71/250, 9-10=-71/250, 7-8=-30/266, 6-7=-325/443
WEBS 4-9=-505/200


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCdL=4.2psf; BCdL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 4-9-0, Exterior(2) 4-9-0 to 8-11-15, Interior(1) 8-11-15 to 15-9-0, Exterior(2) 15-9-0 to 20-1-3, Interior(1) 20-1-3 to 20-6-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 131 lb uplift at joint 6, 137 lb uplift at joint 2 and 121 lb uplift at joint 9.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H21	Half Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:31 2020 Page 1
ID:VI9e1jzWg7fmbBoML6pDUzzowqH-M4ZJVbukSaV6A7bzDz3FzHyWAipSb2YsP4wGdazjTrc



Scale = 1:43.9




Plate Offsets (X,Y)-- [2:0-1-15,0-0-6], [3:0-4-4,0-1-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0 Plate Grip DOL 1.15	TC 0.77	Vert(LL)	0.13 6-10	>846	240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.70	Vert(CT)	-0.14 6-10	>741	180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.48	Horz(CT)	0.04 2	n/a	n/a		
BCDL 10.0	Code IBC2015/TPI2014	Matrix-MS					Weight: 51 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins: 3-4.
 BOT CHORD Rigid ceiling directly applied or 5-2-14 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=409/0-4-0 (min. 0-1-8), 5=352/0-3-8 (min. 0-1-8)
 Max Horz 2=215(LC 11)
 Max Uplift 2=-54(LC 12), 5=-131(LC 9)
 Max Grav 2=443(LC 21), 5=405(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-12=-369/88
 BOT CHORD 2-7=-923/1085
 WEBS 3-6=-50/311, 3-5=-445/247

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 6-5-0, Exterior(2) 6-5-0 to 8-10-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 54 lb uplift at joint 2 and 131 lb uplift at joint 5.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H22	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:32 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-qG6hixvNDtdznHA9mgaUWVUpy6ITKaO?ekfp90zjTrb




Plate Offsets (X,Y)--	[1:0-6-13,0-2-0], [2:0-4-4,0-1-12], [4:0-4-4,0-1-12], [5:0-6-13,0-2-0], [7:0-3-0,0-2-4], [9:0-3-0,0-2-4]
-----------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.25	Vert(LL)	0.02	8	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.07	Vert(CT)	-0.03	8	>999		
TCDL 10.0	Lumber DOL 1.15	WB 0.19	Horz(CT)	0.00	1	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 62 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 2-4.
BOT CHORD 2x6 SPF 1650F 1.5E	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 5-7.
WEBS 2x4 SPF Stud	
SLIDER Left 2x8 SP No.1 -4 1-1-8, Right 2x8 SP No.1 -4 1-1-8	

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=478/0-4-0 (min. 0-1-8), 5=534/0-4-0 (min. 0-1-8)
 Max Horz 1=-42(LC 13)
 Max Uplift 1=-205(LC 9), 5=-221(LC 8)
 Max Grav 1=512(LC 41), 5=568(LC 39)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-499/245, 2-18=-779/395, 18-19=-779/395, 3-19=-779/395, 3-20=-779/395, 20-21=-779/395, 21-22=-779/395, 4-22=-779/395, 4-5=-498/260
 BOT CHORD 9-23=-158/384, 23-24=-158/384, 8-24=-158/384, 8-25=-152/379, 25-26=-152/379, 7-26=-152/379
 WEBS 2-8=-225/478, 3-8=-309/180, 4-8=-213/475

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 5-7-15, Interior(1) 5-7-15 to 10-7-0, Exterior(2) 10-7-0 to 12-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 205 lb uplift at joint 1 and 221 lb uplift at joint 5.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 71 lb down and 69 lb up at 1-5-0, 74 lb down and 63 lb up at 3-5-12, 70 lb down and 63 lb up at 5-5-12, 74 lb down and 63 lb up at 7-5-12, and 74 lb down and 63 lb up at 9-5-12, and 71 lb down and 69 lb up at 10-7-0 on top chord, and 24 lb down and 33 lb up at 1-5-12, 24 lb down and 33 lb up at 3-5-12, 24 lb down and 33 lb up at 5-5-12, 24 lb down and 33 lb up at 7-5-12, and 24 lb down and 33 lb up at 9-5-12, and 24 lb down and 33 lb up at 10-6-4 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H22	Hip Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:32 2020 Page 2
ID:V19e1jzVWg7fmbBoML6pDUzzowqH-qG6hixvNDtdznHA9mgaUWVUppy6ITKaO?ekfp90zjTrb

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15


Uniform Loads (plf)

Vert: 1-2=-60, 2-4=-60, 4-6=-60, 10-14=-20

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H24	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:33 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-ISg3wHw?_BlqPRkMKN5j21x2WYE31j9sOPMhTzjTra



Scale = 1:55.1




Plate Offsets (X,Y)-- [2:0-8-2,Edge], [5:0-4-4,0-1-12], [6:0-4-4,0-1-12], [9:0-8-2,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.42	Vert(LL)	-0.09 11-13	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.42	Vert(CT)	-0.12 11-13	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.18	Horz(CT)	0.04 9	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 115 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1: 2x4 SPF Stud
 SLIDER Left 2x8 SP No.1 -4 1-6-0, Right 2x8 SP No.1 -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-5-5 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 5-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 6-13

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=932/0-4-0 (min. 0-1-8), 9=932/0-4-0 (min. 0-1-8)
 Max Horz 2=175(LC 11)
 Max Uplift 2=-141(LC 12), 9=-141(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-434/0, 3-22=-950/219, 4-22=-888/238, 4-5=-821/281, 5-23=-580/257, 23-24=-580/257,
 6-24=-580/257, 6-7=-838/281, 7-25=-888/238, 8-25=-950/219, 8-9=-436/0
 BOT CHORD 2-13=-146/687, 12-13=-24/557, 12-26=-24/557, 11-26=-24/557, 9-11=-65/601
 WEBS 5-13=-58/318, 6-11=-89/364


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 8-1-0, Exterior(2) 8-1-0 to 12-3-15, Interior(1) 12-3-15 to 13-11-0, Exterior(2) 13-11-0 to 17-10-13, Interior(1) 17-10-13 to 22-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 141 lb uplift at joint 2 and 141 lb uplift at joint 9.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	H25	Hip	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:33 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-ISg3wHw? BlqPRkMKN5j2i1_WUD3?w9sOPMhTzjTra



Scale = 1:66.7




Plate Offsets (X,Y)-- [2:0-8-2,Edge], [5:0-4-4,0-1-12], [6:0-4-4,0-1-12], [9:0-8-2,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.25	Vert(LL)	-0.18 11-20	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.65	Vert(CT)	-0.32 11-20	>823	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.30	Horz(CT)	0.03 9	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 123 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2
 SLIDER Left 2x8 SP No.1 -4 1-6-0, Right 2x8 SP No.1 -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-9-13 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 5-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=932/0-4-0 (min. 0-1-9), 9=932/0-4-0 (min. 0-1-9)
 Max Horz 2=207(LC 11)
 Max Uplift 2=-145(LC 12), 9=-145(LC 13)
 Max Grav 2=982(LC 20), 9=982(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-673/0, 3-22=-962/216, 4-22=-827/240, 4-23=-829/263, 5-23=-735/289, 5-6=-581/268,
 6-24=-734/289, 7-24=-829/263, 7-25=-826/240, 8-25=-961/216, 8-9=-677/0
 BOT CHORD 2-26=-141/738, 26-27=-141/738, 13-27=-141/738, 12-13=-1/517, 11-12=-1/517,
 11-28=-53/640, 28-29=-53/640, 9-29=-53/640
 WEBS 4-13=-321/260, 5-13=-114/369, 6-11=-140/398, 7-11=-323/261


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 9-9-0, Exterior(2) 9-9-0 to 16-5-15, Interior(1) 16-5-15 to 22-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 145 lb uplift at joint 2 and 145 lb uplift at joint 9.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J01	Jack-Open	6	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:34 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-mfER7dxdIVuh1bJYu5dybwaBkv_IoWFI528wDvzjTrZ



Scale = 1:17.5



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.11	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.05	Vert(LL) -0.00 4-5 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.04	Vert(CT) -0.00 4-5 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP	Horz(CT) -0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 11 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-5-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=164/0-4-0 (min. 0-1-8), 3=52/Mechanical, 4=23/Mechanical
Max Horz 5=93(LC 12)
Max Uplift 3=-56(LC 12), 4=-16(LC 12)
Max Grav 5=170(LC 18), 3=69(LC 20), 4=45(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 56 lb uplift at joint 3 and 16 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J02	Jack-Open	3	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:35 2020 Page 1
 ID:VI9e1jzWg7fmbBoML6pDUzzowqH-EropLzxFVo0YelukSo8B776F1JJoXySSKiuTmLzjTrY



Scale = 1:19.3




Plate Offsets (X,Y)-- [2:0-3-0,0-1-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.52	Vert(LL)	0.00	5	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.09	Vert(CT)	-0.00	4-5	>999		
TCDL 10.0	Lumber DOL 1.15	WB 0.11	Horz(CT)	-0.00	4	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MP						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 11 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-8 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=159/0-4-0 (min. 0-1-8), 4=67/Mechanical
 Max Horz 5=106(LC 9)
 Max Uplift 4=-64(LC 9)
 Max Grav 5=251(LC 18), 4=98(LC 18)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 BOT CHORD 4-5=-313/216
 WEBS 2-4=-235/341


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 64 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J03	Jack-Open	12	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:35 2020 Page 1
ID: V19e1jzWg7fmbBoML6pDUzzowqH-EropLzxFVo0YelukSo8B776MCJKJXzJSKiuTmLzjTrY



Scale = 1:21.8



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.12	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.06	Vert(LL) -0.00 4-5 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.05	Vert(CT) -0.01 4-5 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP	Horz(CT) -0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 13 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-8-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=174/0-4-0 (min. 0-1-8), 3=62/Mechanical, 4=26/Mechanical
Max Horz 5=123(LC 12)
Max Uplift 3=-78(LC 12), 4=-27(LC 12)
Max Grav 5=174(LC 1), 3=87(LC 20), 4=51(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 2-7-12 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 78 lb uplift at joint 3 and 27 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J04	Jack-Open	2	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:35 2020 Page 1
ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-EropLzxFVo0YelukSo8B776MUJKoXzZSKiuTmLzjTrY



Scale = 1:15.8



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.11	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.03	Vert(LL) -0.00 5 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.03	Vert(CT) -0.00 4-5 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP	Horz(CT) -0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 9 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=152/0-4-0 (min. 0-1-8), 4=19/Mechanical, 3=38/Mechanical
Max Horz 5=81(LC 12)
Max Uplift 4=-21(LC 12), 3=-43(LC 12)
Max Grav 5=167(LC 18), 4=37(LC 3), 3=53(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 21 lb uplift at joint 4 and 43 lb uplift at joint 3.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J05	Jack-Open Supported Gable	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:36 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-i1MBYJyTG68PGuTx?WfQgLv7jfqGP1bZMd1lozjTrX



Scale = 1:25.3

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.24	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.11	Vert(LL) -0.00 2 n/r 120		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.07	Vert(CT) -0.00 2 n/r 90		
BCDL 10.0	Rep Stress Incr YES	Matrix-R	Horz(CT) 0.00 5 n/a n/a		
	Code IBC2015/TPI2014			Weight: 19 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud
OTHERS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-5-4 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 7=125/3-5-4 (min. 0-1-8), 5=66/3-5-4 (min. 0-1-8), 6=122/3-5-4 (min. 0-1-8)
Max Horz 7=131(LC 11)
Max Uplift 7=-45(LC 8), 5=-26(LC 9), 6=-174(LC 12)
Max Grav 7=171(LC 21), 5=75(LC 20), 6=210(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Corner(3) -0-10-8 to 2-1-8, Exterior(2) 2-1-8 to 3-3-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - 3) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 4) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Gable requires continuous bottom chord bearing.
 - 6) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
 - 7) Gable studs spaced at 2-0-0 oc.
 - 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 45 lb uplift at joint 7, 26 lb uplift at joint 5 and 174 lb uplift at joint 6.
 - 11) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J06	Jack-Open	18	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:36 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-i1MBYJytG68PGuTx?WfQgLfvjfsGQRbZMd1lozjTrX



Scale = 1:25.3



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.20	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.11	Vert(LL) -0.01 4-5 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.06	Vert(CT) -0.01 4-5 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP	Horz(CT) -0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 16 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 3-5-4 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=201/0-4-0 (min. 0-1-8), 3=87/Mechanical, 4=33/Mechanical
Max Horz 5=152(LC 12)
Max Uplift 3=106(LC 12), 4=21(LC 12)
Max Grav 5=201(LC 1), 3=119(LC 20), 4=66(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 106 lb uplift at joint 3 and 21 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J07	Jack-Open	14	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:36 2020 Page 1
ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-i1MBYJytG68PGuTx?WfQgLfXEjgvGQobZMd1lozjTrX



Scale = 1:16.7



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.11	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.04	Vert(LL) -0.00 4-5 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.04	Vert(CT) -0.00 4-5 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP	Horz(CT) -0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 10 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-2-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=158/0-4-0 (min. 0-1-8), 3=44/Mechanical, 4=21/Mechanical
Max Horz 5=86(LC 12)
Max Uplift 3=49(LC 12), 4=18(LC 12)
Max Grav 5=169(LC 18), 3=60(LC 20), 4=41(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 49 lb uplift at joint 3 and 18 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J08	Jack-Open	10	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:37 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-BEwamfv1QGGu227ZDAFDYCiP703?tbkn0NaqEzjTrW



Scale = 1:13.7




Plate Offsets (X,Y)-- [2:0-0-6,0-0-5], [2:0-3-9,0-0-10]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15	TC 0.08	Vert(LL) 0.00	7	>999	240	MT20	197/144
TCDL 10.0	Rep Stress Incr YES	BC 0.04	Vert(CT) -0.00	7	>999	180		
BCLL 0.0 *	Code IBC2015/TPI2014	WB 0.00	Horz(CT) 0.00	3	n/a	n/a		
BCDL 10.0		Matrix-MP					Weight: 7 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEDGE
Left: 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-10-8 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 3=41/Mechanical, 2=139/0-4-0 (min. 0-1-8), 4=21/Mechanical
Max Horz 2=80(LC 12)
Max Uplift 3=42(LC 12), 2=-3(LC 12), 4=-5(LC 12)
Max Grav 3=54(LC 20), 2=145(LC 18), 4=33(LC 3)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 42 lb uplift at joint 3, 3 lb uplift at joint 2 and 5 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard


Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	J09	Jack-Open	11	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:37 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-BEwamfzV1QGGu227ZDAFDYCi_70K?t4kn0NaqEzjTrW



Scale = 1:15.3



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.11	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.03	Vert(LL) -0.00 5 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.03	Vert(CT) -0.00 4-5 >999 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MP	Horz(CT) -0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 9 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 1-10-8 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 5=148/0-4-0 (min. 0-1-8), 3=33/Mechanical, 4=17/Mechanical
Max Horz 5=77(LC 12)
Max Uplift 3=-39(LC 12), 4=-22(LC 12)
Max Grav 5=167(LC 18), 3=47(LC 20), 4=36(LC 10)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 39 lb uplift at joint 3 and 22 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB01	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:38 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzowqH-fQUyz?_7ojO6VcdJ7xhulmqGXITkKru0g67NgzjTrv



Scale = 1:14.7




Plate Offsets (X,Y)--	[2:0-3-1,0-1-8], [3:0-1-12,Edge], [4:0-1-12,Edge], [5:0-3-1,0-1-8]
-----------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.26	Vert(LL)	-0.00	5	n/r	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.29	Vert(CT)	0.00	6	n/r		
TCDL 10.0	Lumber DOL 1.15	WB 0.00	Horz(CT)	0.00	5	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-R					Weight: 16 lb	FT = 20%
BCDL 10.0	Code IBC2015/TPI2014							

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-4.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=271/6-2-6 (min. 0-1-8), 5=271/6-2-6 (min. 0-1-8)
Max Horz 2=-18(LC 10)
Max Uplift 2=-50(LC 9), 5=-50(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-3=-353/196, 3-7=-313/165, 7-8=-313/165, 4-8=-313/165, 4-5=-353/196
BOT CHORD 2-5=-129/313


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 5-6-9, Interior(1) 5-6-9 to 6-1-14, Exterior(2) 6-1-14 to 7-2-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) Gable requires continuous bottom chord bearing.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 50 lb uplift at joint 2 and 50 lb uplift at joint 5.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB02	Piggyback	6	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:38 2020 Page 1
ID:VI9e1jzWg7fmbBoML6pDUzzowqH-fQUyz?_7ojO6VCdJ7xhulmks5XLhkLu0g67NgzjTrV



LOADING (psf)		SPACING-		CSI.		DEFL.				PLATES		GRIP	
TCLL	20.0	Plate Grip DOL	2-0-0	TC	0.15	Vert(LL)	-0.00	5	n/r	120	MT20	197/144	
(Roof Snow=20.0)		Lumber DOL	1.15	BC	0.08	Vert(CT)	0.00	4	n/r	90			
TCDL	10.0	Rep Stress Incr	YES	WB	0.03	Horz(CT)	0.00	4	n/a	n/a			
BCLL	0.0 *	Code IBC2015/TPI2014		Matrix-P							Weight: 21 lb	FT = 20%	
BCDL	10.0												

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=169/6-2-6 (min. 0-1-8), 4=169/6-2-6 (min. 0-1-8), 6=205/6-2-6 (min. 0-1-8)
 Max Horz 2=56(LC 11)
 Max Uplift 2=-51(LC 12), 4=-57(LC 13)
 Max Grav 2=169(LC 1), 4=171(LC 21), 6=205(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 3-2-14, Interior(1) 3-2-14 to 3-8-12, Exterior(2) 3-8-12 to 6-9-15, Interior(1) 6-9-15 to 7-2-10 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 51 lb uplift at joint 2 and 57 lb uplift at joint 4.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB03	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:39 2020 Page 1
 ID:VI9e1jzWg7fmbBoML6pDUzzowqH-7c1KAL?mZ1Wz7MCWheC7IzH1gwgfTnA1FKshv6zjTrU



Scale = 1:36.0




Plate Offsets (X,Y)-- [2:0-3-1,0-1-8], [3:0-2-8,0-0-3], [7:0-2-8,0-0-3], [10:0-2-8,0-0-3], [12:0-3-1,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.16	Vert(LL) -0.00	12	n/r	120	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.10	Vert(CT) -0.00	12	n/r	90		
TCDL 10.0	Rep Stress Incr YES	WB 0.06	Horz(CT) 0.00	12	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-S					Weight: 55 lb	FT = 20%
BCDL 10.0								

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-6, 7-10.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 19-4-15.
 (lb) - Max Horz 2=-44(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 12, 17, 18, 19, 15, 14, 2
 Max Grav All reactions 250 lb or less at joint(s) 12, 19, 14, 2 except 17=298(LC 1), 18=346(LC 1), 15=332(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
WEBS 5-18=-262/124

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 4-9-3, Interior(1) 4-9-3 to 7-11-1, Exterior(2) 7-11-1 to 10-11-1, Interior(1) 10-11-1 to 17-9-1, Exterior(2) 17-9-1 to 20-5-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are 1.5x4 MT20 unless otherwise indicated.
 - 6) Gable requires continuous bottom chord bearing.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 12, 17, 18, 19, 15, 14, 2.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 11) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB04	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:39 2020 Page 1
ID: V19e1jzWg7fmbBoML6pDUzzowqH-7c1KAL?mZ1Wz7MCWheC7IzH2iwf_Tmz1FKshv6zjTrU




Plate Offsets (X,Y)-- [2:0-3-1,0-1-8], [4:0-2-8,0-0-3], [6:0-2-8,0-0-3], [8:0-3-1,0-1-8]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL	1.15	TC 0.09	Vert(LL)	-0.00	8	n/r	MT20	197/144
(Roof Snow=20.0)	Lumber DOL	1.15	BC 0.14	Vert(CT)	0.00	8	n/r		
TCDL 10.0	Rep Stress Incr	YES	WB 0.07	Horz(CT)	0.00	8	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014		Matrix-S					Weight: 48 lb	FT = 20%
BCDL 10.0									

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 14-4-13.
 (lb) - Max Horz 2=83(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 2, 8, 11 except 12=-136(LC 12), 10=-134(LC 13)
 Max Grav All reactions 250 lb or less at joint(s) 2, 8 except 11=361(LC 23), 12=347(LC 20), 10=345(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 3-2-14, Interior(1) 3-2-14 to 5-3-13, Exterior(2) 5-3-13 to 9-6-11, Interior(1) 9-6-11 to 10-4-3, Exterior(2) 10-4-3 to 14-7-1, Interior(1) 14-7-1 to 15-5-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) Gable requires continuous bottom chord bearing.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 8, 11 except (jt=lb) 12=136, 10=134.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB05	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:39 2020 Page 1
 ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-7c1KAL?mZ1Wz7MCWheC7IzH1lf0TmG1FKshv6zjTrU



Scale = 1:39.9

Plate Offsets (X,Y)-- [2:0-3-1,0-1-8], [6:0-3-1,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.15	Vert(LL)	0.00	6	n/r	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.14	Vert(CT)	0.00	6	n/r		
TCDL 10.0	Lumber DOL 1.15	WB 0.12	Horz(CT)	0.00	6	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-S						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 52 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 14-4-13.
 (lb) - Max Horz 2=-122(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 2 except 10=-203(LC 12), 8=-203(LC 13)
 Max Grav All reactions 250 lb or less at joint(s) 2, 6 except 9=342(LC 23), 10=425(LC 20), 8=424(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 3-10=-316/242, 5-8=-316/242


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCCL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 3-2-14, Interior(1) 3-2-14 to 7-9-15, Exterior(2) 7-9-15 to 10-9-15, Interior(1) 10-9-15 to 15-5-1 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCCL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 10=203, 8=203.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB06	Piggyback	3	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:40 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-bpbiOg?OKLeqIWniEMjMqBqCUK?FCCWBU_bERZzjTrT



Scale = 1:40.1

Plate Offsets (X,Y)-- [2:0-3-1,0-1-8], [6:0-3-1,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.15	Vert(LL)	-0.00	6	n/r	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.14	Vert(CT)	0.00	6	n/r		
TCDL 10.0	Lumber DOL 1.15	WB 0.12	Horz(CT)	0.00	6	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-S						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 52 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 14-4-13.
 (lb) - Max Horz 2=-122(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 2 except 10=-203(LC 12), 8=-203(LC 13)
 Max Grav All reactions 250 lb or less at joint(s) 2, 6 except 9=342(LC 23), 10=425(LC 20), 8=424(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 3-10=-316/242, 5-8=-316/242


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 3-2-14, Interior(1) 3-2-14 to 7-10-0, Exterior(2) 7-10-0 to 10-10-0, Interior(1) 10-10-0 to 15-5-1 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Gable requires continuous bottom chord bearing.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 10=203, 8=203.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB08	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:41 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-3?94b0005emhMgMuo3FbNOMMwLcxnKieLoz?zjTrS



Scale = 1:45.1




Plate Offsets (X,Y)-- [2:0-3-1,0-1-8], [4:0-2-8,0-0-3], [6:0-2-8,0-0-3], [11:0-2-8,0-0-3], [12:0-3-1,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.17	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.13	Vert(LL) -0.00 13 n/r 120		
TCDL 10.0	Lumber DOL 1.15	WB 0.08	Vert(CT) 0.00 13 n/r 90		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.00 12 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 77 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 OTHERS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 4-6, 7-11.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 24-4-13.
 (lb) - Max Horz 2=85(LC 11)
 Max Uplift All uplift 100 lb or less at joint(s) 12, 18, 15, 14, 2 except 17=-122(LC 13), 19=-114(LC 12)
 Max Grav All reactions 250 lb or less at joint(s) 12, 2 except 17=358(LC 1), 18=314(LC 23), 19=413(LC 20), 15=308(LC 1), 14=324(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 WEBS 8-17=-275/169


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 3-2-14, Interior(1) 3-2-14 to 5-5-3, Exterior(2) 5-5-3 to 8-5-3, Interior(1) 8-5-3 to 10-2-13, Exterior(2) 10-2-13 to 12-0-6, Interior(1) 12-0-6 to 22-0-6, Exterior(2) 22-0-6 to 25-0-6, Interior(1) 25-0-6 to 25-5-1 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are 1.5x4 MT20 unless otherwise indicated.
 - 6) Gable requires continuous bottom chord bearing.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 12, 18, 15, 14, 2 except (jt=lb) 17=122, 19=114.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 11) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB09	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:42 2020 Page 1
 ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-XBjTpM1esyY_pw5MmmqwcVxZ8i?g7wTxI4LWRzjTrR



Scale = 1:44.2




Plate Offsets (X,Y)--	[2:0-3-1,0-1-8], [3:0-2-8,0-0-3], [10:0-2-8,0-0-3], [11:0-3-1,0-1-8]
-----------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.15	Vert(LL)	-0.00	12	n/r	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.12	Vert(CT)	0.00	11	n/r		
TCDL 10.0	Lumber DOL 1.15	WB 0.06	Horz(CT)	0.00	11	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-S						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 69 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2	TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-10.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
OTHERS 2x4 SPF Stud	MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 24-4-13.
 (lb) - Max Horz 2=-46(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 11, 16, 17, 18, 14, 13, 2
 Max Grav All reactions 250 lb or less at joint(s) 11, 2 except 16=319(LC 1), 17=321(LC 1), 18=298(LC 1), 14=321(LC 1), 13=298(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-2-14 to 7-3-4, Interior(1) 7-3-4 to 22-7-10, Exterior(2) 22-7-10 to 25-5-1 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are 1.5x4 MT20 unless otherwise indicated.
 - 6) Gable requires continuous bottom chord bearing.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 16, 17, 18, 14, 13, 2.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 11) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.
 - 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	PB10	Piggyback	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:42 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-XBjTpM1esyY_pw5MmmqwcYg8jyg7QTxl4LWRzjTrR



Scale = 1:17.6

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0	TC 0.11	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.06	Vert(LL) n/a - n/a 999		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.03	Vert(CT) n/a - n/a 999		
BCDL 10.0	Rep Stress Incr YES	Matrix-P	Horz(CT) 0.00 3 n/a n/a		
	Code IBC2015/TPI2014			Weight: 17 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
OTHERS 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=123/6-0-15 (min. 0-1-8), 3=123/6-0-15 (min. 0-1-8), 4=179/6-0-15 (min. 0-1-8)
Max Horz 1=43(LC 9)
Max Uplift 1=-37(LC 12), 3=-42(LC 13)
Max Grav 1=123(LC 1), 3=127(LC 20), 4=179(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Gable requires continuous bottom chord bearing.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 6) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 1, 3.
 - 7) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T01	ROOF SPECIAL GIRDER	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:43 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzowqH-?OHR0i2GdG0PczVHwUH3SpSd_YziPQMdAyyqu2uzjTrQ




Plate Offsets (X,Y)-- [3:0-4-4,0-2-0], [5:0-2-12,0-2-4], [7:0-4-4,0-2-0], [8:0-4-4,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.46	Vert(LL)	0.14	20-21	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.41	Vert(CT)	-0.27	20-21	>999		
TCDL 10.0	Lumber DOL 1.15	WB 0.69	Horz(CT)	0.06	13	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 218 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x6 SPF 1650F 1.5E
 WEBS 2x4 SPF Stud
 SLIDER Left 2x4 SPF Stud -4 1-6-0, Right 2x4 SPF Stud -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-7-0 oc purlins, except 2-0-0 oc purlins (3-7-14 max.): 3-5, 7-8.
 BOT CHORD Rigid ceiling directly applied or 9-11-7 oc bracing.
 WEBS 1 Row at midpt 5-20, 6-17, 8-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1486/Mechanical, 13=1429/0-4-0 (min. 0-2-4)
 Max Horz 1=-220(LC 8)
 Max Uplift 1=-453(LC 12), 13=-251(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-890/254, 2-3=-1753/570, 3-4=-2409/721, 4-35=-2409/721, 5-35=-2409/721, 5-6=-2199/545, 6-36=-1484/445, 7-36=-1373/470, 7-8=-1041/408, 8-37=-1818/725, 9-37=-1874/705, 9-10=-1558/424, 10-11=-1637/403, 11-38=-1614/360, 12-38=-1729/349, 12-13=-729/79
 BOT CHORD 1-39=-485/1278, 23-39=-485/1278, 23-40=-483/1283, 22-40=-483/1283, 21-22=-822/3162, 20-21=-819/3164, 19-20=-339/1634, 19-41=-339/1634, 18-41=-339/1634, 17-18=-339/1634, 16-17=-24/824, 15-16=-24/824, 13-15=-183/1264
 WEBS 3-22=-371/1572, 5-22=-1113/147, 5-20=-1763/553, 6-20=-221/951, 6-17=-1023/438, 7-17=-208/702, 17-24=-142/455, 8-24=-120/412, 8-25=-492/884, 15-25=-529/976, 9-15=-519/380

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 6-2-11, Interior(1) 6-2-11 to 19-0-5, Exterior(2) 19-0-5 to 24-4-8, Interior(1) 24-4-8 to 34-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=453, 13=251.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T01	ROOF SPECIAL GIRDER	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.310 s May 22 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:43 2020 Page 2
 ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-?OHR0i2GdG0PczVHwUH3SpSd_YziPQMdAyqu2uzjTrQ

NOTES-


- 11) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 79 lb down and 83 lb up at 1-9-12, and 79 lb down and 83 lb up at 3-9-12, and 79 lb down and 83 lb up at 5-9-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
- 12) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

LOAD CASE(S) Standard

- 1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
 - Uniform Loads (plf)
 - Vert: 1-3=-60, 3-5=-60, 5-7=-60, 7-8=-60, 8-14=-60, 27-31=-20
 - Concentrated Loads (lb)
 - Vert: 22=-48(B) 39=-48(B) 40=-48(B)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T02	Roof Special	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler
 Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:43 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-?OHR0i2GdG0PczVHwUH3SpSYDYsfPMSdAyuq2uzjTrQ



4x6 || Scale = 1:80.0




Plate Offsets (X,Y)-- [1:0-3-8,Edge], [3:0-4-4,0-2-0], [4:0-3-0,Edge], [10:0-6-12,Edge]					
LOADING (psf)	SPACING - 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.83	Vert(LL) -0.31 13-16 >999 240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.86	Vert(CT) -0.54 13-16 >750 180		
TCDL 10.0	Rep Stress Incr YES	WB 0.94	Horz(CT) 0.10 10 n/a n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS			
BCDL 10.0				Weight: 167 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W3,W8: 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except 2-0-0 oc purlins (2-7-13 max.): 3-4.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 4-16, 5-13, 8-13
 MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1359/Mechanical, 10=1413/0-4-0 (min. 0-2-8)
 Max Horz 1=-235(LC 8)
 Max Uplift 1=-253(LC 12), 10=-229(LC 13)
 Max Grav 1=1381(LC 21), 10=1584(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-353/0, 2-26=-1733/322, 26-27=-1701/333, 3-27=-1607/345, 3-28=-2284/454, 4-28=-2284/454, 4-5=-2947/651, 5-29=-1477/391, 6-29=-1351/412, 6-30=-1378/385, 7-30=-1381/367, 7-8=-1492/352, 8-31=-1715/332, 9-31=-1896/307, 9-10=-420/0
 BOT CHORD 1-17=-291/1349, 16-17=-293/1349, 16-32=-207/1512, 15-32=-207/1512, 14-15=-207/1512, 13-14=-207/1512, 13-33=-138/1357, 12-33=-138/1357, 12-34=-138/1357, 10-34=-138/1357
 WEBS 3-16=-172/1337, 4-16=-2091/539, 5-16=-393/1671, 5-13=-992/387, 6-13=-351/1454, 8-13=-574/300, 8-12=0/275


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-4-13, Interior(1) 3-4-13 to 5-2-11, Exterior(2) 5-2-11 to 8-7-8, Interior(1) 8-7-8 to 20-0-0, Exterior(2) 20-0-0 to 23-4-13, Interior(1) 23-4-13 to 34-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=253, 10=229.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T03	Roof Special	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:44 2020 Page 1
 ID:Vl9ejzWg7fmbBoML6pDUzzowqH-TarDE22uOZ8GD74TTBol?1_ibxDX8rmmObZSaKzjTrP



4x6 ||

Scale = 1:80.0





Plate Offsets (X,Y)-- [1:0-3-8,Edge], [3:0-4-4,0-2-0], [4:0-5-12,0-1-8], [9:0-6-12,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.85	Vert(LL)	-0.13 11-12	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.82	Vert(CT)	-0.26 11-12	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.80	Horz(CT)	0.11 9	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 162 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2 *Except*
 T1: 2x4 SPF 1650F 1.5E
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W3,W7: 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except 2-0-0 oc purlins (3-9-8 max.): 3-4.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 4-12, 7-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1359/Mechanical, 9=1413/0-4-0 (min. 0-2-8)
 Max Horz 1=-235(LC 8)
 Max Uplift 1=-253(LC 12), 9=-229(LC 13)
 Max Grav 1=1507(LC 21), 9=1599(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-428/96, 2-25=-1891/323, 25-26=-1781/327, 3-26=-1759/346, 3-27=-1859/414, 4-27=-1859/414, 4-28=-1518/369, 5-28=-1422/387, 5-29=-1376/391, 6-29=-1383/373, 6-7=-1494/358, 7-30=-1831/335, 8-30=-1923/310, 8-9=-402/0
 BOT CHORD 1-31=-244/1431, 16-31=-244/1431, 16-32=-245/1424, 15-32=-245/1424, 14-15=-277/1852, 14-33=-277/1852, 13-33=-277/1852, 12-13=-277/1852, 12-34=-135/1364, 11-34=-135/1364, 11-35=-135/1364, 9-35=-135/1364
 WEBS 3-16=0/315, 3-15=-127/783, 4-15=-391/174, 4-12=-1173/356, 5-12=-301/1411, 7-12=-587/294, 7-11=0/304


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-4-13, Interior(1) 3-4-13 to 7-7-8, Exterior(2) 7-7-8 to 11-0-5, Interior(1) 11-0-5 to 20-0-0, Exterior(2) 20-0-0 to 23-4-13, Interior(1) 23-4-13 to 34-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=253, 9=229.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T04	Roof Special	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:45 2020 Page 1
ID: V19e1jzWg7fmbBoML6pDUzzowqH-ymPbRO3X9tG7rHff1vJXXEXuzLXXtiRwdFJ?6mzjTr0



4x6 ||

Scale = 1:80.0




Plate Offsets (X,Y)-- [1:0-3-8,Edge], [4:0-4-4,0-2-0], [5:0-5-4,0-1-8], [10:0-6-12,Edge]					
LOADING (psf)	SPACING - 2-0-0	CSI	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.81	Vert(LL) -0.21 12-14 >999 240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.90	Vert(CT) -0.41 12-14 >999 180		
TCDL 10.0	Rep Stress Incr YES	WB 0.78	Horz(CT) 0.09 10 n/a n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS			
BCDL 10.0				Weight: 176 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
W1,W2,W8: 2x4 SPF Stud
SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-0-2 oc purlins, except 2-0-0 oc purlins (4-1-14 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 5-14, 5-12, 6-12

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1359/Mechanical, 10=1413/0-4-0 (min. 0-2-8)
Max Horz 1=-235(LC 8)
Max Uplift 1=-253(LC 12), 10=-229(LC 13)
Max Grav 1=1437(LC 20), 10=1591(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-2=-352/0, 2-26=-1798/330, 3-26=-1690/343, 3-27=-1648/369, 4-27=-1597/393,
4-28=-1522/385, 5-28=-1522/385, 5-29=-1077/317, 6-29=-964/336, 6-30=-1734/498,
7-30=-1742/480, 7-8=-1854/465, 8-31=-1706/346, 9-31=-1885/322, 9-10=-512/0
BOT CHORD 1-17=-307/1433, 16-17=-307/1433, 16-32=-171/1262, 15-32=-171/1262, 14-15=-171/1262,
13-14=-170/1494, 13-33=-170/1494, 12-33=-170/1494, 12-34=-143/1332, 34-35=-143/1332,
10-35=-143/1332
WEBS 3-16=-285/194, 4-16=-77/368, 4-14=-96/539, 5-12=-1089/308, 6-12=-396/1549,
8-12=-448/369


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-4-13, Interior(1) 3-4-13 to 10-0-5, Exterior(2) 10-0-5 to 13-5-2, Interior(1) 13-5-2 to 20-0-0, Exterior(2) 20-0-0 to 23-4-13, Interior(1) 23-4-13 to 34-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=253, 10=229.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T05	Roof Special	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:45 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-ymPbRO3X9tG7rHff1vJXXEs2LZttHlwdFJ76mzjTrO



Scale = 1:80.7

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15	TC 0.93 BC 0.82 WB 0.88	in (loc) l/defl L/d Vert(LL) -0.25 13-15 >999 240 Vert(CT) -0.45 13-15 >916 180 Horz(CT) 0.10 11 n/a n/a	MT20	197/144
TCDL 10.0 BCLL 0.0 * BCDL 10.0	Rep Stress Incr YES Code IBC2015/TPI2014	Matrix-MS		Weight: 185 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W8: 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-6-0, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied, except 2-0-0 oc purlins (4-8-4 max.): 5-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 3-17, 6-15, 7-13

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 1=1359/Mechanical, 11=1413/0-4-0 (min. 0-2-9)
 Max Horz 1=-235(LC 8)
 Max Uplift 1=-253(LC 12), 11=-229(LC 13)
 Max Grav 1=1489(LC 20), 11=1616(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-388/0, 2-27=-1856/327, 3-27=-1698/345, 3-4=-1584/369, 4-28=-1499/381, 5-28=-1491/399, 5-29=-1269/375, 6-29=-1269/375, 6-7=-1574/478, 7-30=-1960/601, 8-30=-1965/583, 8-9=-2075/568, 9-31=-1841/330, 10-31=-1960/305, 10-11=-355/0
 BOT CHORD 1-32=-290/1474, 18-32=-290/1474, 17-18=-290/1474, 16-17=-109/1157, 15-16=-109/1157, 15-33=-37/1058, 14-33=-37/1058, 14-34=-37/1058, 13-34=-37/1058, 13-35=-134/1369, 11-35=-134/1369
 WEBS 3-17=-439/254, 5-17=-107/497, 5-15=-94/274, 6-15=-1095/376, 7-15=-336/1247, 7-13=-421/873, 9-13=-525/441


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 3-4-13, Interior(1) 3-4-13 to 12-5-2, Exterior(2) 12-5-2 to 15-9-14, Interior(1) 15-9-14 to 20-0-0, Exterior(2) 20-0-0 to 23-4-13, Interior(1) 23-4-13 to 34-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 14.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 1=253, 11=229.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T06	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:46 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUZzowqH-Qyzzek49wBO_TREsbcm4S30FvtcpZ3sv2YfCzjTrN



Scale = 1:90.4




Plate Offsets (X,Y)-- [1:0-6-12,Edge], [5:0-8-8,0-1-8], [6:0-8-14,0-1-14], [7:0-6-4,0-2-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.97	Vert(LL)	-0.19 17-19	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.77	Vert(CT)	-0.38 13-27	>309	180	MT18HS	197/144
TCDL 10.0	Lumber DOL 1.15	WB 0.53	Horz(CT)	0.07 13	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 215 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF 1650F 1.5E *Except*
 T3: 2x4 SP DSS, T5,T6: 2x4 SPF No.2
 BOT CHORD 2x4 SPF 1650F 1.5E *Except*
 B2: 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W6,W8,W9: 2x4 SPF Stud
 WEDGE
 Right: 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-9-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied, except
 2-0-0 oc purlins (2-2-0 max.): 5-6.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
 6-0-0 oc bracing: 11-13.
 WEBS 1 Row at midpt 3-19, 5-17, 7-17, 8-13

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 12-4-0 except (jt=length) 1=0-4-0, 14=0-3-8.
 (lb) - Max Horz 1=-252(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 11 except 1=-215(LC 14), 13=-425(LC 15)
 Max Grav All reactions 250 lb or less at joint(s) 14 except 1=1862(LC 45), 13=1988(LC 1), 11=307(LC 41), 11=279(LC 1)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-2=-440/0, 2-28=-2351/349, 28-29=-2234/350, 29-30=-2197/357, 3-30=-2106/369,
 3-4=-1884/388, 4-31=-1773/395, 31-32=-1676/404, 5-32=-1646/420, 5-33=-1236/399,
 33-34=-1236/399, 34-35=-1236/399, 6-35=-1236/399, 6-36=-1620/417, 7-36=-1818/392,
 7-37=-1640/354, 8-37=-1697/346, 8-38=-112/563, 9-38=-113/513, 9-10=-122/505,
 10-39=-40/377, 11-39=-94/328
 BOT CHORD 1-40=-233/1848, 20-40=-233/1848, 20-41=-233/1848, 19-41=-233/1848, 18-19=-29/1325,
 18-42=-29/1325, 17-42=-29/1325, 17-43=-136/1584, 16-43=-136/1584, 15-16=-40/653,
 14-15=-40/653, 13-14=-40/653, 11-13=-302/60
 WEBS 3-19=-721/284, 5-19=-105/798, 6-17=-73/682, 7-17=-537/255, 7-16=-576/150,
 8-16=-121/1232, 8-13=-1912/450, 10-13=-514/263

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TC DL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-0-0 to 4-7-3, Interior(1) 4-7-3 to 13-3-4, Exterior(2) 13-3-4 to 17-10-7, Interior(1) 17-10-7 to 20-8-12, Exterior(2) 20-8-12 to 25-3-15, Interior(1) 25-3-15 to 46-10-8 zone; cantilever left and right exposed; and vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Provide adequate drainage to prevent water ponding.
 - 6) All plates are MT20 plates unless otherwise indicated.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T06	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:46 2020 Page 2
ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-Qyzzek49wBO_TREsbcm4S30FlvtcpZ3sv2YfCzjTrN

NOTES-

- 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 11, 11 except (jt=lb) 1=215, 13=425.
- 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
- 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T07	Piggyback Base	2	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:47 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzowqH-u9WMS45nhUWr5bp29KL?dfcC_9CSLChD5Zo6BfzjTrM

0-10-8	6-9-6	13-3-4	20-8-12	26-10-8	33-1-14	39-5-3	46-0-0	46-10-8
0-10-8	6-9-6	6-5-14	7-5-8	6-1-12	6-3-6	6-3-6	6-6-13	0-10-8

Scale = 1:91.1




Plate Offsets (X,Y)-- [2:0-6-12,Edge], [6:0-8-8,0-1-8], [7:0-8-14,0-1-14], [8:0-6-4,0-2-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.90	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.94	Vert(LL) -0.18 18-20 >999 240	MT18HS	197/144
TCDL 10.0	Lumber DOL 1.15	WB 0.79	Vert(CT) -0.30 18-20 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.05 15 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 219 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF 1650F 1.5E *Except*
 T3: 2x4 SP DSS, T5,T6: 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W6,W8,W9,W10: 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-9-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except 2-0-0 oc purlins (3-6-8 max.): 6-7.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
 WEBS 1 Row at midpt 4-20, 6-18, 8-18

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=1339/0-4-0 (min. 0-2-13), 15=2098/0-4-0 (min. 0-3-5), 12=348/0-4-0 (min. 0-1-8)
 Max Horz 2=-246(LC 10)
 Max Uplift 2=-223(LC 14), 15=-356(LC 15), 12=-129(LC 11)
 Max Grav 2=1795(LC 45), 15=2098(LC 1), 12=378(LC 41)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-388/0, 3-29=-2186/324, 29-30=-2082/325, 30-31=-2070/327, 4-31=-1940/343,
 4-5=-1710/363, 5-32=-1600/371, 32-33=-1502/380, 6-33=-1473/395, 6-34=-1028/371,
 34-35=-1028/371, 35-36=-1028/371, 7-36=-1028/371, 7-37=-1346/380, 8-37=-1539/356,
 8-38=-1147/289, 9-38=-1199/281, 9-39=-13/612, 10-39=-20/581, 10-11=-28/555,
 11-40=-296/203, 12-40=-361/164
 BOT CHORD 2-41=-224/1723, 21-41=-224/1723, 21-42=-224/1723, 20-42=-224/1723, 19-20=-20/1192,
 19-43=-20/1192, 18-43=-20/1192, 18-44=-75/1110, 17-44=-75/1110, 16-17=-278/98,
 15-16=-278/98, 14-15=-143/293, 12-14=-143/293
 WEBS 4-20=-732/285, 6-20=-106/803, 6-18=-302/79, 7-18=-61/507, 8-17=-848/184,
 9-17=-186/1695, 9-15=-1729/357, 11-15=-784/242

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCCL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 3-8-11, Interior(1) 3-8-11 to 13-3-4, Exterior(2) 13-3-4 to 17-10-7, Interior(1) 17-10-7 to 20-8-12, Exterior(2) 20-8-12 to 25-3-15, Interior(1) 25-3-15 to 46-10-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCCL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Provide adequate drainage to prevent water ponding.
 - 6) All plates are MT20 plates unless otherwise indicated.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=223, 15=356, 12=129.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T07	Piggyback Base	2	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler


Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:47 2020 Page 2
ID:V19e1jzWg7fmbBoML6pDUzzowqH-u9WMs45nhUWr5bp29KL?dfcC_9CSLChD5Zo6BfzjTrM

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T08	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:48 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-ML4k3Q6PSoeikOE11E9t9OxZaa4eUMJDxfj5zjTrL



Scale = 1:83.9




Plate Offsets (X,Y)-- [2:0-3-0,Edge], [4:0-7-2,0-2-2], [5:0-4-12,0-1-12], [6:0-6-4,0-2-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.89	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.82	Vert(LL) -0.21 18-19 >999 240		
TCDL 10.0	Lumber DOL 1.15	WB 0.89	Vert(CT) -0.37 18-19 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.04 13 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 231 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2 *Except*
 T3: 2x4 SP DSS, T4: 2x4 SPF 1650F 1.5E
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud *Except*
 W4,W5,W6,W7,W8,W10: 2x4 SPF No.2

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (3-2-2 max.): 1-2, 4-5.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 3-18, 5-18, 6-16

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 20=1279/0-4-0 (min. 0-2-6), 13=2094/0-4-0 (min. 0-3-5), 10=348/0-4-0 (min. 0-1-8)
 Max Horz 20=-296(LC 12)
 Max Uplift 20=-211(LC 14), 13=-366(LC 15), 10=-122(LC 11)
 Max Grav 20=1532(LC 37), 13=2094(LC 1), 10=376(LC 45)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-20=-1504/273, 1-24=-1506/267, 2-24=-1506/267, 2-25=-1995/392, 3-25=-1914/411,
 3-26=-1610/391, 4-26=-1453/404, 4-27=-1127/366, 27-28=-1127/366, 28-29=-1127/366,
 29-30=-1127/366, 5-30=-1127/366, 5-31=-1294/373, 31-32=-1332/356, 6-32=-1517/349,
 6-33=-1140/275, 7-33=-1191/267, 7-34=-46/597, 8-34=-53/563, 8-9=-61/537,
 9-35=-289/184, 10-35=-354/145
 BOT CHORD 19-20=-58/278, 19-36=-120/1449, 36-37=-120/1449, 18-37=-120/1449, 17-18=0/1042,
 16-17=0/1042, 16-38=-48/1104, 15-38=-48/1104, 14-15=-257/120, 13-14=-257/120,
 12-13=-125/287, 10-12=-125/287
 WEBS 1-19=-305/2057, 2-19=-1460/351, 3-19=-80/348, 3-18=-611/259, 4-18=-96/671,
 5-18=-77/273, 5-16=-66/344, 6-15=-825/191, 7-15=-196/1679, 7-13=-1697/366,
 9-13=-782/244, 9-12=0/251

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 4-2-4, Interior(1) 4-2-4 to 13-3-4, Exterior(2) 13-3-4 to 17-10-7, Interior(1) 17-10-7 to 20-8-12, Exterior(2) 20-8-12 to 25-3-15, Interior(1) 25-3-15 to 46-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Provide adequate drainage to prevent water ponding.
 - 6) The Fabrication Tolerance at joint 4 = 16%
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 20=211, 13=366, 10=122.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T08	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:49 2020 Page 2
ID:V19e1jzWg7fmbBoML6pDUzzowqH-qXe6HI61C6mZKuzRG1OTi4hZhywpp5kVYtHDFXzjTrk

NOTES-


11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T09	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:50 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-lkCUU57fzPvPy2YdqSviEIEkMMJdY3fnX0mo_zjTr



Scale = 1:90.3




Plate Offsets (X,Y)-- [2:0-6-12,0-1-8], [3:0-8-14,0-1-14], [4:0-4-12,0-1-12], [5:0-6-4,0-2-8], [18:0-3-8,0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.90	Vert(LL) -0.16	15-17	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.59	Vert(CT) -0.28	15-17	>999	180	MT18HS	197/144
TCDL 10.0	Rep Stress Incr YES	WB 0.88	Horz(CT) 0.03	12	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS						
BCDL 10.0							Weight: 229 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2 *Except*
 T1,T2: 2x4 SPF 2100F 1.8E, T3: 2x4 SP DSS, T4: 2x4 SPF 1650F 1.5E
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W3,W8,W10,W11,W12: 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (2-2-1 max.): 1-2, 3-4.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 WEBS 1 Row at midpt 1-19, 2-17, 4-17, 5-15

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 19=1280/0-4-0 (min. 0-2-9), 12=2090/0-4-0 (min. 0-3-4), 9=351/0-4-0 (min. 0-1-8)
 Max Horz 19=-316(LC 12)
 Max Uplift 19=-224(LC 14), 12=-365(LC 15), 9=-123(LC 11)
 Max Grav 19=1621(LC 36), 12=2090(LC 1), 9=378(LC 45)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-19=-1557/316, 1-23=-1347/318, 23-24=-1347/318, 2-24=-1347/318, 2-25=-1572/345,
 25-26=-1330/352, 3-26=-1298/370, 3-27=-1058/375, 27-28=-1058/375, 28-29=-1058/375,
 29-30=-1058/375, 4-30=-1058/375, 4-31=-1249/375, 31-32=-1284/358, 5-32=-1483/350,
 5-33=-1113/278, 6-33=-1170/270, 6-34=-44/584, 7-34=-51/528, 7-8=-59/497,
 8-35=-295/152, 9-35=-360/137
 BOT CHORD 19-36=-126/295, 18-36=-126/295, 18-37=-109/1423, 17-37=-109/1423, 16-17=0/1011,
 15-16=0/1011, 15-38=-49/1082, 14-38=-49/1082, 11-12=-95/293, 9-11=-95/293
 WEBS 1-18=-335/1803, 2-18=-1099/313, 2-17=-471/189, 3-17=-44/459, 4-17=-82/254,
 4-15=-62/379, 5-14=-798/190, 6-14=-196/1609, 6-12=-1674/366, 8-12=-781/244

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 4-8-15, Interior(1) 4-8-15 to 13-3-4, Exterior(2) 13-3-4 to 17-10-7, Interior(1) 17-10-7 to 20-8-12, Exterior(2) 20-8-12 to 25-3-15, Interior(1) 25-3-15 to 46-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Provide adequate drainage to prevent water ponding.
 - 6) All plates are MT20 plates unless otherwise indicated.
 - 7) The Fabrication Tolerance at joint 3 = 8%
 - 8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 19=224, 12=365, 9=123.
 - 11) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T09	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler


Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:50 2020 Page 2
ID:VI9e1jzWg7fmbBoML6pDUzzowqH-lkCUU57fzPvPy2YdqSviEIEkMMJdYY3fnX0mo_zjTrJ

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T10	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:51 2020 Page 1
ID: V19e1jzWg7fmbBoML6pDUzzowqH-mwmsiR8Hkj1GZC6pO9QxnVnvNmbvH1Co?BmJKQzjTr



Scale = 1:87.3




Plate Offsets (X,Y)-- [4:0-7-0,0-2-0], [5:0-8-14,0-1-14], [6:0-6-4,0-2-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.88	Vert(LL) -0.31	19-20	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.84	Vert(CT) -0.53	19-20	>761	180	MT18HS	197/144
TCDL 10.0	Rep Stress Incr YES	WB 0.76	Horz(CT) 0.04	13	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS						
BCDL 10.0							Weight: 243 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* T3: 2x4 SP DSS, T4: 2x4 SPF 1650F 1.5E	TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (3-1-0 max.): 1-3, 4-5.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 13-15.
WEBS 2x4 SPF No.2 *Except* W8,W10,W11,W12: 2x4 SPF Stud	WEBS 1 Row at midpt 1-20, 2-20, 3-19, 3-18, 4-16, 6-16

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 20=1286/0-4-0 (min. 0-2-13), 13=2070/0-4-0 (min. 0-3-4), 10=365/0-4-0 (min. 0-1-8)
Max Horz 20=-336(LC 12)
Max Uplift 20=-242(LC 14), 13=-361(LC 15), 10=-121(LC 11)
Max Grav 20=1781(LC 36), 13=2070(LC 1), 10=390(LC 45)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 2-24=-1317/329, 3-24=-1317/329, 3-25=-1434/393, 25-26=-1400/394, 4-26=-1363/406,
4-27=-1002/362, 27-28=-1002/362, 28-29=-1002/362, 29-30=-1002/362, 5-30=-1002/362,
5-31=-1236/376, 31-32=-1286/359, 6-32=-1437/351, 6-33=-1096/280, 7-33=-1153/272,
7-34=-36/541, 8-34=-43/481, 8-9=-51/433, 9-35=-329/141, 10-35=-394/132
BOT CHORD 20-36=0/896, 36-37=0/896, 19-37=0/896, 18-19=-56/1375, 17-18=0/1142, 17-38=0/1142,
16-38=0/1142, 16-39=-51/1072, 15-39=-51/1072, 12-13=-71/324, 10-12=-71/324
WEBS 2-20=-1698/338, 2-19=-163/1092, 3-19=-771/239, 3-18=-539/186, 4-18=-101/661,
5-16=-35/418, 6-15=-751/188, 7-15=-195/1517, 7-13=-1655/365, 9-13=-777/244


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 4-7-11, Interior(1) 4-7-11 to 13-3-4, Exterior(2) 13-3-4 to 17-10-7, Interior(1) 17-10-7 to 20-8-12, Exterior(2) 20-8-12 to 25-3-15, Interior(1) 25-3-15 to 46-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Provide adequate drainage to prevent water ponding.
 - 6) All plates are MT20 plates unless otherwise indicated.
 - 7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 20=242, 13=361, 10=121.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T11	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:52 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-E6KFvn9wV197BMh0xtxAKjJ4KAzs0UMyErVtsszjTrH



LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.87	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.67	Vert(LL) -0.17 17-19 >999 240		
TCDL 10.0	Lumber DOL 1.15	WB 0.76	Vert(CT) -0.29 17-19 >999 180		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.04 14 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 279 lb	FT = 20%

LUMBER-	BRACING-
TOP CHORD 2x4 SPF No.2 *Except* T3: 2x6 SPF 1650F 1.5E, T4: 2x4 SPF 1650F 1.5E	TOP CHORD Structural wood sheathing directly applied or 3-5-15 oc purlins, except end verticals, and 2-0-0 oc purlins (5-0-6 max.): 1-3, 4-6.
BOT CHORD 2x4 SPF No.2	BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS 2x4 SPF No.2 *Except* W1: 2x4 SPF 1650F 1.5E, W9,W11,W12,W13: 2x4 SPF Stud	WEBS 1 Row at midpt 1-22, 2-21, 3-21, 3-19, 5-19, 5-17, 7-17

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 22=1282/0-4-0 (min. 0-3-0), 14=2083/0-4-0 (min. 0-3-4), 11=356/0-4-0 (min. 0-1-8)
 Max Horz 22=-356(LC 12)
 Max Uplift 22=-296(LC 10), 14=-361(LC 15), 11=-120(LC 11)
 Max Grav 22=1914(LC 37), 14=2083(LC 1), 11=384(LC 46)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-22=-1862/351, 1-26=-914/283, 26-27=-914/283, 2-27=-914/283, 2-3=-914/283, 3-4=-1547/435, 4-28=-1174/359, 28-29=-1175/358, 5-29=-1177/358, 5-30=-1055/354, 30-31=-1054/354, 6-31=-1054/354, 6-32=-1329/368, 32-33=-1343/351, 7-33=-1397/344, 7-34=-1078/273, 8-34=-1112/265, 8-35=-41/569, 9-35=-48/521, 9-10=-56/495, 10-36=-310/150, 11-36=-376/129
 BOT CHORD 22-37=-276/366, 21-37=-276/366, 21-38=0/1331, 20-38=0/1331, 19-20=0/1332, 19-39=0/1213, 18-39=0/1213, 18-40=0/1213, 17-40=0/1213, 17-41=-45/1040, 16-41=-45/1040, 13-14=-93/307, 11-13=-93/307
 WEBS 1-21=-321/1825, 2-21=-774/209, 3-21=-802/197, 3-19=-594/224, 4-19=-194/782, 5-17=-483/125, 6-17=-94/601, 7-16=-749/187, 8-16=-192/1542, 8-14=-1668/363, 10-14=-780/244

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 4-8-15, Interior(1) 4-8-15 to 13-3-4, Exterior(2) 13-3-4 to 17-10-7, Interior(1) 17-10-7 to 20-8-12, Exterior(2) 20-8-12 to 25-3-15, Interior(1) 25-3-15 to 46-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) This truss has been designed for greater of min roof live load of 20.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 5) Provide adequate drainage to prevent water ponding.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 22=296, 14=361, 11=120.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T11	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MITek Industries, Inc. Wed Feb 19 20:38:52 2020 Page 2
ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-E6KFvn9wV197BMh0xtxAKjJ4KAzs0UMyErVtsszjTrH

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T12	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:53 2020 Page 2
ID:V19e1jzWg7fmbBoML6pDUzzowqH-jJud679YGKH_pWGCVaSPswsD6aITlvk5TVFQOlzTrG

NOTES-


12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T13	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:54 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-BVS?KTAA1ePrQrO3IzeP8PPCzhtUN4F19_xljzTrf



Scale = 1:82.3




Plate Offsets (X,Y)-- [1:0-3-0,0-1-8], [2:0-4-4,0-2-0], [4:0-2-12,0-1-12], [7:0-6-0,0-1-12], [8:0-6-8,0-2-8], [9:Edge,0-2-12], [11:0-3-8,0-2-0]

LOADING (psf)	SPACING-	2-0-0	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15		TC 0.90	Vert(LL) -0.14 16-17	>999	240		MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15		BC 0.57	Vert(CT) -0.23 16-17	>999	180		MT18HS	197/144
TCDL 10.0	Rep Stress Incr YES		WB 0.81	Horz(CT) 0.06 10	n/a	n/a			
BCLL 0.0 *	Code IBC2015/TPI2014		Matrix-MS						
BCDL 10.0								Weight: 286 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2 *Except*
T5,T6: 2x4 SPF 1650F 1.5E
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
W13,W15: 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 2-2-0 oc purlins, except end verticals, and 2-0-0 oc purlins (3-8-6 max.): 2-3, 4-7.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 2-19, 3-18, 5-17, 6-14, 8-12, 9-10, 3-17
2 Rows at 1/3 pts 1-20

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 20=1495/0-4-0 (min. 0-3-4), 10=1495/Mechanical
Max Horz 20=-314(LC 12)
Max Uplift 20=-253(LC 10), 10=-230(LC 15)
Max Grav 20=2057(LC 37), 10=1638(LC 55)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-21=-826/291, 2-21=-771/307, 2-22=-1267/345, 22-23=-1267/345, 3-23=-1267/345,
3-4=-1632/434, 4-24=-1299/362, 24-25=-1299/362, 5-25=-1299/362, 5-6=-1715/414,
6-26=-1715/414, 26-27=-1715/414, 7-27=-1715/414, 7-28=-1868/415, 28-29=-1871/397,
29-30=-1878/395, 8-30=-1922/388, 8-31=-1609/299, 31-32=-1613/292, 9-32=-1647/290,
1-20=-2026/349, 9-10=-1578/341
BOT CHORD 19-20=-259/300, 19-33=-103/649, 18-33=-103/649, 17-18=-170/1285, 17-34=-196/1669,
16-34=-196/1669, 15-16=-196/1669, 15-35=-196/1669, 14-35=-196/1669, 14-36=-152/1428,
13-36=-152/1428, 12-13=-152/1428, 12-37=-244/1507, 11-37=-244/1507
WEBS 2-19=-1451/280, 2-18=-276/1701, 3-18=-1368/262, 4-17=-182/740, 5-17=-934/190,
5-16=0/304, 6-14=-644/175, 7-14=-155/704, 7-12=-76/462, 8-12=-358/187, 8-11=-822/237,
1-19=-229/1623, 9-11=-276/1794

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 7-2-5, Interior(1) 7-2-5 to 9-0-13, Exterior(2) 9-0-13 to 12-10-0, Interior(1) 12-10-0 to 24-8-12, Exterior(2) 24-8-12 to 28-5-15, Interior(1) 28-5-15 to 37-6-4 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Unbalanced snow loads have been considered for this design.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) All plates are MT20 plates unless otherwise indicated.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 8) Refer to girder(s) for truss to truss connections.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 20=253, 10=230.
 - 10) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T13	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:54 2020 Page 2
 ID:V19e1jzVg7fmbBoML6pDUzzowqH-BVS?KTAA1ePrQfrO3IzeP8PPCzhtUN4Fi9__xlzjTrF

NOTES-

11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T14	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler


Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:55 2020 Page 2
ID:V19e1jzWg7fmbBoML6pDUzzowqH-fh?NXpBooyXi2pQad?VtxLxaaNyCDpoOwpkXTBzjTrE

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T15	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:56 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-7uZlI9CQZFfZgz?nAj06UZUifnKOyG2X9TT4?dzjTrD



Scale = 1:74.9




Plate Offsets (X,Y)-- [3:0-4-4,0-2-0], [5:0-4-4,0-2-0], [7:0-3-0,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0 (Roof Snow=20.0)	2-0-0 Plate Grip DOL 1.15 Lumber DOL 1.15	TC 0.91 BC 0.76 WB 0.85	Vert(LL) -0.18 Vert(CT) -0.31 Horz(CT) 0.06	10-11 10-11 9	>999 >999 n/a	240 180 n/a	MT20	197/144
TCDL 10.0 BCLL 0.0 * BCDL 10.0	Rep Stress Incr YES Code IBC2015/TPI2014	Matrix-MS					Weight: 233 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SPF No.2
BOT CHORD 2x4 SPF No.2
WEBS 2x4 SPF No.2 *Except*
W1,W12,W10,W11: 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-2-4 oc purlins, except end verticals, and 2-0-0 oc purlins (4-5-11 max.): 1-2, 3-5, 7-8.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 1-17, 2-16, 4-15, 4-11, 6-11

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 17=1495/0-4-0 (min. 0-2-8), 9=1495/Mechanical
Max Horz 17=-294(LC 10)
Max Uplift 17=-218(LC 8), 9=-232(LC 13)
Max Grav 17=1574(LC 2), 9=1551(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-17=-1539/336, 1-2=-800/247, 2-18=-1346/351, 3-18=-1263/372, 3-19=-999/360,
4-19=-999/360, 4-20=-1233/375, 5-20=-1233/375, 5-21=-1653/431, 6-21=-1665/408,
6-7=-1867/422, 7-22=-1418/280, 8-22=-1418/280, 8-9=-1530/318
BOT CHORD 16-17=-270/280, 16-23=-248/832, 15-23=-248/832, 15-24=-241/1352, 14-24=-241/1352,
13-14=-241/1352, 12-13=-241/1352, 12-25=-241/1352, 11-25=-241/1352, 11-26=-244/1297,
26-27=-244/1297, 10-27=-244/1297
WEBS 1-16=-335/1637, 2-16=-1344/354, 2-15=-89/404, 3-15=-56/513, 4-15=-729/207, 4-13=0/461,
4-11=-334/172, 5-11=-120/765, 6-11=-375/239, 7-10=-1353/359, 8-10=-350/1972


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCCL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-7-9, Interior(1) 3-7-9 to 9-0-13, Exterior(2) 9-0-13 to 12-10-0, Interior(1) 12-10-0 to 24-8-12, Exterior(2) 24-8-12 to 28-5-15, Interior(1) 28-5-15 to 37-6-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 17=218, 9=232.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T16	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:57 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzowqH-b478yUD2KZnQH7azkQL0m1u0BjUjhNh07DeY4zjTrC



Scale = 1:79.2




Plate Offsets (X,Y)-- [4:0-4-0-2-0], [7:0-4-4-0-2-0]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 1.00	Vert(LL) -0.10	12-14	>999	240	MT20	197/144
(Roof Snow=20.0)	Lumber DOL 1.15	BC 0.57	Vert(CT) -0.18	10-11	>999	180		
TCDL 10.0	Rep Stress Incr YES	WB 0.84	Horz(CT) 0.07	10	n/a	n/a		
BCLL 0.0 *	Code IBC2015/TPI2014	Matrix-MS						
BCDL 10.0							Weight: 265 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W14,W2,W3,W4,W12: 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-8-8 oc purlins, except end verticals, and 2-0-0 oc purlins (4-11-10 max.): 1-2, 4-7, 8-9.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 3-18, 5-17, 6-14, 8-12, 8-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 20=1495/0-4-0 (min. 0-2-6), 10=1495/Mechanical
 Max Horz 20=289(LC 9)
 Max Uplift 20=-199(LC 12), 10=-246(LC 13)
 Max Grav 20=1508(LC 2), 10=1587(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-20=-1440/272, 1-2=-359/135, 2-3=-1122/288, 3-4=-1311/397, 4-21=-963/350,
 5-21=-963/350, 5-6=-1297/405, 6-22=-1297/405, 7-22=-1297/405, 7-23=-1532/413,
 8-23=-1630/393
 BOT CHORD 19-20=-287/261, 18-19=-256/446, 17-18=-274/905, 17-25=-271/1227, 16-25=-271/1227,
 15-16=-271/1227, 15-26=-271/1227, 14-26=-271/1227, 14-27=-223/1171, 13-27=-223/1171,
 12-13=-223/1171, 12-28=-277/1386, 11-28=-277/1386, 11-29=-279/1380, 10-29=-279/1380
 WEBS 1-19=-271/1398, 2-19=-1401/333, 2-18=-142/836, 3-18=-584/153, 3-17=-88/304,
 4-17=-135/589, 5-17=-783/207, 5-16=0/305, 6-14=-318/174, 7-14=-164/339, 7-12=-70/497,
 8-12=-414/175, 8-11=0/329, 8-10=-1913/368


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 1-2-13, Interior(1) 1-2-13 to 9-0-13, Exterior(2) 9-0-13 to 12-10-0, Interior(1) 12-10-0 to 24-8-12, Exterior(2) 24-8-12 to 28-5-15, Interior(1) 28-5-15 to 37-6-4 zone; cantilever left and right exposed ; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 20=199, 10=246.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T17	Roof Special	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:57 2020 Page 1
 ID:Vl9e1jzWg7fmbBoML6pDUzzowqH-b478yUD2KZnQH7azkQL0m100BdZhkOhO7DeY4zjTrC



Scale = 1:114.3




Plate Offsets (X,Y)-- [7:0-3-0,Edge], [9:Edge,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.46	Vert(LL)	-0.56 11-13	>748	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.95	Vert(CT)	-0.88 11-13	>472	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.78	Horz(CT)	0.04 10	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 256 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2 *Except*
 B3: 2x4 SPF 1650F 1.5E
 WEBS 2x4 SPF No.2 *Except*
 W1,W2: 2x4 SPF Stud
 OTHERS 2x4 SPF No.2 T

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 3-11-6 oc purlins, except end verticals, and 2-0-0 oc purlins (4-11-3 max.): 7-9.
 BOT CHORD Rigid ceiling directly applied or 2-2-0 oc bracing.
 WEBS 1 Row at midpt 9-10, 3-16, 4-15, 4-13, 5-13, 6-13, 6-11, 7-11, 8-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 10=1382/Mechanical, 16=1608/0-4-0 (min. 0-2-15)
 Max Horz 16=436(LC 9)
 Max Uplift 10=-271(LC 13), 16=-243(LC 12)
 Max Grav 10=1638(LC 19), 16=1876(LC 20)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 3-4=-1185/337, 4-19=-1182/419, 5-19=-1090/439, 5-20=-1119/434, 6-20=-1218/407,
 6-7=-1848/481, 7-8=-1388/301
 BOT CHORD 16-22=-306/688, 22-23=-306/688, 15-23=-306/688, 15-24=-199/928, 14-24=-199/928,
 13-14=-199/928, 13-25=-209/1084, 12-25=-209/1084, 12-26=-209/1084, 11-26=-209/1084,
 11-27=-168/764, 27-28=-168/764, 10-28=-168/764
 WEBS 3-16=-1619/320, 3-15=-3/613, 4-15=-290/76, 4-13=-272/307, 5-13=-403/1114,
 6-13=-808/364, 6-11=-211/827, 7-11=-1360/415, 8-11=-149/1296, 8-10=-1601/322


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-10-15, Interior(1) 3-10-15 to 16-10-12, Exterior(2) 16-10-12 to 20-8-0, Interior(1) 20-8-0 to 37-6-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Lumber designated with a "T" is fire-retardant treated. Lumber and plate values have been reduced for fire-retardant treated lumber. Treatment chemicals shall be Hickson Dricon, Hoover Pyro-Guard, or CSI/D-Blaze. Lumber shall be redried after treating to 19% moisture content prior to fabrication. Lumber and trusses shall be protected from weather and moisture during storage, transportation, fabrication, and erection. Adequate roof ventilation required.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 10=271, 16=243.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T18	Piggyback Base	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:58 2020 Page 1
ID:V19e1jzWg7fmbBoML6pDUzzowqH-3GhWAqDg5tvHvH99I82aZ_Z5sbz3QBBqcnYB4WzjTrB



Scale = 1:78.5




Plate Offsets (X,Y)-- [3:0-4-4,0-2-0], [5:0-4-4,0-2-0], [8:0-4-4,0-2-0], [9:0-3-4,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.86	Vert(LL)	-0.36	11-12	>999	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.93	Vert(CT)	-0.60	11-12	>697	MT18HS	197/144
TCDL 10.0	Lumber DOL 1.15	WB 0.81	Horz(CT)	0.05	10	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 274 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W2: 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-9-10 oc purlins, except end verticals, and 2-0-0 oc purlins (4-11-7 max.): 3-5, 6-8.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 2-2-0 oc bracing: 12-13,11-12.
 WEBS 1 Row at midpt 2-18, 4-17, 4-13, 6-13, 6-12, 7-11, 8-11
 2 Rows at 1/3 pts 9-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 18=1609/0-4-0 (min. 0-2-11), 10=1381/Mechanical
 Max Horz 18=316(LC 9)
 Max Uplift 18=-207(LC 12), 10=-292(LC 9)
 Max Grav 18=1721(LC 22), 10=1498(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-21=-985/288, 3-21=-967/309, 3-22=-715/287, 4-22=-715/287, 4-23=-1070/367, 5-23=-1070/367, 5-6=-1345/433, 6-7=-1140/349, 7-24=-330/211, 8-24=-330/211, 8-9=-483/295, 9-10=-1679/290
 BOT CHORD 18-25=-267/452, 25-26=-267/452, 17-26=-267/452, 17-27=-321/1154, 16-27=-321/1154, 15-16=-321/1154, 14-15=-321/1154, 14-28=-321/1154, 13-28=-321/1154, 12-13=-262/1129, 12-29=-203/759, 29-30=-203/759, 11-30=-203/759
 WEBS 2-18=-1531/330, 2-17=-110/772, 3-17=-44/321, 4-17=-895/218, 4-15=0/470, 5-13=-144/616, 6-13=-650/125, 6-12=-434/237, 7-12=-146/869, 7-11=-1206/346, 9-11=-221/1459

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-10-15, Interior(1) 3-10-15 to 9-0-13, Exterior(2) 9-0-13 to 12-10-0, Interior(1) 12-10-0 to 24-8-12, Exterior(2) 24-8-12 to 25-9-14, Interior(1) 25-9-14 to 35-9-14, Exterior(2) 35-9-14 to 37-6-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) All plates are MT20 plates unless otherwise indicated.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Refer to girder(s) for truss to truss connections.
 - 8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 18=207, 10=292.
 - 9) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 10) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T19	Piggyback Base	3	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:59 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-XTFuNAEJsA18XRkMsrZp6B6EV_Oe9aR_rRikcyzjTrA




Plate Offsets (X,Y)-- [3:0-4-4,0-2-0], [8:0-4-4,0-2-0], [9:0-2-12,0-1-8], [10:Edge,0-1-8]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 1.00	Vert(LL)	-0.09 14-15	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.53	Vert(CT)	-0.16 14-15	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 1.00	Horz(CT)	0.05 10	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 265 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF No.2 *Except*
 W1,W2: 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-10-1 oc purlins, except end verticals, and 2-0-0 oc purlins (5-2-5 max.): 3-8.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 2-18, 4-17, 5-14, 7-11, 8-11, 9-10

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 18=1609/0-4-0 (min. 0-2-12), 10=1381/Mechanical
 Max Horz 18=316(LC 9)
 Max Uplift 18=-213(LC 9), 10=-282(LC 9)
 Max Grav 18=1748(LC 22), 10=1497(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-971/315, 3-21=-702/290, 4-21=-702/290, 4-5=-1187/380, 5-6=-1187/380, 6-7=-1187/380, 7-22=-413/256, 8-22=-413/256, 8-9=-576/309, 9-10=-1498/322
 BOT CHORD 18-23=-270/452, 23-24=-270/452, 17-24=-270/452, 17-25=-325/1088, 16-25=-325/1088, 15-16=-325/1088, 15-26=-325/1088, 14-26=-325/1088, 13-14=-237/927, 13-27=-237/927, 12-27=-237/927, 12-28=-237/927, 11-28=-237/927
 WEBS 2-18=-1549/338, 2-17=-126/763, 3-17=-63/337, 4-17=-906/251, 4-15=0/370, 5-14=-375/192, 7-14=-155/462, 7-12=0/383, 7-11=-1228/312, 9-11=-254/1212


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-10-15, Interior(1) 3-10-15 to 9-0-13, Exterior(2) 9-0-13 to 14-4-12, Interior(1) 14-4-12 to 34-8-12, Exterior(2) 34-8-12 to 37-6-4 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) Provide adequate drainage to prevent water ponding.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=18) 18=213, 10=282.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T20	Roof Special Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:38:59 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-XTFuNAEJsA18XRkMsrZp6B6Ns_UY9ke_rRikcyzjTrA



Scale = 1:36.7




Plate Offsets (X,Y)-- [3:0-4-4,0-1-12], [4:0-4-4,0-1-12], [7:0-4-4,0-1-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.40	Vert(LL) -0.01	11	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.15	Vert(CT) -0.02	11	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.35	Horz(CT) 0.00	8	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014							
							Weight: 124 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x8 SP No.1
 WEBS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except 2-0-0 oc purlins (6-0-0 max.): 3-4, 5-7.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 13-14, 12-13.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=395/0-4-0 (min. 0-1-8), 12=926/0-4-0 (min. 0-1-8), 8=441/0-4-0 (min. 0-1-8)
 Max Horz 2=-78(LC 10)
 Max Uplift 2=-83(LC 32), 12=-252(LC 13), 8=-163(LC 13)
 Max Grav 2=395(LC 1), 12=926(LC 1), 8=441(LC 39)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-23=-351/110, 3-23=-284/117, 4-5=-254/135, 6-28=-492/211, 28-29=-492/211, 29-30=-492/211, 7-30=-492/211, 7-8=-470/173
 BOT CHORD 12-31=-214/516, 31-32=-214/516, 11-32=-214/516, 11-33=-114/337, 33-34=-114/337, 10-34=-114/337, 8-10=-112/343
 WEBS 5-12=-390/121, 6-12=-786/326

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-1-0, Exterior(2) 3-1-0 to 6-1-0, Interior(1) 6-1-0 to 6-11-0, Exterior(2) 6-11-0 to 8-7-0, Interior(1) 8-7-0 to 19-1-0, Exterior(2) 19-1-0 to 21-4-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2 except (jt=lb) 12=252, 8=163.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 72 lb down and 68 lb up at 11-0-10, 72 lb down and 68 lb up at 13-0-10, 72 lb down and 68 lb up at 15-0-10, and 73 lb down and 68 lb up at 17-0-10, and 72 lb down and 75 lb up at 19-1-0 on top chord, and 16 lb down and 15 lb up at 11-0-10, 16 lb down and 15 lb up at 13-0-10, 16 lb down and 15 lb up at 15-0-10, and 16 lb down and 15 lb up at 17-0-10, and 16 lb down and 15 lb up at 19-0-10 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T20	Roof Special Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MITek Industries, Inc. Wed Feb 19 20:38:59 2020 Page 2
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-XTFuNAEJsA18XRkMsrZp6B6Ns_UY9ke_rRikcyzjTrA

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)


Vert: 1-3=-60, 3-4=-60, 4-5=-60, 5-7=-60, 7-9=-60, 17-20=-20

Concentrated Loads (lb)

Vert: 10=-4(F) 31=-4(F) 32=-4(F) 33=-4(F) 34=-4(F)

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T22	Roof Special Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:39:01 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-UrNeosGZOoHsmktkzGcHBcBkho7VdaOGJlBrhrzTr8



Scale = 1:39.2





Plate Offsets (X,Y)-- [2:0-3-3,0-0-6], [3:0-4-4,0-1-12], [6:0-4-12,0-1-0], [8:0-4-4,0-1-12], [9:0-2-6,0-0-5]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.38	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.38	Vert(LL) 0.10 15-17 >999 240		
TCDL 10.0	Lumber DOL 1.15	WB 0.59	Vert(CT) -0.18 15-17 >999 180		
BCLL 0.0 *	Rep Stress Incr NO	Matrix-MS	Horz(CT) 0.01 2 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 145 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x8 SP No.1
 WEBS 2x4 SPF Stud
 SLIDER Left 2x6 SPF 1650F 1.5E -4 1-1-8, Right 2x6 SPF 1650F 1.5E -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 4-4-1 oc purlins, except 2-0-0 oc purlins (3-11-4 max.): 3-5, 6-8.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 2=932/0-4-0 (min. 0-1-8), 9=932/0-4-0 (min. 0-1-8)
 Max Horz 2=-78(LC 30)
 Max Uplift 2=-340(LC 12), 9=-184(LC 8)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-977/379, 3-27=-1904/711, 27-28=-1904/711, 28-29=-1904/711, 4-29=-1904/711, 4-30=-1904/711, 30-31=-1904/711, 5-31=-1904/711, 5-6=-1834/593, 6-7=-1047/357, 7-8=-1047/357, 8-32=-861/280, 9-32=-936/273
 BOT CHORD 18-33=-261/736, 33-34=-261/736, 17-34=-261/736, 17-35=-668/2273, 16-35=-668/2273, 16-36=-668/2273, 15-36=-668/2273, 14-15=-669/2278, 13-14=-290/1219, 12-13=-109/612, 11-12=-106/609
 WEBS 3-17=-451/1332, 4-17=-339/192, 5-17=-424/175, 5-14=-1691/609, 6-14=-440/1360, 6-13=-296/135, 8-13=-195/705

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) -0-10-8 to 4-5-0, Interior(1) 4-5-0 to 13-1-0, Exterior(2) 13-1-0 to 16-0-0, Interior(1) 16-0-0 to 18-11-0, Exterior(2) 18-11-0 to 22-0-0, Interior(1) 22-0-0 to 22-10-8 zone; cantilever left and right exposed; and vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 2=340, 9=184.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
 - 10) Hanger(s) or other connection device(s) shall be provided sufficient to support concentrated load(s) 67 lb down and 69 lb up at 1-5-0, 68 lb down and 62 lb up at 3-5-12, 67 lb down and 62 lb up at 5-5-12, and 67 lb down and 62 lb up at 7-5-12, and 67 lb down and 62 lb up at 9-5-12 on top chord, and 24 lb down and 33 lb up at 1-5-12, 24 lb down and 33 lb up at 3-5-12, 24 lb down and 33 lb up at 5-5-12, and 24 lb down and 33 lb up at 7-5-12, and 24 lb down and 33 lb up at 9-5-12 on bottom chord. The design/selection of such connection device(s) is the responsibility of others.
 - 11) In the LOAD CASE(S) section, loads applied to the face of the truss are noted as front (F) or back (B).

Continued on page 2

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T22	Roof Special Girder	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler


Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:39:01 2020 Page 2
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-UrNeosGZOoHsmktzGcHBcBkho7VdaOGJlBrhrzjTr8

LOAD CASE(S) Standard

1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15

Uniform Loads (plf)

Vert: 1-3=-60, 3-5=-60, 5-6=-60, 6-8=-60, 8-10=-60, 19-23=-20



Scale = 1:40.3




Plate Offsets (X,Y)-- [3:0-4-4,0-1-12], [5:0-5-4,0-1-4], [6:0-6-4,0-1-12], [7:0-4-4,0-1-12]

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.38	in (loc) l/defl L/d	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.75	Vert(LL) -0.21 13-15 >999 240		
TCDL 10.0	Lumber DOL 1.15	WB 0.58	Vert(CT) -0.44 13-15 >594 180		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.03 10 n/a n/a		
BCDL 10.0	Code IBC2015/TPI2014			Weight: 113 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-6-12 oc purlins, except end verticals, and 2-0-0 oc purlins (5-0-13 max.): 3-5, 6-7.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 6-0-0 oc bracing: 15-16.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 16=930/0-4-0 (min. 0-1-8), 10=930/0-4-0 (min. 0-1-8)
 Max Horz 16=-135(LC 10)
 Max Uplift 16=-198(LC 12), 10=-139(LC 12)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-17=-931/168, 3-17=-818/177, 3-18=-606/173, 4-18=-606/173, 4-5=-1206/283,
 5-6=-1123/334, 6-7=-574/219, 7-19=-823/213, 19-20=-847/197, 8-20=-931/195,
 2-16=-953/198, 8-10=-888/234
 BOT CHORD 14-15=-234/1131, 13-14=-234/1131, 12-13=-154/1213, 11-12=-66/740
 WEBS 3-15=-17/439, 4-15=-664/227, 5-13=0/387, 5-12=-1222/219, 6-12=-273/1019,
 6-11=-396/112, 7-11=-51/380, 2-15=-50/635, 8-11=-25/463


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-1-8, Interior(1) 2-1-8 to 3-1-0, Exterior(2) 3-1-0 to 6-1-0, Interior(1) 6-1-0 to 14-9-0, Exterior(2) 14-9-0 to 20-3-0, Interior(1) 20-3-0 to 22-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 16=198, 10=139.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T24	Roof Special	1	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:39:02 2020 Page 1
 ID: V19e1jzWg7fmbBoML6pDUzzowqH-y1w1?CGB95PiOuSxXz7WjqktwCNwM29QXPwPDHzjTr



4x4 ||

Scale = 1:50.0




Plate Offsets (X,Y)-- [2:0-3-8,Edge], [3:0-4-4,0-1-12], [5:0-4-0,Edge], [8:0-7-14,0-0-1]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.47	Vert(LL)	-0.24 10-12	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.75	Vert(CT)	-0.49 10-12	>532	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.55	Horz(CT)	0.05 8	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS					Weight: 106 lb	FT = 20%
BCDL 10.0	Code IBC2015/TPI2014							

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud *Except*
 W4: 2x4 SPF No.2
 SLIDER Right 2x8 SP No.1 -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-2-11 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-5.
 BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.
 MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 13=936/0-4-0 (min. 0-1-8), 8=926/0-4-0 (min. 0-1-9)
 Max Horz 13=-158(LC 10)
 Max Uplift 13=-199(LC 12), 8=-155(LC 12)
 Max Grav 13=936(LC 1), 8=989(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-18=-982/181, 18-19=-912/183, 3-19=-893/198, 3-20=-625/213, 4-20=-625/213,
 4-5=-884/234, 5-6=-1148/293, 6-21=-895/214, 21-22=-913/196, 7-22=-996/191,
 2-13=-922/213
 BOT CHORD 11-12=-170/885, 11-23=-170/885, 23-24=-170/885, 10-24=-170/885, 10-25=-43/624,
 25-26=-43/624, 8-26=-43/624
 WEBS 3-12=-11/422, 4-12=-395/179, 5-10=-864/256, 6-10=-248/1191, 2-12=-34/573


- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-10-8 to 2-1-8, Interior(1) 2-1-8 to 4-9-0, Exterior(2) 4-9-0 to 7-9-0, Interior(1) 7-9-0 to 16-0-0, Exterior(2) 16-0-0 to 19-0-0, Interior(1) 19-0-0 to 22-10-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) Provide adequate drainage to prevent water ponding.
 - 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 13=199, 8=155.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
 - 9) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	Lee - Verona B
QUOTE FILE	T25	Common	3	1	Job Reference (optional)

84 Lumber 0280, Coal Center, PA 15423, Marty Stiffler

Run: 8.300 s Jun 26 2019 Print: 8.310 s May 22 2019 MiTek Industries, Inc. Wed Feb 19 20:39:02 2020 Page 1
 ID:V19e1jzWg7fmbBoML6pDUzzowqH-y1w1?CGB95PiOuSxXz7WjqkvJCSuMMyeQXPwPDHjTr



4x4 =

Scale = 1:75.4




Plate Offsets (X,Y)-- [7:0-8-2,Edge]

LOADING (psf)	SPACING-	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.32	Vert(LL)	-0.08 9-15	>999	240	MT20	197/144
(Roof Snow=20.0)	Plate Grip DOL 1.15	BC 0.43	Vert(CT)	-0.13 10-12	>999	180		
TCDL 10.0	Lumber DOL 1.15	WB 0.91	Horz(CT)	0.03 7	n/a	n/a		
BCLL 0.0 *	Rep Stress Incr YES	Matrix-MS						
BCDL 10.0	Code IBC2015/TPI2014						Weight: 116 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SPF No.2
 BOT CHORD 2x4 SPF No.2
 WEBS 2x4 SPF Stud *Except*
 W4,W5: 2x4 SPF No.2
 SLIDER Right 2x8 SP No.1 -4 1-6-0

BRACING-
 TOP CHORD Structural wood sheathing directly applied or 5-8-12 oc purlins, except end verticals.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
 WEBS 1 Row at midpt 2-9

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size) 12=860/Mechanical, 7=914/0-4-0 (min. 0-1-8)
 Max Horz 12=-251(LC 10)
 Max Uplift 12=-140(LC 13), 7=-143(LC 13)
 Max Grav 12=863(LC 21), 7=950(LC 21)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 1-17=-920/183, 2-17=-814/201, 2-18=-664/242, 3-18=-565/270, 3-19=-908/378,
 4-19=-915/361, 4-5=-949/350, 5-20=-817/207, 6-20=-973/187, 6-7=-348/0, 1-12=-796/194
 BOT CHORD 11-12=-220/314, 10-11=-220/314, 9-10=-97/709, 9-21=-49/631, 21-22=-49/631,
 7-22=-49/631
 WEBS 2-10=0/261, 2-9=-445/220, 3-9=-337/825, 5-9=-396/347, 1-10=-32/506

- NOTES-**
- 1) Wind: ASCE 7-10; Vult=115mph (3-second gust) Vasd=91mph; TCDL=4.2psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Pr. Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) 0-1-12 to 3-1-12, Interior(1) 3-1-12 to 10-8-0, Exterior(2) 10-8-0 to 13-8-0, Interior(1) 13-8-0 to 22-6-8 zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 2) TCLL: ASCE 7-10; Pf=20.0 psf (flat roof snow); Category II; Exp B; Fully Exp.; Ct=1.10
 - 3) This truss has been designed for greater of min roof live load of 12.0 psf or 2.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
 - 4) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 5) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
 - 6) Refer to girder(s) for truss to truss connections.
 - 7) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) except (jt=lb) 12=140, 7=143.
 - 8) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard