

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT 50

INITIAL SYSTEM: Pump to  
APPROVED 25% REDUCTION

REPAIR Pump to  
APPROVED 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION Top of stake FC 51/50

NO. BEDROOMS: 3

LIAR 0.4 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
<u>1</u>	<u>P</u>	<u>97.33</u>	<u>75</u>
<u>2</u>	<u>Y</u>	<u>97.00</u>	<u>75</u>
<u>3</u>	<u>P</u>	<u>96.33</u>	<u>75</u>
			<u>225</u>
<u>4</u>	<u>Y</u>	<u>96.00</u>	<u>75</u>
<u>5</u>	<u>P</u>	<u>95.59</u>	<u>75</u>
<u>6</u>	<u>Y</u>	<u>95.17</u>	<u>75</u>
			<u>225</u>

BY B. C. Rayner

DATE 07/17/2018

TYPICAL PROFILE

0-14 LS v fri gran  
14-36 scl firm SBK  
CR2 > 88"

THERE SHALL BE NO GRADING,  
CUTTING LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

