

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin
INITIAL SYSTEM: GRAY APPROVED 25% REDUCTION

LOT 52
REPAIR GRAY APPROVED 25% REDUCTION

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION Top of Stake Lot 52/51

NO. BEDROOMS: 4

LIAR 0.79 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	P	94.75	100
2	Y	94.33	100
3	P	93.75	100
			<u>300</u>
4	Y	93.17	100
5	P	92.58	100
6	Y	92.08	100
			<u>300</u>

BY B.C. Raynor

DATE 07/17/2018

TYPICAL PROFILE

0-12 LS vfr gran
12-36 sel firm SBK
CR2 > 28"

THERE SHALL BE NO GRADING,
CLIPPING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

NOT TO SCALE

