

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT 60

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR APPROVED 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION BC Lot mid/60

NO. BEDROOMS: 4

I) 0.8 gpd/ft²
LIAR R) 0.5 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	B	98.00	50
2	Y	97.25	50
3	B	96.58	50
			150
R { 4	Y	95.75	45
5	B	95.00	45
6	Y	94.17	45
7	B	93.00	45
8	Y	91.83	45
9	B	91.50	40
			265 AVAIL

BY B.C. Raynor

DATE 07/10/2018

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

(I) 0-48 LS v fri gran
CR 2 > 40"

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

(R) 0-20 LS v fri gran
20-36 SCL firm SAK
CR 2 > 30"

