

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT 61

GRAV

INITIAL SYSTEM: APPROVED 25% REDUCTION

Pump to
REPAIR APPROVED 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION D-BOX

BENCHMARK: 100.0

LOCATION 1) BC Lot IRON 61/62
2) BC Lot IRON 61/62

NO. BEDROOMS: 4

LIAR 1) 0.8 gpd/ft²
2) 0.4 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1) 1	B	101.92	50
2		101.00	50
3		100.08	50
			150
2) 4	O	99.47	70
5	Y	98.75	60
6	O	98.67	60
7	Y	98.08	60
8	O	97.17	50
			300

BY B.C. Raynor

DATE 07/16/2018

TYPICAL PROFILE

THERE SHALL BE NO GRADING,

R 1) 10-40 LS vfrigan
CR 2 > 40"

CUTTING, LOGGING OR OTHER SOIL

I 2) 0-20 LS vfrigan
20-30 SCL firm SBK
CR 2 > 32"

DISTURBANCE IN SEPTIC AREA

