

WELL CONSTRUCTION RECORD (GW-1)

1. Well Contractor Information:

Well Contractor Name: Larry Williford Jr
2803 A
 NC Well Contractor Certification Number
 Company Name: Williford's Well Drilling

2. Well Construction Permit #: _____
 List all applicable well construction permits (i.e. UIC, County, State, Variance, etc.)

3. Well Use (check well use):

Water Supply Well:

Agricultural Municipal/Public
 Geothermal (Heating/Cooling Supply) Residential Water Supply (single)
 Industrial/Commercial Residential Water Supply (shared)
 Irrigation

Non-Water Supply Well:

Monitoring Recovery

Injection Well:

Aquifer Recharge Groundwater Remediation
 Aquifer Storage and Recovery Salinity Barrier
 Aquifer Test Stormwater Drainage
 Experimental Technology Subsidence Control
 Geothermal (Closed Loop) Tracer
 Geothermal (Heating/Cooling Return) Other (explain under #21 Remarks)

4. Date Well(s) Completed: 9/24/20 Well ID# _____

5a. Well Location:

Facility/Owner Name: Nate Mullins Facility ID# (if applicable) _____
 Physical Address, City, and Zip: 1070 W. Strickland Rd Dunn NC
Hargett 1537-40-6847
 County: _____ Parcel Identification No. (PIN) _____

5b. Latitude and longitude in degrees/minutes/seconds or decimal degrees:
 (if well field, one lat/long is sufficient)
35° 19.075 N 78° 32.889 W

6. Is(are) the well(s) Permanent or Temporary

7. Is this a repair to an existing well: Yes or No
 If this is a repair, fill out known well construction information and explain the nature of the repair under #21 remarks section or on the back of this form.

8. For Geoprobe/DPT or Closed-Loop Geothermal Wells having the same construction, only 1 GW-1 is needed. Indicate TOTAL NUMBER of wells drilled: _____

9. Total well depth below land surface: 31 (ft.)
 For multiple wells list all depths if different (example- 3@200' and 2@100')

10. Static water level below top of casing: 7 (ft.)
 If water level is above casing, use "+"

11. Borehole diameter: 6 (in.)

12. Well construction method: mud Rotary
 (i.e. auger, rotary, cable, direct push, etc.)

FOR WATER SUPPLY WELLS ONLY:

13a. Yield (gpm) 8 Method of test: pumping
 13b. Disinfection type: HTH Amount: 1/4 Cup

For Internal Use Only:

14. WATER ZONES

FROM	TO	DESCRIPTION
21 ft.	25 ft.	tan sand
ft.	ft.	

15. OUTER CASING (for multi-cased wells) OR LINER (if applicable)

FROM	TO	DIAMETER	THICKNESS	MATERIAL
+1 ft.	21 ft.	2 in.	Sch 40	PVC

16. INNER CASING OR TUBING (geothermal closed-loop)

FROM	TO	DIAMETER	THICKNESS	MATERIAL
ft.	ft.	in.		
ft.	ft.	in.		

17. SCREEN

FROM	TO	DIAMETER	SLOT SIZE	THICKNESS	MATERIAL
21 ft.	25 ft.	2 in.	.012	Sch 40	PVC
ft.	ft.	in.			

18. GROUT

FROM	TO	MATERIAL	EMPLACEMENT METHOD & AMOUNT
0 ft.	20 ft.	Bentonite	2 1/2 - pour bags
ft.	ft.		
ft.	ft.		

19. SAND/GRAVEL PACK (if applicable)

FROM	TO	MATERIAL	EMPLACEMENT METHOD
20 ft.	31 ft.	#2 sand	pour
ft.	ft.		

20. DRILLING LOG (attach additional sheets if necessary)

FROM	TO	DESCRIPTION (color, hardness, soil/rock type, grain size, etc.)
0 ft.	2 ft.	tan clay
2 ft.	9 ft.	orange sandy clay
9 ft.	21 ft.	orange clay
21 ft.	25 ft.	tan sand
25 ft.	31 ft.	gray clay
ft.	ft.	
ft.	ft.	

21. REMARKS
Outer casing 25'-31'

22. Certification:
Larry Williford Jr 9/24/20
 Signature of Certified Well Contractor Date

By signing this form, I hereby certify that the well(s) was (were) constructed in accordance with 15A NCAC 02C .0100 or 15A NCAC 02C .0200 Well Construction Standards and that a copy of this record has been provided to the well owner.

23. Site diagram or additional well details:
 You may use the back of this page to provide additional well site details or well construction details. You may also attach additional pages if necessary.

SUBMITTAL INSTRUCTIONS

24a. For All Wells: Submit this form within 30 days of completion of well construction to the following:

Division of Water Resources, Information Processing Unit,
 1617 Mall Service Center, Raleigh, NC 27699-1617

24b. For Injection Wells: In addition to sending the form to the address in 24a above, also submit one copy of this form within 30 days of completion of well construction to the following:

Division of Water Resources, Underground Injection Control Program,
 1636 Mall Service Center, Raleigh, NC 27699-1636

24c. For Water Supply & Injection Wells: In addition to sending the form to the address(es) above, also submit one copy of this form within 30 days of completion of well construction to the county health department of the county