

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT 65

INITIAL SYSTEM: Gravity  
APPROVED 25% REDUCTION

REPAIR Gravity  
Approved 25% Reduction

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION BC IRON 65/64/62

NO. BEDROOMS: 4

LIAR. 5 gpd/ft<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
I { 1	O/W	100.08	60
2	B	99.67	80
3	Y	99.33	80
4a	W	98.75	20
			<u>240</u>
R { 4b	W	98.75	60
5	B	97.92	80
6	Y	97.17	80
7	W	96.42	80
8	R/Y	96.00	45
9	B	95.67	45
			<u>390 AVAIL</u>

BY B.C. Raynor

DATE 07/15/2018

TYPICAL PROFILE

0-10 LS v fri gran  
10-30 Sloam fri gran  
30-40 L-SCL firm SBK

THERE SHALL BE NO GRADING,  
CUTTING LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA

CR 2 > 40"

