Client: Weaver Development


Project: Address:

Date: 6/24/2020 Input by: Curtis Quick Job Name: The Lauren III Beams Page 1 of 6

Project #:

1.750" X 16.000" **Kerto-S LVL** 2-Ply - PASSED **GDH**

Level: Level



Member Information Reactions UNPATTERNED Ib (Uplift) Application: Brg Live Wind Type: Floor Dead Snow Const Plies: 2 Design Method: ASD 0 1840 1723 0 0 1 Moisture Condition: Dry **Building Code:** IBC 2012 2 0 1840 1723 0 0 Deflection LL: 480 Load Sharing: No Deflection TL: 360 Deck: Not Checked Importance: Normal Temperature: Temp <= 100°F **Bearings** Bearing Length Cap. React D/L lb Total Ld. Case Ld. Comb. 1-SPF 3.500" D+S 1840 / 1723 3564 L 2 - SPF 3.500" 68% 1840 / 1723 3564 L D+S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	16009 ft-lb	9'5"	39750 ft-lb	0.403 (40%)	D+S	L
Unbraced	16009 ft-lb	9'5"	16016 ft-lb	1.000 (100%)	D+S	L
Shear	2976 lb	17'3 3/8"	13739 lb	0.217 (22%)	D+S	L
LL Defl inch	0.213 (L/1035)	9'5 1/16"	0.460 (L/480)	0.460 (46%)	S	L
TL Defl inch	0.441 (L/501)	9'5 1/16"	0.613 (L/360)	0.720 (72%)	D+S	L

Design Notes

- 1 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 7'4 1/2" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Тор	183 PLF	0 PLF	183 PLF	0 PLF	0 PLF	"A" Trusses
	Self Weight				12 PLF					

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive
- Handling & Installation
- LVL beams must not be cut or drilled Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals Damaged Beams must not be used
- Design assumes top edge is laterally restrained
 Provide lateral support at bearing points to avoid
 lateral displacement and rotation
- 6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023

Client: Weaver Development

Project: Address: Date: 6/24/2020 Input by:

Curtis Quick Job Name: The Lauren III Beams Page 2 of 6


Project #:

Kerto-S LVL GDH

1.750" X 16.000"

2-Ply - PASSED

Level: Level



Multi-Ply Analysis

Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

1 3		`	,
Capacity	0.0 %		
Load	0.0 PLF		
Yield Limit per Foot	245.6 PLF		
Yield Limit per Fastener	81.9 lb.		
Yield Mode	IV		
Edge Distance	1 1/2"		
Min. End Distance	3"		
Load Combination			
Duration Factor	1.00		

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023

Manufacturer Info

Client: Weaver Development

Project: Address:


6/24/2020

Input by: Curtis Quick Job Name: The Lauren III Beams Page 3 of 6

Project #:

1.750" X 11.875" 2-Ply - PASSED GDH-1 Kerto-S LVL

Level: Level



Member Info	rmation			Reactions UNPATTERNED Ib (Uplift)					
Type:	Girder	Application:	Floor	Brg	Live	Dead	Snow	Wind	Const
Plies:	2	Design Method:	ASD	1	1610	1675	0	0	0
Moisture Condition	n: Dry	Building Code:	IBC 2012	2	1610	1675	0	0	0
Deflection LL:	480	Load Sharing:	No						
Deflection TL:	360	Deck:	Not Checked						
Importance:	Normal								
Temperature:	Temp <= 100°F								
				Bearing	gs				
				Bearin	g Length	Cap. Rea	ct D/L lb	Total Ld. Case	Ld. Comb.
				1 - SPI	3.500"	63% 167	75 / 1610	3285 L	D+L
				2 - SPI	3.500"	63% 167	75 / 1610	3285 L	D+L

Analysis Results

	•						
Ī	Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
	Moment	10756 ft-lb	7'	19911 ft-lb	0.540 (54%)	D+L	L
	Unbraced	10756 ft-lb	7'	10772 ft-lb	0.998 (100%)	D+L	L
	Shear	2713 lb	1'2 5/8"	8867 lb	0.306 (31%)	D+L	L
	LL Defl inch	0.193 (L/843)	7' 1/16"	0.339 (L/480)	0.570 (57%)	L	L
Ì	TL Defl inch	0.393 (L/413)	7' 1/16"	0.451 (L/360)	0.870 (87%)	D+L	L

Design Notes

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top must be laterally braced at a maximum of 8'2 5/8" o.c.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments	
1	Uniform			Тор	230 PLF	230 PLF	0 PLF	0 PLF	0 PLF	G1	
	Self Weight				9 PLF						

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

Informing & Installation

I. VIL beams must not be cut or drilled

Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

Damaged Beams must not be used

Design assumes top edge is laterally restrained

Design assumes top edge is laterally restrained is provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023 CSD DESIGN

Client: Weaver Development

Project: Address: Date: 6/24/2020 Input by:


Curtis Quick Job Name: The Lauren III Beams Page 4 of 6

Project #:

Kerto-S LVL GDH-1

1.750" X 11.875" 2-Ply - PASSED

Level: Level



Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

1 3		`	,
Capacity	0.0 %		
Load	0.0 PLF		
Yield Limit per Foot	163.7 PLF		
Yield Limit per Fastener	81.9 lb.		
Yield Mode	IV		
Edge Distance	1 1/2"		
Min. End Distance	3"		
Load Combination			
Duration Factor	1.00		

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023



Client: Weaver Development


Project: Address: Date: 6/24/2020 Input by:


Curtis Quick Job Name: The Lauren III Beams

Project #:

1.750" X 9.250" 2-Ply - PASSED **Kerto-S LVL** BM₁

Level: Level





Page 5 of 6

Member Information

Type:	Girder
Plies:	2
Moisture Condition:	Dry
Deflection LL:	480
Deflection TL:	360
Importance:	Normal
Temperature:	Temp <= 100°F

Application: Floor Design Method: ASD **Building Code:** IBC 2012 Load Sharing: No

Deck: Not Checked

Reactions UNPATTERNED Ib (Uplift)

Brg	Live	Dead	Snow	Wind	Const
1	0	1930	1908	0	0
2	0	1930	1908	0	0

Bearings

Bearing Length	Cap. React D/L lb	Total Ld. Case	Ld. Comb.
1 - SPF 3.500"	74% 1930 / 1908	3838 L	D+S
0 005 0500	740/ 4000 / 4000	2020 1	D.O

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4911 ft-lb	3'	14423 ft-lb	0.340 (34%)	D+S	L
Unbraced	4911 ft-lb	3'	11027 ft-lb	0.445 (45%)	D+S	L
Shear	2558 lb	5'	7943 lb	0.322 (32%)	D+S	L
LL Defl inch	0.038 (L/1754)	3'	0.139 (L/480)	0.270 (27%)	S	L
TL Defl inch	0.076 (L/872)	3'	0.185 (L/360)	0.410 (41%)	D+S	L

Design Notes

- 1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
- 2 Refer to last page of calculations for fasteners required for specified loads.
- 3 Girders are designed to be supported on the bottom edge only.
- 4 Top loads must be supported equally by all plies.
- 5 Top braced at bearings.
- 6 Bottom braced at bearings.
- 7 Lateral slenderness ratio based on single ply width

	- Lateral districts ratio based on single ply main										
ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments	
1	Uniform			Top	636 PLF	0 PLF	636 PLF	0 PLF	0 PLF	A2	

Self Weight 7 PLF

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

LVL beams must not be cut or drilled
Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

2 Damaged Beams must not be used

Design assumes top edge is laterally restrained
Provide lateral support at bearing points to avoid
lateral displacement and rotation

For flat roofs provide proper drainage to prevent ponding

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS



This design is valid until 2/26/2023

Client: Weaver Development

Project: Address: Date: 6/24/2020 Input by:

Curtis Quick Job Name: The Lauren III Beams


Project #:


Kerto-S LVL BM1

1.750" X 9.250"

2-Ply - PASSED

Level: Level





Page 6 of 6

Multi-Ply Analysis

Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c.. Maximum end distance not to exceed 6"

process processing a route or rotal and the rotal processing of the	
Capacity	0.0 %
Load	0.0 PLF
Yield Limit per Foot	163.7 PLF
Yield Limit per Fastener	81.9 lb.
Yield Mode	IV
Edge Distance	1 1/2"
Min. End Distance	3"
Load Combination	
Duration Factor	1.00

Notes

NOtes
Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

- Dry service conditions, unless noted otherwise
 LVL not to be treated with fire retardant or corrosive

Handling & Installation

- Handling & Installation

 1. UVI beams must not be cut or drilled

 2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals

 3. Damaged Beams must not be used

 4. Design assumes top edge is laterally restrained

 5. Provide lateral support at bearing points to avoid lateral displacement and rotation

6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Metsä Wood 301 Merritt 7 Building, 2nd Floor Norwalk, CT 06851 (800) 622-5850 www.metsawood.com/us ICC-ES: ESR-3633

Manufacturer Info

Comtech, Inc. 1001 S. Reilly Road, Suite #639 Fayetteville, NC USA 28314 910-864-TRUS

