

Double 1-3/4" x 9-1/4" VERSA-LAM® 2.0 3100 SP



Roof\Dropped Beams\BM1(i27) (Dropped Beam)

BC CALC® Member Report

Dry | 1 span | No cant.

June 30, 2020 08:02:38

Build 7493

Job name:

Address:

Code reports:


City, State, Zip: Customer:

File name: 2000492A.mmdl

Description: Roof\Dropped Beams\BM1(i27)

Specifier:

Designer: Company:



Total Horizontal Product Length = 15-08-08

Reaction Summary (Down / Uplift) (Ibs)

ESR-1040

| Bearing | Live | . ´ `Dead | Snow | Wind | Roof Live | |
|---------|------|-----------|------|-----------|-----------|--|
| B1, 2" | | 358 / 0 | | 271 / 625 | 711 / 135 | |
| B2 2" | | 169 / 0 | | 270 / 562 | 715 / 234 | |

| Lo | ad Summary | | | | | | Live | Dead | Snow | Wind | Roof Live | Tributary |
|-----|-------------|-------------------|------|----------|----------|------|------|------|------|------|-----------------|-----------|
| Tag | Description | Load Type | Ref. | Start | End | Loc. | 100% | 90% | 115% | 160% | 125% | |
| 0 | Self-Weight | Unf. Lin. (lb/ft) | L | 00-00-00 | 15-08-08 | Top | | 9 | | | | 00-00-00 |
| 1 | A2(c2) | Conc. Pt. (lbs) | L | 01-09-04 | 01-09-04 | Top | | 103 | | | 133 | n∖a |
| 2 | A2(c1) | Conc. Pt. (lbs) | L | 02-05-04 | 02-05-04 | Top | | 92 | | | 108 | n∖a |
| 3 | A1(c1) | Conc. Pt. (lbs) | L | 03-11-04 | 03-11-04 | Top | | 121 | | | 175 | n∖a |
| 4 | A(c5) | Conc. Pt. (lbs) | L | 05-11-04 | 05-11-04 | Top | | 12 | | | 202 | n∖a |
| 5 | A(c5) | Conc. Pt. (lbs) | L | 05-11-04 | 05-11-04 | Top | | | | | -94 | n∖a |
| 6 | A(c4) | Conc. Pt. (lbs) | L | 07-11-04 | 07-11-04 | Top | | 15 | | | 202 | n∖a |
| 7 | A(c4) | Conc. Pt. (lbs) | L | 07-11-04 | 07-11-04 | Тор | | | | | - 87 | n∖a |
| 8 | A(c3) | Conc. Pt. (lbs) | L | 09-11-04 | 09-11-04 | Top | | 8 | | | 202 | n∖a |
| 9 | A(c3) | Conc. Pt. (lbs) | L | 09-11-04 | 09-11-04 | Top | | | | | - 9 | n∖a |
| 10 | A(c2) | Conc. Pt. (lbs) | L | 11-11-04 | 11-11-04 | Top | | 16 | | | 202 | n∖a |
| 11 | A(c2) | Conc. Pt. (lbs) | L | 11-11-04 | 11-11-04 | Top | | | | | -86 | n∖a |
| 12 | A(c1) | Conc. Pt. (lbs) | L | 13-11-04 | 13-11-04 | Тор | | 12 | | | 202 | n∖a |
| 13 | A(c1) | Conc. Pt. (lbs) | L | 13-11-04 | 13-11-04 | Top | | | | | -93 | n∖a |

| Controls Summary | Value | % Allowable | Duration | Case | Location |
|-----------------------|-----------------|-------------|----------|------|----------|
| Pos. Moment | 3912 ft-lbs | 24.0% | 125% | 1 | 07-11-04 |
| Neg. Moment | -961 ft-lbs | 4.7% | 160% | 128 | 07-11-04 |
| End Shear | 1060 lbs | 13.8% | 125% | 1 | 00-11-04 |
| Total Load Deflection | L/505 (0.368") | 47.5% | n∖a | 1 | 07-08-04 |
| Live Load Deflection | L/657 (0.283") | 54.8% | n∖a | 131 | 07-11-04 |
| Total Neg. Defl. | L/999 (-0.046") | n\a | n∖a | 62 | 08-08-04 |
| Max Defl. | 0.368" | 36.8% | n∖a | 1 | 07-08-04 |
| Span / Depth | 20.1 | | | | |

| Bear | ing Supports | Dim. (LxW) | Value | % Allow Support | % Allow Member | Material |
|------|--------------|-------------|----------|--------------------|-------------------|-------------|
| B1 | Hanger | 2" x 3-1/2" | 1069 lbs | n\a | 20.4% | Hanger |
| B1 | Uplift | | 161 lbs | | | |
| B2 | Column | 2" x 3-1/2" | 883 lbs | 17.4% | 16.8% | Unspecified |
| B2 | Uplift | | 259 lbs | | | |

Cautions

Uplift of -259 lbs found at bearing B2.

Hanger model Hanger was not found. Hanger has not been analyzed for adequate capacity.





Roof\Dropped Beams\BM1(i27) (Dropped Beam)

Designer:

Company:

2000492A.mmdl

PASSED

BC CALC® Member Report

Dry | 1 span | No cant.

June 30, 2020 08:02:38

Build 7493

File name: Job name:

Description: Roof\Dropped Beams\BM1(i27) Address: Specifier:

City, State, Zip: Customer: Code reports: ESR-1040

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Design meets arbitrary (1") Maximum Total load deflection criteria.

Design meets arbitrary (0.75") Maximum live load deflection criteria.

Calculations assume unbraced length of Top: 01-10-08, Bottom: 01-10-08.


Hanger Manufacturer: Unassigned

BC CALC® analysis is based on IBC 2012.

Wind loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Connection Diagram: Full Length of Member



a minimum = 2"

c = 5-1/4"

b minimum = 3"

d = 24"

Connectors are: 3-1/4 in. Pneumatic Gun Nails

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™. ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM $^{\text{TM}}$, BC FloorValue $^{\circledR}$, VERSA-LAM®, VERSA-RIM PLUS®,



Double 1-3/4" x 11-7/8" VERSA-LAM® 2.0 3100 SP

Roof\Dropped Beams\GDH(i29) (Dropped Beam)

Dry | 1 span | No cant.

June 30, 2020 08:02:38

PASSED

BC CALC® Member Report Build 7493

City, State, Zip:


Job name: Address:

Customer: Code reports: ESR-1040 File name: 2000492A.mmdl

Roof\Dropped Beams\GDH(i29)

Specifier: Designer: Company:

Description:



Total Horizontal Product Length = 21-05-00

Reaction Summary (Down / Uplift) (lbs)

| Bearing | Live | Dead | Snow | Wind | Roof Live |
|-------------|------|----------|------|------------|------------|
| B1, 32-1/2" | | 1689 / 0 | | 876 / 1809 | 2110 / 115 |
| B2. 32-1/2" | | 1646 / 0 | | 836 / 1793 | 2011 / 127 |

| Loa | ad Summary | | | | | | Live | Dead | Snow | Wind | Roof Live | Tributary |
|-----|----------------------|-------------------|------|----------|----------|------|------|------|------|------|-----------------|-----------|
| Tag | Description | Load Type | Ref. | Start | End | Loc. | 100% | 90% | 115% | 160% | 125% | |
| 0 | Se l f-Weight | Unf. Lin. (lb/ft) | L | 00-00-00 | 21-05-00 | Top | | 12 | | | | 00-00-00 |
| 1 | Smoothed Load | Unf. Lin. (lb/ft) | L | 00-09-04 | 06-09-04 | Top | | 156 | | | 212 | n\a |
| 2 | B(c10) | Conc. Pt. (lbs) | L | 01-09-04 | 01-09-04 | Top | | | | | - 24 | n\a |
| 3 | B(c9) | Conc. Pt. (lbs) | L | 03-09-04 | 03-09-04 | Top | | | | | - 23 | n\a |
| 4 | B(c8) | Conc. Pt. (lbs) | L | 05-09-04 | 05-09-04 | Top | | | | | - 23 | n\a |
| 5 | B(c7) | Conc. Pt. (lbs) | L | 07-09-04 | 07-09-04 | Top | | 307 | | | 424 | n\a |
| 6 | B(c7) | Conc. Pt. (lbs) | L | 07-09-04 | 07-09-04 | Top | | | | | -36 | n\a |
| 7 | B1(c6) | Conc. Pt. (lbs) | L | 09-09-04 | 09-09-04 | Top | | 321 | | | 424 | n∖a |
| 8 | B1(c6) | Conc. Pt. (lbs) | L | 09-09-04 | 09-09-04 | Top | | | | | - 9 | n∖a |
| 9 | B1(c5) | Conc. Pt. (lbs) | L | 11-09-04 | 11-09-04 | Top | | 321 | | | 424 | n∖a |
| 10 | B1(c5) | Conc. Pt. (lbs) | L | 11-09-04 | 11-09-04 | Top | | | | | -10 | n∖a |
| 11 | B1(c4) | Conc. Pt. (lbs) | L | 13-09-04 | 13-09-04 | Top | | 307 | | | 424 | n\a |
| 12 | B1(c4) | Conc. Pt. (lbs) | L | 13-09-04 | 13-09-04 | Top | | | | | - 35 | n∖a |
| 13 | B1(c3) | Conc. Pt. (lbs) | L | 15-09-04 | 15-09-04 | Top | | 313 | | | 424 | n∖a |
| 14 | B1(c3) | Conc. Pt. (lbs) | L | 15-09-04 | 15-09-04 | Top | | | | | -24 | n\a |
| 15 | B1(c2) | Conc. Pt. (lbs) | L | 17-09-04 | 17-09-04 | Top | | 313 | | | 424 | n\a |
| 16 | B1(c2) | Conc. Pt. (lbs) | L | 17-09-04 | 17-09-04 | Top | | | | | -24 | n\a |
| 17 | B1(c1) | Conc. Pt. (lbs) | L | 19-09-04 | 19-09-04 | Top | | 256 | | | 305 | n\a |
| 18 | B1(c1) | Conc. Pt. (lbs) | L | 19-09-04 | 19-09-04 | Top | | | | | -34 | n\a |

| Controls Summary | Value | % Allowable | Duration | Case | Location |
|-----------------------|-----------------|-------------|----------|------|----------|
| Pos. Moment | 11624 ft-lbs | 44.8% | 125% | 1 | 09-09-04 |
| Neg. Moment | -204 ft-lbs | 0.6% | 160% | 137 | 09-09-04 |
| End Shear | 2315 lbs | 23.4% | 125% | 1 | 17-08-10 |
| Total Load Deflection | L/350 (0.552") | 68.5% | n∖a | 1 | 10-09-04 |
| Live Load Deflection | L/632 (0.306") | 57.0% | n∖a | 139 | 10-09-04 |
| Max Defl. | 0.552" | 55.2% | n∖a | 1 | 10-09-04 |
| Span / Depth | 16.3 | | | | |
| Conc. Load (B1) | 737 I bs | 8.0% | 100% | | |
| Conc. Load (B2) | 561 l bs | 6.1% | 100% | | |

| Bearin | g Supports | Dim. (LxW) | Value | % Allow Support | % Allow Member | Material |
|--------|------------|------------------|------------------|--------------------|-------------------|-----------------|
| B1 | Wall/Plate | 32-1/2" x 3-1/2" | 3800 lbs | 7.9% | 4.5% | Spruce-Pine-Fir |
| B2 | Wall/Plate | 32-1/2" x 3-1/2" | 3657 I bs | 7.6% | 4.3% | Spruce-Pine-Fir |
| B2 | Uplift | | 88 lbs | | | |



BC CALC® Member Report

Double 1-3/4" x 11-7/8" VERSA-LAM® 2,0 3100 SP

Roof\Dropped Beams\GDH(i29) (Dropped Beam)

Specifier: Designer:

Company:



June 30, 2020 08:02:38

Dry | 1 span | No cant.

Build 7493

2000492A.mmdl Job name: File name:

Description: Roof\Dropped Beams\GDH(i29) Address:

City, State, Zip: Customer: Code reports: ESR-1040

Cautions

Uplift of -88 lbs found at bearing B2.

Notes

Design meets Code minimum (L/240) Total load deflection criteria.

Design meets Code minimum (L/360) Live load deflection criteria.

Design meets arbitrary (1") Maximum Total load deflection criteria.

Design meets arbitrary (0.75") Maximum live load deflection criteria.


Calculations assume unbraced length of Top: 01-10-08, Bottom: 01-10-08.

BC CALC® analysis is based on IBC 2012.

Wind loads determined from building geometry were used in selected product's verification.

Design based on Dry Service Condition.

Connection Diagram: Full Length of Member



a minimum = 2"

c = 7-7/8"

b minimum = 3"

d = 24"

Connectors are: 3-1/4 in. Pneumatic Gun Nails

Disclosure

Use of the Boise Cascade Software is subject to the terms of the End User License Agreement (EULA). Completeness and accuracy of input must be reviewed and verified by a qualified engineer or other appropriate expert to assure its adequacy, prior to anyone relying on such output as evidence of suitability for a particular application. The output here is based on building code-accepted design properties and analysis methods. Installation of Boise Cascade engineered wood products must be in accordance with current Installation Guide and applicable building codes. To obtain Installation Guide or ask questions, please call (800)232-0788 before installation.

BC CALC®, BC FRAMER®, AJS™. ALLJOIST®, BC RIM BOARD™, BCI®, BOISE GLULAM $^{\text{TM}}$, BC FloorValue $^{\circledR}$, VERSA-LAM®, VERSA-RIM PLUS®,