

Norris Farm

Lot #12

4-Bedroom Home (480 gal./day)

<u>LINE #</u>	<u>COLOR</u>	<u>BS</u>	<u>HI</u>	<u>FS</u>	<u>ELEVATION</u>	<u>LINE LENGTH</u>	<u>Design Length</u>
TBM		2.0		100.0		<u>in field</u>	<u>installation</u>
INST. 1			102.0				
1	Red			4	98	100	100
2	Yellow			4.2	97.8	108	100
3	Pink			4.3	97.7	115	100
4	White			4.5	97.5	120	115
5	Blue			4.6	97.4	130	115
6	Orange			4.8	97.2	140	115

System

Lines 1-3

Repair

Lines 4-6

System Type

Accepted Status System

Accepted Status System

Suggested Soil LTAR

0.40

0.35

Total Line Length

300

345

Square Footage

900

1035

Proposed Trench Bottom

20-22"

20-22"

Distribution Method

Gravity to D-Box

Gravity to D-Box