SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin **LOT** 405

INITIAL SYSTEM: Pump to APPROVED 25% REDUCTION **REPAIR** Pump to Approved 25% Reduction

DISTRIBUTION: ~~D-Box~~ **DISTRIBUTION** D-Box

BENCHMARK: 100.0 **LOCATION** Back Left PoL 44/old phase

NO. BEDROOMS: 4 **LTAR** 0.4 gpd/ft²

	LINE	FLAG COLOR	ELEVATION	LENGTH
I	1	Y	96.50	80
	2	B	96.08	80
	3	Y	95.42	80
	4	B	94.75	80
				AVAIL
II	5	Y	94.17	80
	6	B	93.67	80
	7	Y	93.17	80
	8	B	93.00	80
				320 AVAIL

BY B. C. Raynor **DATE** 07/16/2018

TYPICAL PROFILE

0-18 LS vfRI gran
18-36 SCL firm sbk
CR2 > 30"

THERE SHALL BE NO GRADING,

CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA