SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT Revised 46

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR APPROVED 25% REDUCTION

DISTRIBUTION: SERIAL

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION TOP STAKE FOR 45/46

NO. BEDROOMS: 4

LTAR 0.4 GPD/FT²

	LINE	FLAG COLOR	ELEVATION	LENGTH
Initial system	1	W	99.25	125'
	2	P	98.58	150'
	3A	W	98.00	25'
				300'
	3B	W	98.00	125'
	4	P	97.67	90'
	5	Y	97.25	70'
	6	B	96.92	60'
				345' Add

BY M Eoke / BC Rayon

DATE 2/2020

TYPICAL PROFILE

0-14 LS (VFr, wgr)

14-36+ SCLoy Loam (Fi, sbk)

cr & > 32"

INFILT AT 18"

THERE SHALL BE NO GRADING, CUTTING, LOGGING OR OTHER SOIL DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.

DESIGNS DO NOT GURANTEE FUNCTIONALITY