

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT 38

INITIAL SYSTEM: Gravity APPROVED 25% RECUCTION

REPAIR Gravity APPROVED 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION BC Lot Iron 38/39

NO. BEDROOMS: 4

LTAR 0.4 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	Y	105.17	60
2	B	104.67	60
3	Y	104.25	60
4	B	103.67	60
5	Y	103.42	60

300

6	B	102.84	60
7	Y	102.33	60
8	B	102.08	60
9	Y	101.75	60
10	B	101.42	60

300

BY B.C. Raynor

DATE 07/09/2018

TYPICAL PROFILE
0-18 LS vfri gran
18-36 SCL firm SBK
CR 2 > 30"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

