

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: SUMMERLAW

LOT 40

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR APPROVED 25% REDUCTION

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION RL 39/40

NO. BEDROOMS: 4

LTAR 0.4 GPD/FT<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH
1	W	107.50	60'
2	B	103.75	60'
3	W	103.17	60'
4	B	102.50	60'
5	W	102.00	60'
			<u>300'</u>
6	B	101.67	60'
7	W	101.34	60'
8	B	101.00	60'
9	W	100.75	60'
10	B	100.42	60'
			<u>300'</u>

BY M EAKER

DATE 07/2018

TYPICAL PROFILE

0-20 W (UFI, wpl)

20-40<sup>+</sup> SCL (F<sub>o</sub>/F<sub>i</sub>, shk)

cr 2 > 36"

INSTANT AT LB<sup>1</sup>

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA  
ANY DISTURBANCE MAY CAUSE A SITE  
TO BECOME UNSUITABLE

