

3 BA

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: Summerlin

LOT 41

Grav
INITIAL SYSTEM: APPROVED 25% REDUCTION

Pump to
REPAIR APPROVED 25% Reduction

DISTRIBUTION: D-Box

DISTRIBUTION SERIAL

BENCHMARK: 100.0

1) Top of stake 41/40
LOCATION IBC Lot IRON 41/40

NO. BEDROCKS: 3

LTAR 0.4 gpd/ft²

REPAIR 0.35 gpd/ft²

LINE	FLAG COLOR	ELEVATION	LENGTH
1	Y	94.25	40
2	P	93.50	75
3	Y	92.83	85
4	P	92.00	85
4 ₃	Y	91.09	40
			<u>325</u>

R {

5	Y	101.83	75
6	P	101.50	75
7	Y	101.47	75
8	P	100.83	75
			<u>300</u>

F {

BY B.C. Raynor

DATE 07/16/2018

TYPICAL PROFILE

0-18 CL v fri gran
18-36 SCL firm SBK
CR2 > 28"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA

