

THIS LAYOUT IS TO BE USED AS A TRUSS PLACEMENT GUIDE ONLY.  
PLEASE REFER TO BUILDING PLANS FOR BUILDING CONSTRUCTION AND DETAILS,  
SUCH AS PLUMBING OR DUCT DROPS.

PROPOSED DESIGN-  
NOT FOR  
CONSTRUCTION

Job #

Q-2002182

Compton  
3814 McDougal Rd  
Lillington NC

Date Quoted:

Designer:

Sarah Billings

Guy C Lee - Clayton  
151 Hwy 42 E  
Clayton, NC  
27520

Peak Truss  
Builders, LLC  
PO Box 340, New Hill, NC 27562

- Notes:
- Exterior dimensions shown are assumed to be:
    - ☐ Out-to-out of stud
    - ☒ Out-to-out of sheathing
  - Adjust truss locations as needed for plumbing and mechanical clearance. Unless otherwise noted, trusses may be shifted as long as O.C. spacing shown is not exceeded.
  - Do not cut, drill, or otherwise damage any part of any truss without prior approval from Peak Truss.
  - Do not approve drawings if any information herein is unclear. Once ordered trusses will be fabricated as approved.
  - Please contact Peak Truss Builders with any questions. We are available to help any way we can. We can be reached at 919-545-5555 or sales@peaktruss.com

Roof Truss Loading per 2018 NC Residential Code

Top Chord Live Load 20# PSF  
Top Chord Dead Load 10# PSF  
Bottom Chord Live Load 0# PSF  
Bottom Chord Dead Load 10# PSF

Trusses are designed for additional storage load wherever a 42"x24" box will fit between the webs.

- △ - This symbol denotes left end of truss as shown on truss drawings
- - Approximate location of toilet drop. Builder please confirm.

Truss connections by others:

- ⊕ - Nailed
- ⊞ - Ledger

COMPTON  
ROOF TRUSSES  
2' OC, 1' OH

RIDGE LINE IS CENTERED ON PORCH; PLS CONFIRM DISTANCES TO PITCH BREAKS.

12' TO PEAK OF VAULT (WALLS ARE 8'-1-1/2")

Truss Connector Total List		
Manuf	Product	Qty
USP	HJC26	2
USP	JUS26	4

