


THIS LAYOUT IS INTENDED FOR THE PURPOSE OF TRUSS LOCATION AND PLACEMENT ONLY. REFER TO THE BUILDING PLANS FOR ACTUAL BUILDING CONSTRUCTION.



GENERAL NOTES:

- DO NOT CUT OR MODIFY TRUSSES
- TRUSSES ARE SPACED 24" ON CENTER UNLESS OTHERWISE NOTED
- REFER TO THE INDIVIDUAL TRUSS DESIGN DRAWINGS FOR THE LOCATION OF LATERAL BRACING AND MULTI-PLY CONNECTION REQUIREMENTS.
- PER ANSI TPI 1-2002 THE TRUSS ENGINEER IS RESPONSIBLE FOR TRUSS TO TRUSS CONNECTIONS AND TRUSS PLY TO PLY CONNECTIONS. THIS TRUSS LAYOUT PLAN RECOMMENDS TRUSS TO BEARING CONNECTIONS AND TRUSS TO BEAM CONNECTIONS WHICH SHALL BE REVIEWED BY THE BUILDING DESIGNER. IT IS THE RESPONSIBILITY OF THE BUILDING DESIGNER TO RESOLVE ALL ROOF FORCES ADEQUATELY TO THE FOUNDATION.

WIND SPEED: 130 mph

BOTTOM DEAD LOAD: 10.0 lb/ft²

TOP DEAD LOAD: 10.0 lb/ft²

TOP LIVE LOAD: 20.0 lb/ft²

PROJECT:

Master CL 2862 CP

CUSTOMER:

Caviness Land Development

MODEL:

CL 2862 CP

QUOTE #: 1800888



PRINT DATE: 6/14/2018

DRAWN BY: Rodney Evans

SCALE: N.T.S

DEDICATED TO QUALITY AND EXCELLENCE
200 EMMETT ROAD
DUNN, NORTH CAROLINA 28334
PHONE: 919-852-5700








- TO USE:**
- Select the required series and depth.
 - Determine the support condition for the nearest bearing end support or interior support (including cantilever end supports).
 - Select the row corresponding to the required Clear Span for spans between those listed, use the next largest value.
 - Select the column corresponding to the required hole diameter. For diameters between those listed, use the next largest value.
 - The intersection of the Clear Span row and Hole Diameter column gives the minimum distance from the inside face of bearing to the center of a circular hole.
 - Double check the distance to the other support using the appropriate support condition.

Depth	Clear Span (ft)	Distance from End Support					Distance from Interior or Cantilever-End Support					
		Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter	Hole Diameter		
14"	14'	1'-0"	1'-0"	1'-0"	1'-0"	2'-2"	1'-0"	1'-0"	1'-5"	2'-7"	3'-9"	-
	18'	1'-0"	1'-0"	1'-0"	1'-0"	4'-6"	1'-8"	2'-10"	3'-11"	5'-1"	6'-3"	-
	22'	1'-5"	2'-9"	4'-1"	5'-6"	7'-0"	4'-2"	5'-4"	6'-5"	7'-7"	8'-9"	-
	26'	3'-8"	5'-0"	6'-5"	8'-0"	9'-8"	6'-8"	7'-10"	8'-11"	10'-1"	11'-4"	-
16"	18'	1'-0"	1'-0"	1'-4"	2'-5"	3'-7"	4'-11"	1'-6"	2'-6"	3'-6"	4'-6"	5'-6"
	22'	1'-4"	2'-5"	3'-6"	4'-9"	6'-1"	7'-5"	4'-0"	5'-0"	6'-0"	7'-0"	8'-0"
	26'	3'-6"	4'-8"	5'-11"	7'-2"	8'-7"	10'-1"	6'-6"	7'-6"	8'-6"	9'-6"	10'-6"
	30'	5'-8"	7'-0"	8'-4"	9'-9"	11'-3"	12'-10"	9'-0"	10'-0"	11'-0"	12'-0"	13'-2"

- DESIGN ASSUMPTIONS:**
- The hole locations listed above are valid for floor joists supporting only uniform loads. The total uniform load shall not exceed 50 psf (e.g., 40 psf Live Load and 10 psf Dead Load spaced 24" o.c.).
 - Hole location is measured from the inside face of bearing to the center of a circular hole from the joist's support.
 - Clear Span has not been verified for these joists, and is chosen for informational purposes only. Verify that the joist span meets all work for the span and loading conditions needed before clearing hole location.
 - The maximum hole depths for circular holes is the joist depth less 4" except the maximum hole depth is 5" for 1 1/2" LPI joists, and 8" for 2 1/2" LPI joists.
 - Joists cannot be fastened in the span unless designated " without further analysis by a design professional.



- NOTES:**
- These particulars apply to uniformly loaded beams selected from the Quick Reference Tables on the Uniform Load Tables or designed with LPI design software before installation. For all other applications, such as beams with concentrated loads, please contact your LPI Sales/Service Representative or LPI distributor for assistance.
 - Hole locations can be determined in "Area A" provided that no more than four holes are cut with the maximum spacing described in the diagram. The maximum hole size is 1 1/2" for depths up to 9 1/2", and 2" for depths greater than 9 1/2".
 - Rectangular holes are NOT allowed.
 - DO NOT drill holes in cantilevers without prior approval from the project designer.
 - Other hole sizes and configurations MAY be possible with further engineering analysis. For more information, contact your LPI Sales/Service Representative or LPI distributor.
 - Up to three 2 1/2" holes may be drilled in "Area B" to accommodate vents and/or water lines. These holes shall be at least 17" apart. This makes shall be located in the middle third of the depth, or a minimum of 2" from the bottom and top of the beam. For beams shall be more than 9 1/2", locate holes in area designated.
 - Protect plumbing holes from moisture.



2ND FLOOR FRAMING
SCALE: 1/4" = 1'

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
FJ2	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ3	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ4	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ5	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ6	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ7	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ8	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ9	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ10	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ11	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ12	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ13	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ14	LPI 20Plus	2.5	14	1	2	2	20'-0"
FJ15	LPI 20Plus	2.5	14	1	2	2	20'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
F31	LPI-VL 2900fb-2.0E	1.75	24	1	3	3	21'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
D32	LPI-SL 1.5SE	3.5	9.25	1	1	1	16'-0"
D33	LPI-SL 1.5SE	3.5	9.25	1	1	1	16'-0"
D34	LPI-SL 1.5SE	3.5	9.25	1	1	1	16'-0"
D35	LPI-SL 1.5SE	3.5	9.25	1	1	1	16'-0"
D36	LPI-SL 1.5SE	3.5	11.875	1	1	1	21'-0"
D37	LPI-SL 1.5SE	3.5	11.875	1	1	1	16'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
B1	LPI-VL 2900fb-2.0E	1.75	24	1	3	3	16'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
R1	LPI-APA Rated OSB 1.125 X 14	1.125	14	1	18	18	12'-0"

Label	Description	Width	Depth	Qty	Plies	Pcs	Length
H1	LPI 20 Plus	2.5	14	1	1	1	16'-0"

Label	Description	Skew	Slope	Fasteners	Supported Member
B1	HUSZ-56 14 (4lin)			12 Hd	fasteners



2160 Satellite Blvd., Suite 450
Duluth, GA 30097
888-613-5078



Dealer
84 Lumber-Fayetteville #2307
Fayetteville, NC 28301
910.867.9185
Project
CL2862 GL CP
Created
January 29, 2020
Layout Name
CL2862 GL CP

Description
Caviness Land
CL2862 GL CP
Designer
Kyle Miltzer
Revised
March 25, 2020

2nd Fir ASD (USA)
IBCIRC 2015

Design Method	Building Code	Floor
LPI	IBCIRC 2015	2nd Floor
Load		40
Dead		10
Deflection Joist		
LL Span 1/		480
TL Span 1/		240
LL Cant 2L/		240
TL Cant 2L/		180
Deflection Girder		
LL Span 1/		360
TL Span 1/		240
LL Cant 2L/		240
TL Cant 2L/		180
Decking		OSB

Fastener	23/32 APA Rated Street Floor	Nailed & Glued
Legend		
3.5" Ext Wall		
3.5" Int Wall		
5.5" Int Wall		
3.5" Non-Brq Wall		
5.5" Non-Brq Wall		
5.5" Ext Wall		
Wall Opening		
LPI-APA Rated OSB 1.125 X 14		
LPI 20Plus 14		
LPI 32Plus 14		
LPI-SL 1.5SE 3.5 X 9.25		
(Dropped)		
LPI-SL 1.5SE 3.5 X 11.875		
(Dropped)		
LPI-VL 2900fb-2.0E 1.75 X 24		
1.5 X 9.25 (Dropped)		



Small text at the bottom left corner of the page, likely a disclaimer or copyright notice.