

Olde Mill Village 4-Bedroom Septic Proposal Lot #19

Village Bend Drive
50' Public R/W

Drive
62.20'

40'

.09

- #1 Pink 100'
- #2 Orange 100'
- #3 Red 100'
- #4 Blue 100'
- #5 Yellow 100'
- #6 White 100'
- #7 Pink 100'
- #8 Orange 100'

525.40'

423.29'

19
47,652 SF
1.094 AC

127.11'

If plumbing is not sufficient
a pump and tank may be
required to septic drain field.

*Preliminary Design
Not a Permit

System: Gravity to D-Box
Lines: 1-4 (400')
0.3 LTAR
15" Trench Bottom
Accepted Status System
Repair: Gravity to D-Box
Lines: 5-8 (400')
0.3 LTAR
15" Trench Bottom
Accepted Status System



Adams
Soil Consulting
919-414-6761
Job #699