DAVID MILLER, PE

6300 Creedmoor Rd, STE 170#363 Raleigh, NC 27612 (919) 422-8932 (Office); DAVE@DMA-PA.COM

April 25, 2021

Kennith Cummings, LLC

E mailed to: <u>klcmgc@charter.net</u> Kennith Cummings Cell:910-984-6765

> RE: Engineering - Foundation Analysis 7333 Overhills Road ;Spring Lake, NC Project No.:21DDM-0425C

To whom it may concern:

The undersigned arrived on-site 4-25-21 to observe, probe and perform Dynamic Cone Penetrometer (DCP) testing in general accordance with the American Standard Testing Methods (ASTM) special publication 399 and perform Standard Density Testing on the exposed foundation and slab sub grade fill soils at the above referenced site. Based on the observations the tannish grey silty sandy fill soils were adequate for support of the planned loading conditions and 95% compact.

Sincerely,

David Miller, PE

DEM/21DDM-0425C

