

DAVID MILLER, PE

6300 Creedmoor Rd, STE 170#363

Raleigh, NC 27612

(919) 422-8932 (Office); DAVE@DMA-PA.COM

December 15 ,2020

Kennith Cummings, LLC

E mailed to: klemgc@charter.net

Kennith Cummings

Cell:910-984-6765

RE: Engineering - Foundation Analysis
7329 Overhills Road ;Spring Lake, NC
Project No.:20DDM-1211A

To whom it may concern:

Representatives of the undersigned's arrived on-site 12-11-20 to observe, probe and perform Dynamic Cone Penetrometer (DCP) testing in general accordance with the American Standard Testing Methods (ASTM) special publication 399 and perform Standard Density Testing on the exposed foundation and slab sub grade fill soils at the above referenced site. Based on the observations the tannish silty sandy fill soils were adequate for support of the planned loading conditions and 95% compact.

Sincerely,

David Miller, PE

DEM/20DDM-1211A

