

Revised

Harnett County Department of Public Health Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Adams Homes PROPERTY LOCATION: 11 Spring Flowers Dr, Cameron
 SUBDIVISION Carolina Seasons LOT # 10
 NEW REPAIR EXPANSION
 Type of Structure: 39'x39' SFD
 Proposed Wastewater System Type: Pump to 25% reduction
 Projected Daily flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet
 Permit conditions: System will require a french/interceptor drain to be installed above the start of the drainfield to divert storm water from upslope of line
 Permit valid for: Five years No expiration

Authorized State Agent: [Signature] Date: 3-3-22 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Adams Homes PROPERTY LOCATION: 11 Spring Flowers Dr, Cameron
 SUBDIVISION Carolina Seasons LOT # 10
 Facility Type: 39'x39' SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pump to 25% reduction (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable) Pump to 25% reduction (Repair)

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons
 Pump Tank Size 1000 gallons
 Number of trenches 1
 Exact length of each trench 225 feet
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18-26 inches
 (Trench bottoms shall be level to +/- 1/4" in all directions)
 Trench Spacing: 9 Feet on Center
 Soil Cover: 6 inches
 (Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM
 Aggregate Depth: _____ inches below pipe
 _____ inches above pipe
 _____ inches total
 Conditions: System will require a french/interceptor drain to be installed above the start of the drainfield to divert storm water from upslope of line

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____
 This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH


Authorized State Agent: [Signature] Date: 3-3-22
 Construction Authorization Expiration Date: 3-3-27

Harnett County Department of Public Health Site Sketch

Property Location: 11 Spring Flowers Dr

Issued To: Adams Homes Subdivision Carolina Seasons Lot # 10

Authorized State Agent: *[Signature]* RETH Date: 03-03-22



* Bring Supply Line up the property line with 5' of separation of the property line.

* Set Dbox 10' off the property line.

* Bring Curtain Down property line to pull lateral ground water away from the Drain Field.

↳ Must be 10' Above the Drain Field
+ 15' off the side of the Drain Field