Client:	Southern Touch Homes	Date:	8/13/2020
Project:		Input by:	Curtis Quick
Address:		Job Name:	The Lauren III Beams
		Project #:	

GDH Kerto-S LVL 1.750" X 16.000" 2-Ply - PASSED

Level: Level



Member Information

Type:	Girder	Application:	Floor
Plies:	2	Design Method:	ASD
Moisture Condition:	Dry	Building Code:	IBC 2012
Deflection LL:	480	Load Sharing:	No
Deflection TL:	360	Deck:	Not Checked
Importance:	Normal		
Temperature:	Temp <= 100°F		

Reactions UNPATTERNED lb (Uplift)

Brg	Live	Dead	Snow	Wind	Const
1	0	1840	1723	0	0
2	0	1840	1723	0	0

Bearings

Bearing	Length	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF	3.500"	68%	1840 / 1723	3564	L	D+S
2 - SPF	3.500"	68%	1840 / 1723	3564	L	D+S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	16009 ft-lb	9'5"	39750 ft-lb	0.403 (40%)	D+S	L
Unbraced	16009 ft-lb	9'5"	16016 ft-lb	1.000 (100%)	D+S	L
Shear	2976 lb	17'3 3/8"	13739 lb	0.217 (22%)	D+S	L
LL Defl inch	0.213 (L/1035)	9'5 1/16"	0.460 (L/480)	0.460 (46%)	S	L
TL Defl inch	0.441 (L/501)	9'5 1/16"	0.613 (L/360)	0.720 (72%)	D+S	L

Design Notes

1 Fasten all plies using 3 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
2 Refer to last page of calculations for fasteners required for specified loads.
3 Girders are designed to be supported on the bottom edge only.
4 Top loads must be supported equally by all plies.
5 Top must be laterally braced at a maximum of 7'4 1/2" o.c.
6 Bottom braced at bearings.
7 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	183 PLF	0 PLF	183 PLF	0 PLF	0 PLF	"A" Trusses
	Self Weight				12 PLF					

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation
6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info

Metsä Wood
301 Merritt 7 Building, 2nd Floor
Norwalk, CT 06851
(800) 622-5850
www.metsawood.com/us
ICC-ES: ESR-3633

Comtech, Inc.
1001 S. Reilly Road, Suite #639
Fayetteville, NC
USA
28314
910-864-TRUS

Client:	Southern Touch Homes	Date:	8/13/2020
Project:		Input by:	Curtis Quick
Address:		Job Name:	The Lauren III Beams
		Project #:	

BM1 Kerto-S LVL 1.750" X 9.250" 2-Ply - PASSED

Level: Level





Member Information

Type:	Girder	Application:	Floor
Plies:	2	Design Method:	ASD
Moisture Condition:	Dry	Building Code:	IBC 2012
Deflection LL:	480	Load Sharing:	No
Deflection TL:	360	Deck:	Not Checked
Importance:	Normal		
Temperature:	Temp <= 100°F		

Reactions UNPATTERNED lb (Uplift)

Brg	Live	Dead	Snow	Wind	Const
1	0	1930	1908	0	0
2	0	1930	1908	0	0

Bearings

Bearing	Length	Cap.	React D/L lb	Total	Ld. Case	Ld. Comb.
1 - SPF	3.500"	74%	1930 / 1908	3838	L	D+S
2 - SPF	3.500"	74%	1930 / 1908	3838	L	D+S

Analysis Results

Analysis	Actual	Location	Allowed	Capacity	Comb.	Case
Moment	4911 ft-lb	3'	14423 ft-lb	0.340 (34%)	D+S	L
Unbraced	4911 ft-lb	3'	11027 ft-lb	0.445 (45%)	D+S	L
Shear	2558 lb	5'	7943 lb	0.322 (32%)	D+S	L
LL Defl inch	0.038 (L/1754)	3'	0.139 (L/480)	0.270 (27%)	S	L
TL Defl inch	0.076 (L/872)	3'	0.185 (L/360)	0.410 (41%)	D+S	L

Design Notes

1 Fasten all plies using 2 rows of 10d Box nails (.128x3") at 12" o.c. Maximum end distance not to exceed 6".
2 Refer to last page of calculations for fasteners required for specified loads.
3 Girders are designed to be supported on the bottom edge only.
4 Top loads must be supported equally by all plies.
5 Top braced at bearings.
6 Bottom braced at bearings.
7 Lateral slenderness ratio based on single ply width.

ID	Load Type	Location	Trib Width	Side	Dead 0.9	Live 1	Snow 1.15	Wind 1.6	Const. 1.25	Comments
1	Uniform			Top	636 PLF	0 PLF	636 PLF	0 PLF	0 PLF	A2
	Self Weight				7 PLF					

Notes

Calculated Structured Designs is responsible only of the structural adequacy of this component based on the design criteria and loadings shown. It is the responsibility of the customer and/or the contractor to ensure the component suitability of the intended application, and to verify the dimensions and loads.

Lumber

1. Dry service conditions, unless noted otherwise
2. LVL not to be treated with fire retardant or corrosive chemicals

Handling & Installation

1. LVL beams must not be cut or drilled
2. Refer to manufacturer's product information regarding installation requirements, multi-ply fastening details, beam strength values, and code approvals
3. Damaged Beams must not be used
4. Design assumes top edge is laterally restrained
5. Provide lateral support at bearing points to avoid lateral displacement and rotation
6. For flat roofs provide proper drainage to prevent ponding

This design is valid until 2/26/2023

Manufacturer Info

Metsä Wood
301 Merritt 7 Building, 2nd Floor
Norwalk, CT 06851
(800) 622-5850
www.metsawood.com/us
ICC-ES: ESR-3633

Comtech, Inc.
1001 S. Reilly Road, Suite #639
Fayetteville, NC
USA
28314
910-864-TRUS