

North Carolina 2018 - R402.1.5 Total UA



Property
 , NC 27546
 Model: Camden

Organization
 Southern Energy Manager
 Justin Smith

Inspection Status
 Results are projected

Template - A & G - Camden plan
 slab CZ 4 - ecoSelect
 Camden plan slab

Builder
 A & G

This report is based on a proposed design and does not confirm field enforcement of design elements.

Building UA

Elements	NC Reference	As Designed
Ceilings	43.6	39.8
Above-Grade Walls	172.1	135.0
Windows, Doors and Skylights	96.2	90.5
Slab Floor:	67.1	86.9
Framed Floors	18.9	18.4
Foundation Walls	0.0	0.0
Rim Joists	7.9	6.4
Overall UA (Design must be equal or lower):	405.8	377.0

Requirements

✓	402.1.5	Total UA alternative compliance passes by 7.1%.
✓	402.3.2 Glazed Fenestration SHGC	Average SHGC: 0.27 Max SHGC: 0.30
✓	R402.4.2.2	Air Leakage Testing Air sealing is 4.80 ACH at 50 Pa. It must not exceed 5.00 ACH at 50 Pa.
✓	R402.5	Area-weighted average fenestration SHGC
✓	R402.5	Area-weighted average fenestration U-Factor
✓	R404.1	Lighting Equipment Efficiency
✓	Mandatory Checklist	Mandatory code requirements that are not checked by Ekotrope must be met.
✓	R403.3	Duct Insulation
✓	403.3.3	Duct Testing

Design exceeds requirements for North Carolina 2018 Prescriptive compliance by 7.1%.

Name: Justin Smith
 Organization: Southern Energy Management

Signature: Justin Smith
 Digitally signed: 9/11/20 at 1:07 PM

Ekotrope RATER - Version 3.2.3.2522

North Carolina 2018 Prescriptive compliance results calculated using Ekotrope RATER's energy and code compliance algorithm, including appropriate amendments. Ekotrope RATER is a RESNET Accredited HERS Rating Tool. All results are based on data entered by Ekotrope users. Ekotrope disclaims all liability for the information shown on this report.

Building Summary



SOUTHERN ENERGY
MANAGEMENT
ENERGY EFFICIENCY & SOLAR POWER

Property
. NC 27546
Model: Camden

Organization
Southern Energy Management
Justin Smith

Inspection Status
Results are projected

Template - A & G - Camden plan slab CZ 4 -
ecoSelect
Camden plan slab

Builder
A & G

General Building Information

Number Of Bedrooms	3
Number Of Floors	2
Conditioned Floor Area [sq. ft.]	2,300
Has Electric Vehicle Ready Space	No
Unconditioned, attached garage?	Yes
Conditioned Volume [cu. ft.]	20,778
Total Units in Building	1
Residence Type	Single family detached
Floor Number	-
Model	Camden
Community	
Climate Zone	4A

Foundation Wall

None Present

Foundation Wall Library List

None Present

Slab

Name	Library Type	Perimeter	Floor Grade	Carpet R	Exposed Masonry Area	Surface Area	Location	Enclosing
slab	Uninsulated	142	On Grade	1	0	949.0 ft²	Exposed Exterior	Conditioned Space

Slab Library List

Name	Wall Construction Type	Slab Completely Insulated?	Underslab Insulation Width [ft]	Perimeter Insulation Depth [ft]	Perimeter Insulation R Value	Thermal Break	Effective R-value
Uninsulated	Wood Frame / Other	No	0	0	0	No	0.00

Building Summary



Property
 , NC 27546
 Model: Camden

Organization
 Southern Energy Management
 Justin Smith

Inspection Status
 Results are projected

Template - A & G - Camden plan slab CZ 4 -
 ecoSelect
 Camden plan slab

Builder
 A & G

Framed Floor

Name	Library Type	Carpet R	Floor Grade	Surface Area	Location
over ambient	R-19, 16"OC G1 Carpet	0	Above Grade	11.0 ft ²	Exposed Exterior
over garage	R-19, 16"OC G1 Carpet	0	Above Grade	391.0 ft ²	Unconditioned, attached garage

Framed Floor Library List

Name	Effective R-value
R-19, 16"OC G1 Carpet	21.798

Rim Joist

Name	Library Type	Surface Area	Location
1st floor ambient	R 19 G1, 16"OC	108.0 ft ²	Exposed Exterior
1st floor garage	R 19 G1, 16"OC	34.0 ft ²	Unconditioned, attached garage

Rim Joist Library List

Name	Effective Insulation R-value
R 19 G1, 16"OC	17.30

Wall

Name	Library Type	Surface Color	Surface Area	Location
1st floor ambient	R 19 Adv. Framing G2 16" O.C	Medium	972.0 ft ²	Exposed Exterior
1st floor garage	R 19 Adv. Framing G2 16" O.C	Medium	306.0 ft ²	Unconditioned, attached garage
2nd floor ambient	R 19 Adv. Framing G2 16" O.C	Medium	1,232.0 ft ²	Exposed Exterior

Building Summary



Property
 , NC 27546
 Model: Camden

Organization
 Southern Energy Management
 Justin Smith

Inspection Status
 Results are projected

Template - A & G - Camden plan slab CZ 4 -
 ecoSelect
 Camden plan slab

Builder
 A & G

Wall Library List

Name	Effective R-value
R 19 Adv. Framing G2 16" O.C	16.552

Glazing

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Is Operable	Overhang Depth	Overhang Ft To Top	Overhang Ft To Bottom	Orientation	Surface Area
front 2nd unshaded	35/27	2nd floor ambient		Yes	0	0	0	East	55.1 ft ²
front unshaded	35/27	1st floor ambient		Yes	0	0	0	East	31.5 ft ²
left 2nd unshaded	35/27	2nd floor ambient		Yes	0	0	0	South	13.8 ft ²
rear 2nd unshaded	35/27	2nd floor ambient		Yes	0	0	0	West	41.3 ft ²
rear unshaded	35/27	1st floor ambient		Yes	0	0	0	West	67.6 ft ²
right unshaded	35/27	1st floor ambient		Yes	0	0	0	North	27.5 ft ²

Glazing Library List

Name	Shgc	U-factor
35/27	0.27	0.350

Skylight

None Present

Skylight Library List

None Present

Building Summary



Property
 , NC 27546
 Model: Camden

Organization
 Southern Energy Management
 Justin Smith

Inspection Status
 Results are projected

Template - A & G - Camden plan slab CZ 4 -
 ecoSelect
 Camden plan slab

Builder
 A & G

Opaque Door

Name	Library Type	Wall Assignment	Foundation Wall Assignment	Emittance	Solar Absorptance	Surface Color	Surface Area	Location
front door	Fiberglass R-5	1st floor ambient		0.9	0.75	Medium	20.0 ft ²	Exposed Exterior
garage door	Fiberglass R-5	1st floor garage		0.9	0.75	Medium	18.0 ft ²	Exposed Exterior

Opaque Door Library List

Name	Effective U-factor
Fiberglass R-5	0.200

Roof Insulation

Name	Library Type	Attic Exterior Area [ft ²]	Clay or Concrete	Roof Tiles	Surface Color	Surface Area	Location
Attic	R-38 Attic BLOWN FG G1 2x10 24"OC w/ Radiant Barrier	1,664.04		No	Dark	1,132.0 ft ²	Attic
Attic vaulted	R-38 Attic VAULTED FG G1 2x12 w/ Radiant Barrier	321.93		No	Dark	321.9 ft ²	Vaulted Roof

Roof Insulation Library List

Name	Has Radiant Barrier	Effective R-value
R-38 Attic BLOWN FG G1 2x10 24"OC w/ Radiant Barrier	Yes	37.246
R-38 Attic VAULTED FG G1 2x12 w/ Radiant Barrier	Yes	34.059

Whole House Infiltration

Infiltration	Measurement Type	Shelter Class
1662 CFM at 50 Pa	Blower-door tested	4

Building Summary



Property
 , NC 27546
 Model: Camden

Organization
 Southern Energy Management
 Justin Smith

Inspection Status
 Results are projected

Template - A & G - Camden plan slab CZ 4 -
 ecoSelect
 Camden plan slab

Builder
 A & G

Mechanical Ventilation

None Present

Lighting

% Interior Fluorescent Lighting	% Interior LED Lighting	% Exterior Fluorescent Lighting	% Exterior LED Lighting	% Garage Fluorescent Lighting	% Garage LED Lighting
0	100	0	0	0	0

Onsite Generation

None Present

Onsite Generation Library List

None Present

Solar Generation

None Present

Solar Generation Library List

None Present

Conditioning Equipment

Name	Library Type	Heating Percent Load	Cooling Percent Load	Hot Water Percent Load	Location
Water Heating	Z 50 gal. 0.91EF elec	0%	0%	100%	Unspecified
whole house heat pump	z 36k 14 seer 8.2hspf	100%	100%	0%	Unspecified

Building Summary



Property
NC 27546
Model: Camden

Organization
Southern Energy Management
Justin Smith

Inspection Status
Results are projected

Template - A & G - Camden plan slab CZ 4 -
ecoSelect
Camden plan slab

Builder
A & G

Equipment Type: Z 50 gal. 0.91EF elec

Fuel Type	Electric
Distribution Type	Hydronic Delivery (Radiant)
Hot Water Efficiency	0.91 Energy Factor
Tank Capacity (gal.)	50
Hot Water Capacity [kBtu/h]	40
Recovery Efficiency	0.98

Equipment Type: z 36k 14 seer 8.2hspf

Fuel Type	Electric
Distribution Type	Forced Air
Motor Type	PSC (Single Speed)
Heating Efficiency	8.2 HSPF
Heating Capacity [kBtu/h]	36
Use default Supplemental Heat	Yes
Cooling Efficiency	14 SEER
Cooling Capacity [kBtu/h]	36

Building Summary



Property
 , NC 27546
 Model: Camden

Organization
 Southern Energy Management
 Justin Smith

Inspection Status
 Results are projected

Template - A & G - Camden plan slab CZ 4 -
 ecoSelect
 Camden plan slab

Builder
 A & G

Distribution System

Distribution Type	Forced Air
Heating Equipment	whole house heat pump
Cooling Equipment	whole house heat pump
Sq. Feet Served	2300
# Return Grilles	3
Supply Duct R Value	8
Return Duct R Value	8
Supply Duct Area [ft ²]	621
Return Duct Area [ft ²]	345
Leakage to Outdoors	92 CFM @ 25Pa (4 / 100 s.f.)
Total Leakage	92 CFM25
Total Leakage Duct Test Conditions	Post-Construction
Use Default Flow Rate	Yes
Duct 1	
Duct Location	Attic (well vented, radiant barrier)
Percent Supply Area	70
Percent Return Area	70
Duct 2	
Duct Location	Conditioned Space
Percent Supply Area	30
Percent Return Area	30
Duct 3	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 4	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 5	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0
Duct 6	
Duct Location	Conditioned Space
Percent Supply Area	0
Percent Return Area	0

Ceiling Fan

Has Ceiling Fan	Yes
Cfm Per Watt	100

Water Distribution

Water Fixture Type	Standard
Use Default Hot Water Pipe Length	No
Hot Water Pipe Length [ft]	71
At Least R3 Pipe Insulation?	No
Hot Water Recirculation System?	No
Recirculation System Pipe Loop Length [ft]	10
Drain Water Heat Recovery?	No

Building Summary



Property
. NC 27546
Model: Camden

Organization
Southern Energy Management
Justin Smith

Inspection Status
Results are projected

Template - A & G - Camden plan slab CZ 4 -
ecoSelect
Camden plan slab

Builder
A & G

Clothes Dryer

Cef	2.6173913
Fuel Type	Electric
Field Utilization	Timer Controls
Is Outside Conditioned Space	No
Clothes Dryer Available	Yes
Defaults Type	HERS Reference

Clothes Washer

Label Energy Rating	153 kWh/Year
Annual Gas Cost	\$12.00
Electric Rate	\$0.11/kWh
Gas Rate	\$1.22/Therm
Capacity	3.31
Imef	2.1547
Defaults Type	Custom
Is Outside Conditioned Space	No
Clothes Washer Available	Yes

Dishwasher

Dishwasher Efficiency	270 kWh
Dishwasher Size	Standard
Is Outside Conditioned Space	No

Appliances and Controls

Programmable thermostat?	Yes
Range/Oven Fuel	Electric
Convection Oven?	No
Induction Range?	No
Range/Oven Outside Conditioned Space?	No
Refrigerator Consumption	538 kWh/Year
Refrigerator Outside Conditioned Space?	No

Notes

- updated JS 09/11/20
- uninsulated slab modeled
- wall insulation modeled to Grade 2
- confirm attic insulation and hvac specs
- ventilation modeled as none
- confirm cfl lighting %
- modeled to worst case orientation